


BID TABULATION FOR:

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
FEBRUARY 9, 2024  
LJA ENGINEERING, INC.  
C CORTEZ  
FEBRUARY 9, 2024  
0386-5050C (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) HARRIS CONSTRUCTION COMPANY, LLC	\$782,847.20
2) DACO PAVING, INC.	\$797,539.00
3) HCG LLC	\$802,092.75
4) PRECISE SERVICES INC.	\$924,318.10

CALENDAR DAYS 45/55



*Carissa M. Fabian* 2/12/24

I, CARISSA M. FABIAN, P.E., hereby certify these bid tabulations to be true and correct.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
 FEBRUARY 9, 2024  
 LJA ENGINEERING, INC.  
 C CORTEZ  
 FEBRUARY 9, 2024  
 0386-5050C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) HARRIS CONSTRUCTION COMPANY, LLC		2) DACO PAVING, INC.		3) HCG LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SECTION 5 - PAVING ITEMS (INTERNAL)									
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	4200	\$3.00	\$12,600.00	\$5.60	\$23,520.00	\$3.85	\$16,170.00
2	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	8505	\$47.75	\$406,113.75	\$46.00	\$391,230.00	\$44.90	\$381,874.50
3	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	9040	\$1.95	\$17,628.00	\$3.30	\$29,832.00	\$4.40	\$39,776.00
4	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	68	\$365.00	\$24,820.00	\$335.00	\$22,780.00	\$350.00	\$23,800.00
5	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	181	\$140.00	\$25,340.00	\$135.00	\$24,435.00	\$125.00	\$22,625.00
6	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	953	\$3.55	\$3,383.15	\$4.00	\$3,812.00	\$3.90	\$3,716.70
7	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	3746	\$3.55	\$13,298.30	\$4.00	\$14,984.00	\$3.90	\$14,609.40
8	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	28	\$15.00	\$420.00	\$4.00	\$112.00	\$44.85	\$1,255.80
9	STANDARD PAVING HEADER, COMPLETE IN PLACE	LF	56	\$10.00	\$560.00	\$16.00	\$896.00	\$18.70	\$1,047.20
10	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	7	\$19.00	\$133.00	\$18.00	\$126.00	\$16.85	\$117.95
11	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING ALL TRAFFIC BUTTONS, MARKERS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$2,300.00	\$2,300.00	\$1,465.00	\$1,465.00
12	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	4	\$850.00	\$3,400.00	\$900.00	\$3,600.00	\$765.00	\$3,060.00
13	ADA RAMPS (TYPE 7), INCLUDING TRUNCATED DOME BRICKS, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, (PER DETAIL SHEET 29), COMPLETE IN PLACE	EA	8	\$1,425.00	\$11,400.00	\$1,400.00	\$11,200.00	\$1,790.00	\$14,320.00
14	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$200.00	\$200.00	\$1.00	\$1.00	\$187.00	\$187.00
15	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,450.00	\$2,900.00	\$1,350.00	\$2,700.00	\$1,320.00	\$2,640.00
16	FULL CONSTRUCTION STAKING FOR PAVING AND APPURTENANCES ITEMS, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$9,500.00	\$9,500.00	\$9,500.00	\$9,500.00	\$9,500.00	\$9,500.00
17	AS BUILT SURVEY OF PAVING AND APPURTENANCES ITEMS SHOWING ELEVATIONS AT THE TOP OF CURB, BUILDING LINE, BACK OF LOT, SIGNIFICANT GRADE BREAKS AND EXTREME EVENT SWALES, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$6,500.00	\$6,500.00	\$6,500.00	\$6,500.00	\$6,500.00	\$6,500.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
 FEBRUARY 9, 2024  
 LJA ENGINEERING, INC.  
 C CORTEZ  
 FEBRUARY 9, 2024  
 0386-5050C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) HARRIS CONSTRUCTION COMPANY, LLC		2) DACO PAVING, INC.		3) HCG LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
18	EXTRA SURVEY TRIP FOR RESTAKING PREVIOUSLY PROVIDED CONSTRUCTION STAKES THAT WERE DESTROYED BY OTHERS (THIS ITEM DOES NOT INCLUDE RESTAKING DUE TO CONTRACTOR DESTROYING OWN CONSTRUCTION STAKING OR FAILING TO PROTECT CONSTRUCTION STAKING FROM KNOWN HAZARDS SUCH AS CONSTRUCTION TRAFFIC, ORDERING STAKING TOO FAR IN ADVANCE, OR CONTRACTOR'S OWN EQUIPMENT, ETC.)	DAY	1	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00
19	FINAL LOT AND RESERVE GRADING, INCLUDING STRIPPING AND PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, COMPLETE IN PLACE	EA	81	\$125.00	\$10,125.00	\$200.00	\$16,200.00	\$280.00	\$23,490.00
20	REGRAIDING OF EXISTING ROAD SWALES, CONTRACTOR TO ENSURE POSITIVE DRAINAGE	LF	200	\$8.00	\$1,600.00	\$4.00	\$800.00	\$12.30	\$2,460.00
<b>SECTION 5 - PAVING ITEMS (INTERNAL) SUBTOTAL:</b>					<b>\$554,421.20</b>		<b>\$566,528.00</b>		<b>\$570,614.55</b>
<b>SECTION 5 - PAVING ITEMS (TRUNK)</b>									
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	1800	\$5.00	\$9,000.00	\$5.80	\$10,080.00	\$3.85	\$6,930.00
2	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	3380	\$47.75	\$161,872.50	\$46.00	\$155,940.00	\$44.90	\$152,211.00
3	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	3630	\$2.50	\$9,075.00	\$3.30	\$11,979.00	\$4.40	\$15,972.00
4	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	28	\$365.00	\$10,220.00	\$335.00	\$9,380.00	\$350.00	\$9,800.00
5	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	73	\$140.00	\$10,220.00	\$135.00	\$9,855.00	\$125.00	\$9,125.00
6	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2110	\$3.55	\$7,480.50	\$4.00	\$8,440.00	\$3.90	\$8,229.00
7	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 8" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	28	\$25.00	\$700.00	\$4.00	\$112.00	\$44.90	\$1,257.20
8	STANDARD PAVING HEADER, COMPLETE IN PLACE	LF	28	\$15.00	\$420.00	\$16.00	\$448.00	\$19.00	\$532.00
9	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	2	\$19.00	\$38.00	\$18.00	\$36.00	\$17.00	\$34.00
10	6" PVC IRRIGATION SLEEVES SCHEDULE 40, PER DETAIL, COMPLETE IN PLACE	LF	74	\$60.00	\$4,440.00	\$55.00	\$4,070.00	\$47.00	\$3,478.00
11	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	2	\$850.00	\$1,700.00	\$900.00	\$1,800.00	\$660.00	\$1,320.00
12	ADA RAMPS (TYPE 7), INCLUDING TRUNCATED DOME BRICKS, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, (PER DETAIL SHEET 29), COMPLETE IN PLACE	EA	2	\$1,425.00	\$2,850.00	\$1,400.00	\$2,800.00	\$1,790.00	\$3,580.00
13	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$200.00	\$200.00	\$1.00	\$1.00	\$180.00	\$180.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
 FEBRUARY 9, 2024  
 LJA ENGINEERING, INC.  
 C CORTEZ  
 FEBRUARY 9, 2024  
 0386-5050C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) HARRIS CONSTRUCTION COMPANY, LLC		2) DACO PAVING, INC.		3) HCG LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
14	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$1,450.00	\$1,450.00	\$1,350.00	\$1,350.00	\$1,335.00	\$1,335.00
15	FINAL RESERVE GRADING, INCLUDING STRIPPING AND PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, COMPLETE IN PLACE	EA	2	\$1,850.00	\$3,700.00	\$1,200.00	\$2,400.00	\$4,900.00	\$9,800.00
<b>SECTION 5 - PAVING ITEMS (TRUNK) SUBTOTAL:</b>					<b>\$223,376.00</b>		<b>\$218,691.00</b>		<b>\$223,793.20</b>
<b>SECTION 5 - STORM WATER POLLUTION PREVENTION ITEMS</b>									
1	STAGE II INLET PROTECTION BARRIER (4 GRAVEL BAGS PER INLET) FOR PROPOSED AND EXISTING INLETS	EA	18	\$50.00	\$900.00	\$100.00	\$1,800.00	\$85.00	\$1,530.00
2	STORMWATER POLLUTION PREVENTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00	\$6,000.00	\$6,000.00	\$1,010.00	\$1,010.00
3	INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	100	\$1.50	\$150.00	\$1.70	\$170.00	\$2.00	\$200.00
4	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$500.00	\$500.00	\$1,245.00	\$1,245.00
5	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT AND REGRADE THE AREA TO MATCH FINISHED GRADE, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$950.00	\$950.00	\$1,900.00	\$1,900.00
6	30 CY TRASH CONTAINER, CONTRACTOR IS TO REMOVE ALL EXISTING TRASH FROM PROPERTY, ITEM INCLUDES AN ONSITE 30 CY CONTAINER, EMPTYING THE CONTAINER AND RETURNING IT TO THE SITE, AND REMOVAL OF THE CONTAINER UPON COMPLETION, COMPLETE IN PLACE	EA	1	\$800.00	\$800.00	\$900.00	\$900.00	\$800.00	\$800.00
<b>SECTION 5 - STORM WATER POLLUTION PREVENTION ITEMS SUBTOTAL:</b>					<b>\$4,050.00</b>		<b>\$10,320.00</b>		<b>\$6,685.00</b>
<b>SECTION 5 - MISCELLANEOUS ITEMS</b>									
1	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	50	\$20.00	\$1,000.00	\$40.00	\$2,000.00	\$20.00	\$1,000.00
<b>SECTION 5 - MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$1,000.00</b>		<b>\$2,000.00</b>		<b>\$1,000.00</b>
<b>BIDDING SUMMARY</b>									
SUBTOTAL SECTION 5 - PAVING ITEMS (INTERNAL)					\$554,421.20		\$566,528.00		\$570,614.55
SUBTOTAL SECTION 5 - PAVING ITEMS (TRUNK)					\$223,376.00		\$218,691.00		\$223,793.20
SUBTOTAL SECTION 5 - STORM WATER POLLUTION PREVENTION ITEMS					\$4,050.00		\$10,320.00		\$6,685.00
SUBTOTAL SECTION 5 - MISCELLANEOUS ITEMS					\$1,000.00		\$2,000.00		\$1,000.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$762,847.20</b>		<b>\$797,539.00</b>		<b>\$802,092.75</b>

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
 FEBRUARY 9, 2024  
 LJA ENGINEERING, INC.  
 C CORTEZ  
 FEBRUARY 9, 2024  
 0386-5050C (9.2)

4) PRECISE SERVICES INC.					
ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>SECTION 5 - PAVING ITEMS (INTERNAL)</b>					
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	4200	\$5.65	\$23,730.00
2	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	8505	\$53.75	\$457,143.75
3	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	9040	\$5.20	\$47,008.00
4	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	88	\$315.00	\$21,420.00
5	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	181	\$135.00	\$24,435.00
6	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	953	\$4.65	\$4,431.45
7	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	3746	\$4.65	\$17,418.90
8	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	28	\$40.00	\$1,120.00
9	STANDARD PAVING HEADER, COMPLETE IN PLACE	LF	56	\$21.50	\$1,204.00
10	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	7	\$20.00	\$140.00
11	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING ALL TRAFFIC BUTTONS, MARKERS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$1,600.00	\$1,600.00
12	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	4	\$825.00	\$3,300.00
13	ADA RAMPS (TYPE 7), INCLUDING TRUNCATED DOME BRICKS, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, (PER DETAIL SHEET 28), COMPLETE IN PLACE	EA	8	\$1,950.00	\$15,800.00
14	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$100.00	\$100.00
15	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,450.00	\$2,900.00
16	FULL CONSTRUCTION STAKING FOR PAVING AND APPURTENANCES ITEMS, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$9,500.00	\$9,500.00
17	AS BUILT SURVEY OF PAVING AND APPURTENANCES ITEMS SHOWING ELEVATIONS AT THE TOP OF CURB, BUILDING LINE, BACK OF LOT, SIGNIFICANT GRADE BREAKS AND EXTREME EVENT SWALES, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$6,500.00	\$6,500.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
FEBRUARY 9, 2024  
LJA ENGINEERING, INC.  
C CORTEZ  
FEBRUARY 9, 2024  
0386-5050C (9.2)

**4) PRECISE SERVICES INC.**

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
18	EXTRA SURVEY TRIP FOR RESTAKING PREVIOUSLY PROVIDED CONSTRUCTION STAKES THAT WERE DESTROYED BY OTHERS (THIS ITEM DOES NOT INCLUDE RESTAKING DUE TO CONTRACTOR DESTROYING OWN CONSTRUCTION STAKING OR FAILING TO PROTECT CONSTRUCTION STAKING FROM KNOWN HAZARDS SUCH AS CONSTRUCTION TRAFFIC, ORDERING STAKING TOO FAR IN ADVANCE, OR CONTRACTOR'S OWN EQUIPMENT, ETC.)	DAY	1	\$2,000.00	\$2,000.00
19	FINAL LOT AND RESERVE GRADING, INCLUDING STRIPPING AND PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, COMPLETE IN PLACE	EA	81	\$240.00	\$19,440.00
20	REGRADING OF EXISTING ROAD SWALES, CONTRACTOR TO ENSURE POSITIVE DRAINAGE	LF	200	\$11.00	\$2,200.00

**SECTION 5 - PAVING ITEMS (INTERNAL) SUBTOTAL:****\$661,191.10****SECTION 5 - PAVING ITEMS (TRUNK)**

1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	1800	\$5.65	\$10,170.00
2	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	3390	\$53.75	\$182,212.50
3	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	3630	\$5.20	\$18,876.00
4	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	28	\$315.00	\$8,820.00
5	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	73	\$135.00	\$9,855.00
6	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2110	\$4.65	\$9,811.50
7	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	28	\$40.00	\$1,120.00
8	STANDARD PAVING HEADER, COMPLETE IN PLACE	LF	28	\$21.50	\$602.00
9	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	2	\$20.00	\$40.00
10	6" PVC IRRIGATION SLEEVES SCHEDULE 40, PER DETAIL, COMPLETE IN PLACE	LF	74	\$55.00	\$4,070.00
11	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	2	\$825.00	\$1,650.00
12	ADA RAMPS (TYPE 7), INCLUDING TRUNCATED DOME BRICKS, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, (PER DETAIL SHEET 29), COMPLETE IN PLACE	EA	2	\$1,950.00	\$3,900.00
13	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$100.00	\$100.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
TO SERVE GRAND PRAIRIE HIGHLANDS SECTION FIVE  
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
FEBRUARY 9, 2024  
LJA ENGINEERING, INC.  
C CORTEZ  
FEBRUARY 9, 2024  
0386-5050C (9.2)

**4) PRECISE SERVICES INC.**

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
14	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$1,450.00	\$1,450.00
15	FINAL RESERVE GRADING, INCLUDING STRIPPING AND PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, COMPLETE IN PLACE	EA	2	\$1,400.00	\$2,800.00

**SECTION 5 - PAVING ITEMS (TRUNK) SUBTOTAL:****\$255,477.00****SECTION 5 - STORM WATER POLLUTION PREVENTION ITEMS**

1	STAGE II INLET PROTECTION BARRIER (4 GRAVEL BAGS PER INLET) FOR PROPOSED AND EXISTING INLETS	EA	18	\$150.00	\$2,700.00
2	STORMWATER POLLUTION PREVENTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE	LS	1	\$2,000.00	\$2,000.00
3	INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	100	\$1.50	\$150.00
4	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00
5	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT AND REGRADE THE AREA TO MATCH FINISHED GRADE, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$500.00	\$500.00
6	30 CY TRASH CONTAINER, CONTRACTOR IS TO REMOVE ALL EXISTING TRASH FROM PROPERTY, ITEM INCLUDES AN ONSITE 30 CY CONTAINER, EMPTYING THE CONTAINER AND RETURNING IT TO THE SITE, AND REMOVAL OF THE CONTAINER UPON COMPLETION, COMPLETE IN PLACE	EA	1	\$800.00	\$800.00

**SECTION 5 - STORM WATER POLLUTION PREVENTION ITEMS SUBTOTAL:****\$6,650.00****SECTION 5 - MISCELLANEOUS ITEMS**

1	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	50	\$20.00	\$1,000.00
---	--	----	----	---------	------------

**SECTION 5 - MISCELLANEOUS ITEMS SUBTOTAL:****\$1,000.00****BIDDING SUMMARY**

SUBTOTAL SECTION 5 - PAVING ITEMS (INTERNAL)	\$661,191.10
SUBTOTAL SECTION 5 - PAVING ITEMS (TRUNK)	\$255,477.00
SUBTOTAL SECTION 5 - STORM WATER POLLUTION PREVENTION ITEMS	\$6,650.00
SUBTOTAL SECTION 5 - MISCELLANEOUS ITEMS	\$1,000.00
<b>TOTAL AMOUNT BASE BID</b>	<b>\$924,318.10</b>