


BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
JULY 19, 2024
LJA ENGINEERING, INC.
AVIGAIL AMIGLEO
JULY 22, 2024
0386-5090C (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) DURWOOD GREENE CONSTRUCTION CO.	\$997,808.25
2) ALLGOOD CONSTRUCTION CO., INC.	\$1,006,353.25
3) HCG	\$1,007,016.40
4) DACO PAVING, INC.	\$1,035,062.47
5) ICON GC LLC	\$1,091,000.00
6) R CONSTRUCTION CIVIL, LLC	\$1,120,953.00

CALENDAR DAYS 45/55



Carissa M. Fabian 7/24/24

I, Carissa Fabian, PE, hereby certify these bid tabulations to be true and correct.

LJA Engineering, Inc.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 JULY 19, 2024
 LJA ENGINEERING, INC.
 AVIGAIL AMIGLEO
 JULY 22, 2024
 0386-5090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DURWOOD GREENE CONSTRUCTION CO.		2) ALLGOOD CONSTRUCTION CO., INC.		3) HCG	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SECTION NINE - PAVING ITEMS (INTERNAL)									
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5673	\$4.00	\$22,692.00	\$4.38	\$24,847.74	\$4.00	\$22,692.00
2	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	11191	\$48.00	\$537,168.00	\$48.75	\$545,561.25	\$46.70	\$522,619.70
3	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	11950	\$3.50	\$41,825.00	\$4.38	\$52,341.00	\$4.70	\$56,165.00
4	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	90	\$370.00	\$33,300.00	\$385.50	\$34,695.00	\$358.00	\$32,220.00
5	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	239	\$132.00	\$31,548.00	\$136.75	\$32,683.25	\$132.00	\$31,548.00
6	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1174	\$3.75	\$4,402.50	\$3.30	\$3,874.20	\$3.85	\$4,519.90
7	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	5558	\$3.75	\$20,842.50	\$3.30	\$18,341.40	\$3.85	\$21,398.30
8	STANDARD PAVING HEADER, COMPLETE IN PLACE	LF	56	\$10.00	\$560.00	\$2.20	\$123.20	\$33.00	\$1,848.00
9	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	9	\$20.00	\$180.00	\$13.75	\$123.75	\$17.25	\$155.25
10	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING ALL TRAFFIC BUTTONS, MARKERS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$2,400.00	\$2,400.00	\$495.00	\$495.00	\$2,100.00	\$2,100.00
11	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	5	\$800.00	\$4,000.00	\$495.00	\$2,475.00	\$750.00	\$3,750.00
12	ADA RAMPS (TYPE 7), INCLUDING TRUNCATED DOME BRICKS, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, (PER DETAIL SHEET 32), COMPLETE IN PLACE	EA	14	\$1,600.00	\$22,400.00	\$902.00	\$12,628.00	\$1,830.00	\$25,620.00
13	10' X 8' X 8" CONCRETE MAILBOX PAD WITH #3 BARS AT 15" O.C.E.W. OR EQUAL, ON 2" BANK SAND BEDDING (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,200.00	\$1,200.00	\$2,090.00	\$2,090.00	\$1,950.00	\$1,950.00
14	13' X 8' X 8" CONCRETE MAILBOX PAD WITH #3 BARS AT 15" O.C.E.W. OR EQUAL, ON 2" BANK SAND BEDDING (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$2,090.00	\$2,090.00	\$1,990.00	\$1,990.00
15	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	3	\$1,500.00	\$4,500.00	\$1,100.00	\$3,300.00	\$1,350.00	\$4,050.00
16	FULL CONSTRUCTION STAKING FOR PAVING AND APPURTENANCES ITEMS, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$14,100.00	\$14,100.00	\$14,100.00	\$14,100.00	\$14,100.00	\$14,100.00
17	AS BUILT SURVEY OF PAVING AND APPURTENANCES ITEMS SHOWING ELEVATIONS AT THE TOP OF CURB, BUILDING LINE, BACK OF LOT, SIGNIFICANT GRADE BREAKS AND EXTREME EVENT SWALES, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$4,900.00	\$4,900.00	\$4,900.00	\$4,900.00	\$4,900.00	\$4,900.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 JULY 19, 2024
 LJA ENGINEERING, INC.
 AVIGAIL AMIGLEO
 JULY 22, 2024
 0386-5090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DURWOOD GREENE CONSTRUCTION CO.		2) ALLGOOD CONSTRUCTION CO., INC.		3) HCG	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
18	EXTRA SURVEY TRIP FOR RESTAKING PREVIOUSLY PROVIDED CONSTRUCTION STAKES THAT WERE DESTROYED BY OTHERS (THIS ITEM DOES NOT INCLUDE RESTAKING DUE TO CONTRACTOR DESTROYING OWN CONSTRUCTION STAKING OR FAILING TO PROTECT CONSTRUCTION STAKING FROM KNOWN HAZARDS SUCH AS CONSTRUCTION TRAFFIC, ORDERING STAKING TOO FAR IN ADVANCE, OR CONTRACTOR'S OWN EQUIPMENT, ETC.)	DAY	1	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00
19	FINAL LOT AND RESERVE GRADING, INCLUDING STRIPPING AND PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, COMPLETE IN PLACE	EA	101	\$200.00	\$20,200.00	\$172.50	\$17,422.50	\$300.00	\$30,300.00
20	REGRAIDING OF EXISTING ROAD SWALES, CONTRACTOR TO ENSURE POSITIVE DRAINAGE, COMPLETE IN PLACE	LF	200	\$5.00	\$1,000.00	\$7.48	\$1,496.00	\$18.35	\$3,670.00
SECTION NINE - PAVING ITEMS (INTERNAL) SUBTOTAL:					\$770,718.00	\$775,587.29		\$787,596.15	
SECTION NINE - PAVING ITEMS (TRUNK)									
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	423	\$4.00	\$1,692.00	\$4.38	\$1,852.74	\$4.00	\$1,692.00
2	ROADWAY EXCAVATION TO BE USED FOR SECTION 15 FILL (MAX HAUL DISTANCE 2,000 LF OFF ROAD EACH WAY), TO INCLUDE STRIPPING, PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAX 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE.	CY	2250	\$6.00	\$13,500.00	\$6.88	\$15,480.00	\$2.00	\$4,500.00
3	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	3328	\$48.00	\$159,744.00	\$48.75	\$162,240.00	\$46.70	\$155,417.60
4	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	3554	\$3.50	\$12,439.00	\$4.38	\$15,566.52	\$4.65	\$16,526.10
5	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	27	\$370.00	\$9,990.00	\$385.50	\$10,408.50	\$358.00	\$9,666.00
6	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	72	\$132.00	\$9,504.00	\$136.75	\$9,846.00	\$132.00	\$9,504.00
7	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	56	\$10.00	\$560.00	\$3.30	\$184.80	\$32.50	\$1,820.00
8	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2203	\$3.75	\$8,261.25	\$3.30	\$7,269.90	\$3.85	\$8,481.55
9	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	4	\$20.00	\$80.00	\$13.75	\$55.00	\$17.25	\$69.00
10	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$10.00	\$20.00	\$165.00	\$330.00	\$200.00	\$400.00
11	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	3	\$800.00	\$2,400.00	\$495.00	\$1,485.00	\$800.00	\$2,400.00
SECTION NINE - PAVING ITEMS (TRUNK) SUBTOTAL:					\$218,190.25	\$224,718.46		\$210,476.25	
SECTION NINE - STORM WATER POLLUTION PREVENTION PLAN ITEMS									
1	STAGE II INLET PROTECTION BARRIER (4 GRAVEL BAGS PER INLET) FOR PROPOSED AND EXISTING INLETS	EA	29	\$50.00	\$1,450.00	\$52.50	\$1,522.50	\$86.00	\$2,494.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 JULY 19, 2024
 LJA ENGINEERING, INC.
 AVIGAIL AMIGLEO
 JULY 22, 2024
 0386-5090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DURWOOD GREENE CONSTRUCTION CO.		2) ALLGOOD CONSTRUCTION CO., INC.		3) HCG	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
2	STORMWATER POLLUTION PREVENTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$1,575.00	\$1,575.00	\$1,000.00	\$1,000.00
3	INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	100	\$1.50	\$150.00	\$1.50	\$150.00	\$1.80	\$180.00
4	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$500.00	\$500.00	\$1,150.00	\$1,150.00
5	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT AND REGRADE THE AREA TO MATCH FINISHED GRADE, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$500.00	\$500.00	\$1,750.00	\$1,750.00
6	30 CY TRASH CONTAINER, CONTRACTOR IS TO REMOVE ALL EXISTING TRASH FROM PROPERTY, ITEM INCLUDES AN ONSITE 30 CY CONTAINER, EMPTYING THE CONTAINER AND RETURNING IT TO THE SITE, AND REMOVAL OF THE CONTAINER UPON COMPLETION, COMPLETE IN PLACE	EA	1	\$800.00	\$800.00	\$800.00	\$800.00	\$920.00	\$920.00
SECTION NINE - STORM WATER POLLUTION PREVENTION PLAN ITEMS SUBTOTAL:					\$7,900.00	\$5,047.50			\$7,494.00
SECTION NINE - MISCELLANEOUS ITEMS									
1	EXTRA CEMENT STABILIZED SAND, 200 PSI MINIMUM COMPRESSIVE STRENGTH AFTER 48 HOURS, PER HARRIS COUNTY SPECIFICATIONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	50	\$20.00	\$1,000.00	\$20.00	\$1,000.00	\$29.00	\$1,450.00
SECTION NINE - MISCELLANEOUS ITEMS SUBTOTAL:					\$1,000.00	\$1,000.00			\$1,450.00
BIDDING SUMMARY									
SUBTOTAL SECTION NINE - PAVING ITEMS (INTERNAL)					\$770,718.00		\$775,587.29		\$787,586.15
SUBTOTAL SECTION NINE - PAVING ITEMS (TRUNK)					\$218,190.25		\$224,718.46		\$210,476.25
SUBTOTAL SECTION NINE - STORM WATER POLLUTION PREVENTION PLAN ITEMS					\$7,900.00		\$5,047.50		\$7,494.00
SUBTOTAL SECTION NINE - MISCELLANEOUS ITEMS					\$1,000.00		\$1,000.00		\$1,450.00
TOTAL AMOUNT BASE BID					\$997,808.25		\$1,006,353.25		\$1,007,016.40

LJA Engineering, Inc.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 JULY 19, 2024
 LJA ENGINEERING, INC.
 AVIGAIL AMIGLEO
 JULY 22, 2024
 0386-5090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	4) DACO PAVING, INC.		5) ICON GC LLC		6) R CONSTRUCTION CIVIL, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SECTION NINE - PAVING ITEMS (INTERNAL)									
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5673	\$6.00	\$34,038.00	\$8.00	\$45,384.00	\$5.00	\$28,365.00
2	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	11191	\$48.60	\$543,882.60	\$49.00	\$548,359.00	\$53.00	\$593,123.00
3	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	11950	\$3.35	\$40,032.50	\$5.00	\$59,750.00	\$6.00	\$59,750.00
4	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	90	\$365.00	\$32,850.00	\$380.00	\$34,200.00	\$350.00	\$31,500.00
5	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	239	\$165.00	\$39,435.00	\$150.00	\$35,850.00	\$140.00	\$33,460.00
6	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1174	\$4.35	\$5,106.90	\$4.00	\$4,696.00	\$4.00	\$4,696.00
7	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	5558	\$4.35	\$24,177.30	\$4.00	\$22,232.00	\$4.00	\$22,232.00
8	STANDARD PAVING HEADER, COMPLETE IN PLACE	LF	56	\$17.00	\$952.00	\$1.00	\$56.00	\$30.00	\$1,680.00
9	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	9	\$17.00	\$153.00	\$18.00	\$162.00	\$16.00	\$144.00
10	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING ALL TRAFFIC BUTTONS, MARKERS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$2,100.00	\$2,100.00	\$3,222.00	\$3,222.00	\$2,800.00	\$2,800.00
11	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	5	\$800.00	\$4,000.00	\$570.00	\$2,850.00	\$470.00	\$2,350.00
12	ADA RAMPS (TYPE 7), INCLUDING TRUNCATED DOME BRICKS, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, (PER DETAIL SHEET 32), COMPLETE IN PLACE	EA	14	\$1,400.00	\$19,600.00	\$1,450.00	\$20,300.00	\$2,050.00	\$28,700.00
13	10' X 8' X 8" CONCRETE MAILBOX PAD WITH #3 BARS AT 15" O.C.E.W. OR EQUAL, ON 2" BANK SAND BEDDING (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,900.00	\$1,900.00	\$1,280.00	\$1,280.00	\$4,900.00	\$4,900.00
14	13' X 8' X 8" CONCRETE MAILBOX PAD WITH #3 BARS AT 15" O.C.E.W. OR EQUAL, ON 2" BANK SAND BEDDING (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$1,500.00	\$1,500.00	\$5,000.00	\$5,000.00
15	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	3	\$1,400.00	\$4,200.00	\$10.00	\$30.00	\$1,100.00	\$3,300.00
16	FULL CONSTRUCTION STAKING FOR PAVING AND APPURTENANCES ITEMS, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$14,100.00	\$14,100.00	\$14,100.00	\$14,100.00	\$14,100.00	\$14,100.00
17	AS BUILT SURVEY OF PAVING AND APPURTENANCES ITEMS SHOWING ELEVATIONS AT THE TOP OF CURB, BUILDING LINE, BACK OF LOT, SIGNIFICANT GRADE BREAKS AND EXTREME EVENT SWALES, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$4,900.00	\$4,900.00	\$4,900.00	\$4,900.00	\$4,900.00	\$4,900.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 JULY 19, 2024
 LJA ENGINEERING, INC.
 AVIGAIL AMIGLEO
 JULY 22, 2024
 0386-5090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	4) DACO PAVING, INC.		5) ICON GC LLC		6) R CONSTRUCTION CIVIL, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
18	EXTRA SURVEY TRIP FOR RESTAKING PREVIOUSLY PROVIDED CONSTRUCTION STAKES THAT WERE DESTROYED BY OTHERS (THIS ITEM DOES NOT INCLUDE RESTAKING DUE TO CONTRACTOR DESTROYING OWN CONSTRUCTION STAKING OR FAILING TO PROTECT CONSTRUCTION STAKING FROM KNOWN HAZARDS SUCH AS CONSTRUCTION TRAFFIC, ORDERING STAKING TOO FAR IN ADVANCE, OR CONTRACTOR'S OWN EQUIPMENT, ETC.)	DAY	1	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00
19	FINAL LOT AND RESERVE GRADING, INCLUDING STRIPPING AND PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, COMPLETE IN PLACE	EA	101	\$175.00	\$17,675.00	\$375.00	\$37,875.00	\$235.00	\$23,735.00
20	REGRADING OF EXISTING ROAD SWALES, CONTRACTOR TO ENSURE POSITIVE DRAINAGE, COMPLETE IN PLACE	LF	200	\$6.50	\$1,300.00	\$10.70	\$2,140.00	\$5.00	\$1,000.00
SECTION NINE - PAVING ITEMS (INTERNAL) SUBTOTAL:					\$794,402.30		\$840,886.00		\$867,735.00
SECTION NINE - PAVING ITEMS (TRUNK)									
1	ROADWAY, ROW AND LOT EXCAVATION, TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS PER GRADING PLAN (SHEET 12 OF 30), TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	423	\$6.34	\$2,681.82	\$6.00	\$3,384.00	\$5.00	\$2,115.00
2	ROADWAY EXCAVATION TO BE USED FOR SECTION 15 FILL (MAX HAUL DISTANCE 2,000 LF OFF ROAD EACH WAY), TO INCLUDE STRIPPING, PROOFROLLING, HAULING, PLACEMENT, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAX 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE.	CY	2250	\$7.00	\$15,750.00	\$10.00	\$22,500.00	\$5.00	\$11,250.00
3	6" REINFORCED CONCRETE PAVEMENT, MINIMUM 3,000 PSI COMPRESSIVE STRENGTH AND MINIMUM 5 SACKS CEMENT PER CUBIC YARD OF MIX, COMPLETE IN PLACE	SY	3328	\$48.60	\$161,740.80	\$50.00	\$166,400.00	\$55.00	\$183,040.00
4	6" LIME/FLY ASH STABILIZED SUB-GRADE (MANIPULATION), INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	3554	\$3.35	\$11,905.90	\$5.00	\$17,770.00	\$5.00	\$17,770.00
5	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	27	\$365.00	\$9,855.00	\$380.00	\$10,260.00	\$350.00	\$9,450.00
6	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	72	\$165.00	\$11,880.00	\$150.00	\$10,800.00	\$140.00	\$10,080.00
7	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	56	\$4.35	\$243.60	\$1.00	\$56.00	\$50.00	\$2,800.00
8	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2203	\$4.35	\$9,583.05	\$4.00	\$8,812.00	\$4.00	\$8,812.00
9	4" BLUE SQUARE DOUBLE REFLECTORIZED BUTTONS LOCATED ACROSS FROM FIRE HYDRANT, COMPLETE IN PLACE	EA	4	\$17.00	\$68.00	\$18.00	\$72.00	\$16.00	\$64.00
10	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1.00	\$2.00	\$10.00	\$20.00	\$1.00	\$2.00
11	STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	EA	3	\$800.00	\$2,400.00	\$580.00	\$1,740.00	\$470.00	\$1,410.00
SECTION NINE - PAVING ITEMS (TRUNK) SUBTOTAL:					\$226,110.17		\$241,814.00		\$246,793.00
SECTION NINE - STORM WATER POLLUTION PREVENTION PLAN ITEMS									
1	STAGE II INLET PROTECTION BARRIER (4 GRAVEL BAGS PER INLET) FOR PROPOSED AND EXISTING INLETS	EA	29	\$175.00	\$5,075.00	\$50.00	\$1,450.00	\$25.00	\$725.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE GRAND PRAIRIE HIGHLANDS SECTION NINE
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 JULY 19, 2024
 LJA ENGINEERING, INC.
 AVIGAIL AMIGLEO
 JULY 22, 2024
 0386-5090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	4) DACO PAVING, INC.		5) ICON GC LLC		6) R CONSTRUCTION CIVIL, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
2	STORMWATER POLLUTION PREVENTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE	LS	1	\$4,500.00	\$4,500.00	\$1,400.00	\$1,400.00	\$1,200.00	\$1,200.00
3	INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	100	\$2.75	\$275.00	\$5.00	\$500.00	\$2.00	\$200.00
4	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	1	\$650.00	\$650.00	\$500.00	\$500.00	\$500.00	\$500.00
5	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT AND REGRADE THE AREA TO MATCH FINISHED GRADE, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$500.00	\$500.00	\$500.00	\$500.00
6	30 CY TRASH CONTAINER, CONTRACTOR IS TO REMOVE ALL EXISTING TRASH FROM PROPERTY, ITEM INCLUDES AN ONSITE 30 CY CONTAINER, EMPTYING THE CONTAINER AND RETURNING IT TO THE SITE, AND REMOVAL OF THE CONTAINER UPON COMPLETION, COMPLETE IN PLACE	EA	1	\$800.00	\$800.00	\$1,000.00	\$1,000.00	\$800.00	\$800.00
SECTION NINE - STORM WATER POLLUTION PREVENTION PLAN ITEMS SUBTOTAL:					\$12,800.00	\$5,350.00		\$3,925.00	
SECTION NINE - MISCELLANEOUS ITEMS									
1	EXTRA CEMENT STABILIZED SAND, 200 PSI MINIMUM COMPRESSIVE STRENGTH AFTER 48 HOURS, PER HARRIS COUNTY SPECIFICATIONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	50	\$35.00	\$1,750.00	\$59.00	\$2,950.00	\$50.00	\$2,500.00
SECTION NINE - MISCELLANEOUS ITEMS SUBTOTAL:					\$1,750.00	\$2,950.00		\$2,500.00	
BIDDING SUMMARY									
SUBTOTAL SECTION NINE - PAVING ITEMS (INTERNAL)					\$794,402.30		\$840,886.00		\$867,735.00
SUBTOTAL SECTION NINE - PAVING ITEMS (TRUNK)					\$226,110.17		\$241,814.00		\$246,793.00
SUBTOTAL SECTION NINE - STORM WATER POLLUTION PREVENTION PLAN ITEMS					\$12,800.00		\$5,350.00		\$3,925.00
SUBTOTAL SECTION NINE - MISCELLANEOUS ITEMS					\$1,750.00		\$2,950.00		\$2,500.00
TOTAL AMOUNT BASE BID					\$1,035,062.47		\$1,091,000.00		\$1,120,953.00

LJA Engineering, Inc.