

BID TABULATION FOR:

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
TO SERVE BETKA ROADWAY IMPROVEMENTS  
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
FEBRUARY 14, 2024  
LJA ENGINEERING, INC.  
C CORTEZ  
FEBRUARY 14, 2024  
0386-5810 (9.2)


BIDDER'S NAME

TOTAL AMOUNT BID

1) FORDE CONSTRUCTION COMPANY

\$787,490.61

CALENDAR DAYS 35/45



I, STEVEN BOYD, P.E., hereby certify these bid tabulations to be true and correct.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE BETKA ROADWAY IMPROVEMENTS  
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
 FEBRUARY 14, 2024  
 LJA ENGINEERING, INC.  
 C CORTEZ  
 FEBRUARY 14, 2024  
 0388-5810 (9.2)

1) FORDE CONSTRUCTION COMPANY

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>BETKA ROADWAY IMPROVEMENTS - PAVING ITEMS</b>					
1	ROADWAY AND ROW EXCAVATION, (TXDOT ITEM 110). TO BE USED FOR ONSITE FILL TO MATCH ELEVATIONS, MAXIMUM HAUL DISTANCE 4,000 FT, OFFROAD, TO INCLUDE STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, REAPPLICATION OF STRIPPINGS, COMPLETE IN PLACE.	CY	232	\$120.00	\$27,840.00
2	ROADWAY FILL & EMBANKMENT (TXDOT ITEM 110), INCLUDES SITE PREP, EXCAVATION, HAULING, PLACEMENT, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	925	\$80.00	\$74,000.00
3	MANIPULATION, GRADING, AND COMPACTION OF SUBGRADE FOR ASPHALT PAVEMENT (TXDOT ITEM 110).	SY	3325	\$24.00	\$79,800.00
4	PLANE ASPHALT CONCRETE PAVEMENT (TXDOT ITEM 354), 2" DEP TH, COMPLETE IN PLACE	SY	8072	\$4.50	\$36,324.00
5	2" TYPE "D" HMAC PAVEMENT (TXDOT ITEM 340), COMPLETE IN PLACE.	TON	361	\$210.00	\$75,810.00
6	10" HMAC TYPE "B" BLACK BASE (TXDOT ITEM 292), COMPLETE IN PLACE.	TON	1967	\$143.00	\$281,281.00
7	PRIME COAT, (MC-30) @ 0.25 GAL/SY, (TXDOT ITEM 310), COMPLETE IN PLACE.	GAL	720	\$5.00	\$3,600.00
8	TACK COAT, @ 0.08 GAL/SY (TXDOT ITEM 300), COMPLETE IN PLACE.	GAL	173	\$5.00	\$865.00
9	HYDRATED LIME FOR STABILIZED SUB-GRADE (15 LB/SY), (TXDOT ITEM 280), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE.	TON	25	\$369.00	\$9,225.00
10	FLY ASH FOR STABILIZED SUB-GRADE (40 LB/SY), (TXDOT ITEM 285), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE.	TON	67	\$135.00	\$9,045.00
11	2' SAWCUT FOR REMOVAL AND DISPOSAL OF EXISTING ASPHALT PAVEMENT, INCLUDES BASE AND SUBGRADE (TXDOT ITEM 105), CONTRACTOR TO CONNECT PROPOSED ASPHALT PAVEMENT INTO EXISTING BETKA ROAD ASPHALT PAVEMENT, COMPLETE IN PLACE	LF	4057	\$3.25	\$13,185.25
12	CONTRACTOR TO CONNECT PROPOSED ASPHALT PAVEMENT INTO PROPOSED 8" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	84	\$128.00	\$10,752.00
13	4" SOLID, WHITE-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	LF	3968	\$0.70	\$2,777.60
14	4" SOLID, YELLOW-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	LF	3308	\$0.72	\$2,381.76
15	8" SOLID, WHITE-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	LF	600	\$1.90	\$1,140.00
16	24" SOLID, WHITE-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	LF	26	\$12.00	\$312.00
17	24" SOLID, YELLOW-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	LF	510	\$8.00	\$4,080.00
18	WORD, WHITE-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	EA	4	\$180.00	\$720.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
TO SERVE BETKA ROADWAY IMPROVEMENTS  
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 570C  
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS  
FEBRUARY 14, 2024  
LJA ENGINEERING, INC.  
C CORTEZ  
FEBRUARY 14, 2024  
0386-5810 (9.2)

**1) FORDE CONSTRUCTION COMPANY**

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
19	ARROW, WHITE-REFLECTORIZED PAVEMENT MARKINGS - TYPE I, (TXDOT ITEM 666), COMPLETE IN PLACE.	EA	17	\$162.00	\$2,754.00
20	NON-REFLECTORIZED YELLOW RAISED BUTTONS, (TXDOT ITEM 672), COMPLETE IN PLACE.	EA	80	\$6.00	\$480.00
21	REFLECTORIZED PAVEMENT MARKINGS - TYPE I-C RAISED BUTTONS, (TXDOT ITEM 672), COMPLETE IN PLACE.	EA	75	\$6.00	\$450.00
22	REFLECTORIZED PAVEMENT MARKINGS - TYPE II A-A RAISED BUTTONS, (TXDOT ITEM 672), COMPLETE IN PLACE.	EA	120	\$6.00	\$720.00
23	TEMPORARY TRAFFIC CONTROL DEVICES (TXDOT ITEM 502) AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, ETC.) PER TXDOT STANDARDS, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$98,000.00	\$98,000.00
24	FULL CONSTRUCTION STAKING FOR PAVING AND APPURTENANCES ITEMS, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$13,400.00	\$13,400.00
25	AS BUILT SURVEY OF PAVING AND APPURTENANCES ITEMS SHOWING ELEVATIONS AT THE TOP OF PAVEMENT, ROW, SIGNIFICANT GRADE BREAKS AND REGRADED SWALES, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH LJA SURVEYING, INC., AARON G. FERGUSON, 713.953.5196, COMPLETE IN PLACE	LS	1	\$6,400.00	\$6,400.00
26	EXTRA SURVEY TRIP FOR RESTAKING PREVIOUSLY PROVIDED CONSTRUCTION STAKES THAT WERE DESTROYED BY OTHERS (THIS ITEM DOES NOT INCLUDE RESTAKING DUE TO CONTRACTOR DESTROYING OWN CONSTRUCTION STAKING OR FAILING TO PROTECT CONSTRUCTION STAKING FROM KNOWN HAZARDS SUCH AS CONSTRUCTION TRAFFIC, ORDERING STAKING TOO FAR IN ADVANCE, OR CONTRACTOR'S OWN EQUIPMENT, ETC.)	DAY	1	\$2,000.00	\$2,000.00
27	REGRADE EXISTING DRAINAGE SWALES, V-BOTTOM, 4:1 SIDE SLOPES, ALL DEPTHS, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	2284	\$12.00	\$27,168.00
28	REMOVAL AND RELOCATION OF EXISTING SIGNS, COMPLETE IN PLACE	EA	3	\$220.00	\$660.00
29	RELOCATING EXISTING MAILBOX, COMPLETE IN PLACE	EA	2	\$185.00	\$370.00
<b>BETKA ROADWAY IMPROVEMENTS - PAVING ITEMS SUBTOTAL:</b>					<b>\$785,540.61</b>
<b>BETKA ROAD IMPROVEMENTS - STORM WATER POLLUTION PREVENTION ITEMS</b>					
1	STORMWATER POLLUTION PREVENTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE.	LS	1	\$1,800.00	\$1,800.00
2	INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), (TXDOT ITEM 506) COMPLETE IN PLACE.	LF	100	\$1.50	\$150.00
<b>BETKA ROAD IMPROVEMENTS - STORM WATER POLLUTION PREVENTION ITEMS SUBTO</b>					<b>\$1,950.00</b>
<b>BIDDING SUMMARY</b>					
SUBTOTAL BETKA ROADWAY IMPROVEMENTS - PAVING ITEMS					\$785,540.61
SUBTOTAL BETKA ROAD IMPROVEMENTS - STORM WATER POLLUTION PREVENTION ITE					\$1,950.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$787,490.61</b>