

BID TABULATION FOR:

CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES
& PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 491
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
NOVEMBER 19, 2024
LJA ENGINEERING, INC.
A.CAROTHERS
NOVEMBER 20, 2024
1104-6204 (0)


BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID	BID INCLUDING ALTERNATE BID ITEMS NO. 1	BID INCLUDING ALTERNATE BID ITEMS NO. 2
1) CE BARKER LTD.	\$1,485,459.07	\$1,486,269.07	\$1,530,060.23

CALENDAR DAYS 0/75



I, Micah Kreikemeier, PE, hereby certify these bid tabulations to be true and correct.



11/20/2024

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES
& PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 491
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
NOVEMBER 19, 2024
LJA ENGINEERING, INC.
A.CAROTHERS
NOVEMBER 20, 2024
1104-6204 (0)

1) CE BARKER LTD.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
WATER ITEMS					
1	12" P.V.C. RESTRAINED JOINT N.P.W.L. (PURPLE PIPE), AWWA C-900, DR 18, CLASS 235, ALL DEPTHS, INCLUDES ALL FITTINGS, BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	1244	\$94.56	\$117,632.64
2	TRENCH SAFETY SYSTEM, ALL DEPTHS, AND ALL SIZES, COMPLETE IN PLACE	LF	1244	\$0.01	\$12.44
3	REMOVE AND RELOCATE EXISTING FIRE HYDRANT AND 6" GATE VALVE & BOX, 6 " LEAD, INCLUDES ROTATING VALVE AND FIREHYDRANT, COMPLETE IN PLACE	EA	3	\$1,773.19	\$5,319.57
4	12" AWWA GATE VALVE AND BOX, (PURPLE BOX), WITH RESTRAINED JOINTS, COMPLETE IN PLACE	EA	1	\$4,130.88	\$4,130.88
5	16" X 6" BACK TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	3	\$8,320.07	\$24,960.21
6	8" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	355	\$27.75	\$9,851.25
7	CONSTRUCTION STAKING: IN ACCORDANCE WITH SECTION 5.2 IN THE INSTRUCTIONS TO BIDDERS AND SECTION 01000' GENERAL REQUIREMENTS, COMPLETE IN PLACE	LS	1	\$6,580.64	\$6,580.64
8	WET CONNECTION OF PROPOSED 12" N.P.W.L. TO EXISTING N.P.W.L., INCLUDES FITTINGS, ALL ADAPTERS AND CONNECTORS NECESSARY, AND REMOVAL OF EXISTING PLUG & CLAMP AND 2" BLOW-OFF VALVE & BOX, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$966.35	\$966.35
WATER ITEMS SUBTOTAL:					\$169,453.98
SANITARY SEWER ITEMS					
1	8" PVC SANITARY SEWER PIPE, ASTM D-2241, 8'-12' DEPTH, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	503	\$66.19	\$33,293.57
2	1 1/4 " P.V.C. SANITARY FORCE MAIN, ASTM D-2241, SDR 17, ALL DEPTHS, INCLUDES ALL FITTINGS, BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	673	\$38.08	\$25,627.84
3	TRENCH SAFETY SYSTEM, ALL DEPTHS, ALL SIZES, COMPLETE IN PLACE	LF	1176	\$0.01	\$11.76
4	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE (0'-8' DEPTH), INCLUDES PLASTIC INFLOW PROTECTOR AND ADJUSTMENTS, COMPLETE IN PLACE	EA	4	\$2,884.32	\$11,537.28
5	T.V. INSPECTION FOR SANITARY SEWER SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	503	\$1.00	\$503.00
6	CORROSION RESISTANT 5' DIAMETER PRECAST MANHOLE FOR FORCE MAIN DISCHARGE, INCLUDES STAINLESS STEEL INFLOW PROTECTOR AND ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$9,055.92	\$9,055.92
7	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE SEALED AND VENTED, (0'-8' DEPTH), INCLUDES PROTECTIVE INTERIOR COATING AND ADJUSTMENTS, COMPLETE IN PLACE	EA	1	\$7,196.01	\$7,196.01
8	EXTRA VERTICAL DEPTH OF SANITARY SEWER MANHOLES (OVER 8' DEPTH), ALL SIZES, COMPLETE IN PLACE	VF	35	\$182.52	\$6,388.20
9	CORE INTO EXISTING SANITARY SEWER MANHOLE AND CONNECT PROPOSED 8" SANITARY SEWER LINE, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$3,136.07	\$3,136.07
SANITARY SEWER ITEMS SUBTOTAL:					\$96,749.65

BID TABULATION FOR:

BID OPENING DATE:

BID OPENING LOCATION:

TABULATION BY:

TABULATION DATE:

LJA JOB NO.

CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES
 & PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 491
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 NOVEMBER 19, 2024
 LJA ENGINEERING, INC.
 A.CAROTHERS
 NOVEMBER 20, 2024
 1104-6204 (0)

1) CE BARKER LTD.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
DRAINAGE FACILITIES ITEMS					
1	24" RCP STORM SEWER PIPE, ASTM C-76, CLASS III, ALL DEPTHS, INCLUDING BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	555	\$109.41	\$60,722.55
2	30" RCP STORM SEWER PIPE, ASTM C-76, CLASS III, ALL DEPTHS, INCLUDING BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	321	\$135.02	\$43,341.42
3	36" RCP STORM SEWER PIPE, ASTM C-76, CLASS III, ALL DEPTHS, INCLUDING BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	417	\$184.87	\$77,090.79
4	48" RCP STORM SEWER PIPE, ASTM C-76, CLASS III, ALL DEPTHS, INCLUDING BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	240	\$284.95	\$68,388.00
5	TRENCH SAFETY SYSTEM, ALL SIZES AND DEPTHS, COMPLETE IN PLACE	LF	1533	\$0.01	\$15.33
6	TYPE "C" MANHOLE FOR 42" STORM SEWERS AND SMALLER, ALL DEPTHS, INCLUDING ADJUSTMENTS, COMPLETE IN PLACE	EA	12	\$4,001.31	\$48,015.72
7	STAGE I - STANDARD 5' PRECAST INLET ('B-B') (INCLUDES INLET PROTECTION BARRIER FOR STAGE 1 INLETS), COMPLETE IN PLACE	EA	12	\$1,798.06	\$21,576.72
8	STAGE II - STANDARD 5' PRECAST INLET ('B-B') (INCLUDES TEMPORARY SAND-FILLED BURLAP BAGS FOR EROSION AND SEDIMENT CONTROL), COMPLETE IN PLACE	EA	12	\$1,671.43	\$20,057.16
9	REGRADE EXISTING DRAINAGE SWALE, INCLUDES DEMUCK, EXCAVATION, STRIPPING, STOCKPILING STRIPPING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPING, COMPLETE IN PLACE, COMPLETE IN PLACE	LF	954	\$8.86	\$8,452.44
10	18" THICK CONCRETE RIP RAP, INCLUDES GEOTEXTILE FABRIC, COMPLETE IN PLACE	SY	206	\$102.45	\$21,104.70
11	REMOVE AND OFFSITE DISPOSAL OF EXISTING RIP RAP AND GEOTEXTILE FABRIC, COMPLETE IN PLACE	SY	432	\$60.78	\$26,256.96
12	BREAK INTO EXISTING BOX CULVERT AND CONNECT PROPOSED STORM SEWER WITH CONCRETE COLLAR, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$3,308.05	\$3,308.05
13	CONSTRUCT REINFORCED CONCRETE TYPE "C" MANHOLE TOP ON EXISTING BOX CULVERT, INCLUDES ADJUSTMENTS AND APPURTENANCES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$1,687.89	\$1,687.89
DRAINAGE FACILITIES ITEMS SUBTOTAL:					\$400,017.73
MISCELLANEOUS ITEMS					
1	SUITABLE UTILITY SPOILS TO BE DISPOSED OF ON SITE, (INCLUDES 4" STRIPPINGS, STOCKPILING AND REAPPLICATION OF STRIPPINGS TO FILL AREAS), COMPACTION TO 95% STANDARD PROCTOR DENSITY IN ACCORDANCE WITH GRADING PLAN, INCLUDES HAULING (NO GREATER THAN 1 MILE RADIUS),COMPLETE IN PLACE	CY	1538	\$2.00	\$3,076.00
2	SANITARY SEWER WET SAND CONSTRUCTION AS PER DETAILS AND RECOMMENDED BY GEOTECHNICAL ENGINEER, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	600	\$5.00	\$3,000.00
3	DEWATERING FOR SANITARY SEWER, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	600	\$20.00	\$12,000.00
4	DEWATERING FOR STORM SEWER, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	770	\$20.00	\$15,400.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES
& PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 491
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
NOVEMBER 19, 2024
LJA ENGINEERING, INC.
A.CAROTHERS
NOVEMBER 20, 2024
1104-6204 (0)

1) CE BARKER LTD.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
5	STORM SEWER WET SAND CONSTRUCTION AS PER DETAILS AND RECOMMENDED BY GEOTECHNICAL ENGINEER, ALL LINES AND DEPTH, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	770	\$5.00	\$3,850.00
6	8" SCHEDULE 40. P.V.C. SLEEVES, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	100	\$34.99	\$3,499.00
7	6" SCHEDULE 40 P.V.C. SLEEVES, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	100	\$27.90	\$2,790.00
8	EXTRA CEMENT STABILIZED SAND, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	100	\$21.11	\$2,111.00
9	CLEARING AND GRUBBING, TO INCLUDE CHIPPING AND HAULING OFFSITE OF CLEARED MATERIAL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	AC	1	\$7,500.00	\$7,500.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$53,226.00
PAVING ITEMS					
1	ROADWAY EXCAVATION, COMPLETE IN PLACE	CY	4340	\$5.70	\$24,738.00
2	COMPACTED FILL (95% STANDARD PROCTOR DENSITY WITH 6" LIFTS IN ACCORDANCE WITH THE GRADING PLAN), INCLUDES HAULING (NO GREATER THAN 1 MILE RADIUS), COMPLETE IN PLACE	CY	4340	\$5.70	\$24,738.00
3	6-INCH REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	265	\$68.21	\$18,075.65
4	7-INCH REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	6143	\$76.34	\$468,956.62
5	ASPHALT TRANSITION, INCLUDES 2 INCHES OF TYPE D SURFACE, 8 INCHES OF BLACK BASE AND 6 INCHES OF STABILIZED SUB-GRADE	SY	323	\$208.93	\$67,484.39
6	6" LIME-FLY ASH STABILIZED SUBGRADE (MANIPULATION), COMPLETE IN PLACE	SY	594	\$7.60	\$4,514.40
7	HYDRATED LIME FOR 6" SUBGRADE (10 POUNDS PER SQUARE YARD OF STABILIZED SUBGRADE), BY DRY WEIGHT AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY THE GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	2.97	\$417.86	\$1,241.04
8	FLY ASH FOR 6" SUBGRADE (40 POUNDS PER SQUARE YARD OF STABILIZED SUBGRADE), BY DRY WEIGHT AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY THE GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	11.88	\$202.60	\$2,406.89
9	8" LIME -FLY ASH STABILIZED SUBGRADE (MANIPULATION), COMPLETE IN PLACE	SY	6495	\$7.60	\$49,362.00
10	HYDRATED LIME FOR 8" SUBGRADE (16 POUNDS PER SQUARE YARD OF STABILIZED SUBGRADE), BY DRY WEIGHT AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY THE GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	52	\$417.86	\$21,728.72
11	FLY ASH FOR 8" SUBGRADE (65 POUNDS PER SQUARE YARD OF STABILIZED SUBGRADE), BY DRY WEIGHT AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY THE GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	211	\$202.60	\$42,748.60
12	6-INCH REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	3067	\$6.29	\$19,291.43
13	STOP SIGN WITH STREET NAME "R1-1". COMPLETE IN PLACE	EA	1	\$943.96	\$943.96
14	30 MPH SIGN "R2-1", COMPLETE IN PLACE	EA	1	\$648.05	\$648.05
15	STREET NAME SIGN "S3-1", COMPLETE IN PLACE	EA	1	\$648.05	\$648.05

BID TABULATION FOR:**BID OPENING DATE:****BID OPENING LOCATION:****TABULATION BY:****TABULATION DATE:****LJA JOB NO.**

CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES
 & PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL
 HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 491
 CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
 NOVEMBER 19, 2024
 LJA ENGINEERING, INC.
 A.CAROTHERS
 NOVEMBER 20, 2024
 1104-6204 (0)

1) CE BARKER LTD.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
16	PERMANENT TRAFFIC CONTROL DEVICES, TRAFFIC BUTTONS AND PAVEMENT STRIPPING, COMPLETE IN PLACE	LS	1	\$7,940.45	\$7,940.45

PAVING ITEMS SUBTOTAL:**\$755,466.25****PAVING MISCELLANEOUS ITEMS**

1	EXTRA TRAFFIC SIGNS, COMPLETE IN PLACE	EA	1	\$759.74	\$759.74
2	AS-BUILT TOPOGRAPHY SURVEY: INCLUDING SANITARY SEWER INVERT ELEVATIONS AT MANHOLES, STORM SEWER INVERT ELEVATIONS AT MANHOLES, TOP OF CURB, GUTTER LINE, AND INVERT ELEVATIONS AT STORM SEWER INLETS, TOP OF CURB ELEVATION AT STREET HIGH POINTS, TOP OF CURB ELEVATIONS ON ENTRY ON BOULEVARD MEDIANS AND CUL-DE-SAC ISLANDS, ALL PLAN AND APPARENT GRADE CHANGE ELEVATIONS IN THE LOTS AND RESERVES, LOT CORNERS, AND TOP OF CURB ELEVATIONS IN ADJACENT RIGHTS-OF -WAY; IN ACCORDANCE WITH SECTION 5.2 IN THE INSTRUCTIONS AND SECTION 01000" GENERAL REQUIREMENTS". CONTRACTOR TO ALSO PLACE GRADE STAKES ON PERIMETER REAR LOT PINS FOR OWNER'S FENCE, CONTRACTOR VERIFY PROPER FILL ELEVATIONS	LS	1	\$6,500.00	\$6,500.00
3	MAINTAIN STORM WATER POLLUTION PREVENTION PLAN (INCLUDES FILTER FABRIC FENCE, INLET PROTECTION AND CONSTRUCTION ENTRANCE), COMPLETE IN PLACE	LS	1	\$500.00	\$500.00
4	INSTALLATION, MAINTENANCE AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$2,785.72	\$2,785.72

PAVING MISCELLANEOUS ITEMS SUBTOTAL:**\$10,545.46****ALTERNATE BID ITEMS NO. 1**

1	HYDROMULCH SEEDING PER HARRIS COUNTY SPECIFICATION 165 FOR EROSION CONTROL AND STABILIZATION PURPOSES OF ROW AND RESERVES AS DIRECTED BY OWNER, COMPLETE IN PLACE	AC	0.54	\$1,500.00	\$810.00
---	---	----	------	------------	----------

ALTERNATE BID ITEMS NO. 1 SUBTOTAL:**\$810.00****ALTERNATE BID ITEMS NO. 2**

1	CEMENT FOR 6" SUBGRADE (50 POUNDS PER SQUARE YARD OF STABILIZED SUBGRADE), BY DRY WEIGHT AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY THE GEOTECHNICAL ENGINEER, TO BE USED IN LIEU OF PAVING ITEMS NO. 7 & 8, COMPLETE IN PLACE	TON	14.85	\$272.24	\$4,042.76
2	CEMENT FOR 8" SUBGRADE (50 POUNDS PER SQUARE YARD OF STABILIZED SUBGRADE), BY DRY WEIGHT AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY THE GEOTECHNICAL ENGINEER, TO BE USED IN LIEU OF PAVING ITEMS NO. 7 & 8, COMPLETE IN PLACE	TON	162.38	\$272.24	\$44,206.33

ALTERNATE BID ITEMS NO. 2 SUBTOTAL:**\$48,249.09****BIDDING SUMMARY**

SUBTOTAL WATER ITEMS	\$169,453.98
SUBTOTAL SANITARY SEWER ITEMS	\$96,749.65
SUBTOTAL DRAINAGE FACILITIES ITEMS	\$400,017.73
SUBTOTAL MISCELLANEOUS ITEMS	\$53,226.00
SUBTOTAL PAVING ITEMS	\$755,466.25
SUBTOTAL PAVING MISCELLANEOUS ITEMS	\$10,545.46

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES
& PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 491
CITY OF HOUSTON E.T.J., HARRIS COUNTY, TEXAS
NOVEMBER 19, 2024
LJA ENGINEERING, INC.
A.CAROTHERS
NOVEMBER 20, 2024
1104-6204 (0)

1) CE BARKER LTD.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
TOTAL AMOUNT BASE BID					\$1,485,459.07
<u>ALTERNATE BID ITEMS NO. 1</u>					
TOTAL AMOUNT BASE BID					\$1,485,459.07
SUBTOTAL ALTERNATE BID ITEMS NO. 1					\$810.00
TOTAL AMOUNT INCLUDING ALTERNATE BID ITEMS NO. 1					\$1,486,269.07
<u>ALTERNATE BID ITEMS NO. 2</u>					
TOTAL AMOUNT BASE BID					\$1,485,459.07
DEDUCT PAVING ITEMS ITEM NO.7					-\$1,241.04
DEDUCT PAVING ITEMS ITEM NO.8					-\$2,406.89
SUBTOTAL ALTERNATE BID ITEMS NO. 2					\$48,249.09
TOTAL AMOUNT INCLUDING ALTERNATE BID ITEMS NO. 2					\$1,530,060.23

LJA ENGINEERING, INC.

BID TABULATION ROUTING FORM

To: MICAH KREIKEMEIER, P.E. _____

From: A.CAROTHERS _____

Date: ##### _____

Job Number: 1104-6204 (0) _____

Project Name: CONSTRUCTION OF THE WATER , SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE RIO MEDINA TRAIL

Bid Date: NOVEMBER 19, 2024 _____

Attachments: Bid Tabulation
 Bids
 Other: _____

Notes:

PLEASE REVIEW AND SEAL THE BID TAB, CHECK ONE OF THE OPTIONS BELOW, AND RETURN ALL ITEMS TO CAG

- Prepare Recommendation of Award Letter for low bidder
- Prepare Notice of Award Letter for Low Bidder
- Anticipated Award Letter
- Based on actions Taken at District Meeting on: _____ (Date)
- Prepare Contracts for Low Bidder
- Hold until further notice
- Other/Special Instructions:

Please award Base + Alt. #1

