

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER SUPPLY PLANT RECOATING
INTERSTATE MUNICIPAL UTILITY DISTRICT
CITY OF HOUSTON E.T.J.
HARRIS COUNTY, TEXAS
DECEMBER 4, 2018
LJA ENGINEERING, INC.
L. MARTINEZ
DECEMBER 4, 2018
1162-1801 (9.2)

BIDDER'S NAME	TOTAL BID AMOUNT
1) THE TREY EVANS CO.	\$644,500.00
2) T & G SERVICES	\$659,150.00
3) N.G. PAINTINGS, LP	\$709,000.00

CALENDAR DAYS - 130/150



I, Gregg Haan, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

CONSTRUCTION OF THE WATER SUPPLY PLANT RECOATING
 INTERSTATE MUNICIPAL UTILITY DISTRICT
 CITY OF HOUSTON E.T.J.
 HARRIS COUNTY, TEXAS
 DECEMBER 4, 2018
 LJA ENGINEERING, INC.
 L. MARTINEZ
 DECEMBER 4, 2018
 1162-1801 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	1) THE TREY EVANS CO.		2) T & G SERVICES		3) N.G. PAINTINGS, LP	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
BASE BID ITEMS									
1.	500,000 GALLON GROUND STORAGE TANK INTERIOR SURFACES (INCLUDING CLEANING), PROVIDE SSPC-SP5/NACE 1 WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH AN EPOXY SYSTEM COATING PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 8, COMPLETE IN PLACE	EA	1	\$75,000.00	\$75,000.00	\$130,000.00	\$130,000.00	\$100,000.00	\$100,000.00
2.	500,000 GALLON GROUND STORAGE TANK EXTERIOR SURFACES (INCLUDING CLEANING), PROVIDE SSPC-SP10/NACE 2 NEAR-WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH ZINC/EPOXY/URETHANE SYSTEM COATING PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 7, COMPLETE IN PLACE	EA	1	\$70,000.00	\$70,000.00	\$90,000.00	\$90,000.00	\$80,000.00	\$80,000.00
3.	15,000 GALLON HYDROPNEUMATIC TANK INTERIOR SURFACES. (INCLUDING CLEANING), PROVIDE SSPC-SP5/NACE 1 WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH AN EPOXY SYSTEM COATING PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 8, COMPLETE IN PLACE	EA	1	\$15,000.00	\$15,000.00	\$11,500.00	\$11,500.00	\$18,000.00	\$18,000.00
4.	15,000 GALLON HYDROPNEUMATIC TANK EXTERIOR SURFACES (INCLUDING CLEANING), PROVIDE SSPC-SP10/NACE 2 NEAR-WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH ZINC/EPOXY/URETHANE SYSTEM COATING PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 7, COMPLETE IN PLACE	EA	1	\$11,000.00	\$11,000.00	\$9,700.00	\$9,700.00	\$10,000.00	\$10,000.00
5.	FOR ALL PLANT EXTERIOR PIPING, INCLUDING WELL HEADER, PROVIDE SSPC-SP10/NACE 2 NEAR-WHITE METAL BLAST CLEANING SURFACE PREPARATION WITH ZINC/EPOXY/URETHANE SYSTEM COATING PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 7, COMPLETE IN PLACE	LS	1	\$6,000.00	\$6,000.00	\$5,500.00	\$5,500.00	\$15,000.00	\$15,000.00
6.	PAINT ONSITE CONTROL BUILDING EXTERIOR PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 9, INCLUDES, DOORS, OVERHEAD DOOR, AND PIPE BOLLARDS, INCLUDING PRESSURE WASHING, COATING BUILDING EXTERIOR WITH ACRYLIC PAINT, COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$3,000.00	\$3,000.00	\$6,000.00	\$6,000.00
7.	PAINT ONSITE CONTROL BUILDING INTERIOR PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 9, INCLUDES, DOORS, OVERHEAD DOOR, AND ALL ASSOCIATED PIPING PER PAINTING SPECIFICATION - PAINTING SYSTEM NO. 7, INCLUDING PAINT REMOVAL, COATING WITH ACRYLIC PAINT, COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$3,000.00	\$3,000.00	\$10,000.00	\$10,000.00
8.	REPLACE ROOF VENT FOR GROUND STORAGE TANK, COMPLETE IN PLACE	EA	1	\$5,000.00	\$5,000.00	\$3,500.00	\$3,500.00	\$7,500.00	\$7,500.00
9.	REPLACE ROOF ACCESS HATCH FOR GROUND STORAGE TANK, COMPLETE IN PLACE	EA	1	\$4,000.00	\$4,000.00	\$3,750.00	\$3,750.00	\$5,000.00	\$5,000.00
10.	CONSTRUCT ADDITIONAL ROOF HATCH ON GROUND STORAGE TANK, COMPLETE IN PLACE	EA	1	\$4,500.00	\$4,500.00	\$3,750.00	\$3,750.00	\$5,000.00	\$5,000.00
11.	COLLECTION AND OFFSITE DISPOSAL OF WASTE MATERIAL GENERATED BY COATING REMOVAL PROCESS ALL AREAS, COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$3,000.00	\$3,000.00	\$5,000.00	\$5,000.00
12.	FURNISH, OPERATE, AND MAINTAIN DEHUMIDIFICATION SYSTEM DURING BASTING, COATING, AND CURING OF INTERIOR WET AREAS OF GROUND STORAGE TANK, COMPLETE IN PLACE	LS	1	\$25,000.00	\$25,000.00	\$7,500.00	\$7,500.00	\$20,000.00	\$20,000.00
13.	MISCELLANEOUS WELDING REPAIRS ON GROUND STORAGE TANK, COMPLETE IN PLACE	HR	25	\$100.00	\$2,500.00	\$275.00	\$6,875.00	\$120.00	\$3,000.00
14.	PAINTING OF NON SKID AREAS ON ROOF DECK AREA ON GROUND STORAGE TANK, COMPLETE IN PLACE	LS	1	\$2,000.00	\$2,000.00	\$3,500.00	\$3,500.00	\$2,000.00	\$2,000.00
15.	PRE SURFACE PREP OF WELDS BY GRINDING TO ELIMINATE ROUGH EDGE, SPLATTER, GOUGES, ETC. ON GROUND STORAGE TANK IN AREAS APPROVED BY ENGINEER, COMPLETE IN PLACE	HR	25	\$80.00	\$2,000.00	\$50.00	\$1,250.00	\$70.00	\$1,750.00

BID TABULATION FOR:

CONSTRUCTION OF THE WATER SUPPLY PLANT RECOATING
 INTERSTATE MUNICIPAL UTILITY DISTRICT
 CITY OF HOUSTON E.T.J.
 HARRIS COUNTY, TEXAS
 DECEMBER 4, 2018
 LJA ENGINEERING, INC.
 L. MARTINEZ
 DECEMBER 4, 2018
 1162-1801 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	1) THE TREY EVANS CO.		2) T & G SERVICES		3) N.G. PAINTINGS, LP	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
16.	PROVIDE SURFACE PREPERATION AND COATING OF THE EXISTING INTERIOR WET SURFACES ON ELEVATED STORAGE TANK, COMPLETE IN PLACE	LS	1	\$80,000.00	\$80,000.00	\$110,000.00	\$110,000.00	\$100,000.00	\$100,000.00
17.	PROVIDE SURFACE PREPERATION AND COATING OF THE EXISTING INTERIOR DRY SURFACES ON ELEVATED STORAGE TANK, INCLUDING ALL PIPING, COMPLETE IN PLACE	LS	1	\$55,000.00	\$55,000.00	\$67,000.00	\$67,000.00	\$20,000.00	\$20,000.00
18.	PROVIDE SURFACE PREPERATION AND COATING OF THE EXISTING EXTERIOR SURFACES ON ELEVATED STORAGE TANK, INCLUDING ALL PIPING, COMPLETE IN PLACE	LS	1	\$215,000.00	\$215,000.00	\$157,000.00	\$157,000.00	\$250,000.00	\$250,000.00
19.	FURNISH, OPERATE AND MAINTAIN DEHUMIDIFICATION SYSTEM DURING BLASTING, COATING AND CURING OF THE INTERIOR WET AREA, ON ELEVATED STORAGE TANK, COMPLETE IN PLACE	LS	1	\$25,000.00	\$25,000.00	\$7,500.00	\$7,500.00	\$20,000.00	\$20,000.00
20.	PAINTING OF NON-SLIP OR NON-SKID AREAS ON ROOF DECK AREA ON ELEVATED STORAGE TANK, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$3,500.00	\$3,500.00	\$3,000.00	\$3,000.00
21.	PRE-SURFACE PREPERATION OF WELDS BY GRINDING TO ELIMINATE ROUGH EDGES, SPLATTER, GOUGES, ETC., ON ELEVATED STORAGE TANK, COMPLETE IN PLACE	HR	25	\$80.00	\$2,000.00	\$50.00	\$1,250.00	\$70.00	\$1,750.00
22.	APPLICATION OF APPROVED ELASTOMERIC SEALANT TO CAULK GAPS OR AREAS WHERE PAITING IS NOT ACCESSIBLE IN INTERIOR WET AREA ABOVE WATER LINE ON ELEVATED STORAGE TANK AS APPROVED BY ENGINEER, COMPLETE IN PLACE	LF	100	\$20.00	\$2,000.00	\$40.00	\$4,000.00	\$20.00	\$2,000.00
23.	MISCELLANEOUS WELDING REPAIRS, ON ELEVATED STORAGE TANK, COMPLETE IN PLACE	HRS	25	\$100.00	\$2,500.00	\$275.00	\$6,875.00	\$120.00	\$3,000.00
24.	PAINT DISTRICT LOGO AND NAME ON NORTH SIDE OF ELEVATED STORAGE TANK TWO COLORS, APPROXIMATELY 10' HIGH X 20' WIDE, COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$5,500.00	\$5,500.00	\$8,000.00	\$8,000.00
SUBTOTAL BASE BID ITEMS					\$633,500.00	\$648,450.00	\$648,450.00	\$696,000.00	\$696,000.00
MISCELLANEOUS ITEMS									
1.	DISINFECTION OF ALL GROUND STORAGE TANK, HYDROPNEUMATIC TANK AND ELEVATED STORAGE TANK, REQUIRED BACTERIOLOGICAL SAMPLING AND OBTAINING LABORATORY RESULTS, COMPLETE IN PLACE	LS	1	\$2,000.00	\$2,000.00	\$5,000.00	\$5,000.00	\$6,000.00	\$6,000.00
2.	REPLACE INTERIOR ACCESS LADDER AND INSTALL SAFETY CLIMBING DEVICE FOR GROUND STORAGE TANK, COMPLETE IN PLACE	LS	1	\$9,000.00	\$9,000.00	\$5,700.00	\$5,700.00	\$7,000.00	\$7,000.00
SUBTOTAL MISCELLANEOUS ITEMS					\$11,000.00	\$10,700.00	\$10,700.00	\$13,000.00	\$13,000.00
BID SUMMARY									
SUBTOTAL BASE BID ITEMS					\$633,500.00	\$648,450.00	\$648,450.00	\$696,000.00	\$696,000.00
SUBTOTAL MISCELLANEOUS ITEMS					\$11,000.00	\$10,700.00	\$10,700.00	\$13,000.00	\$13,000.00
TOTAL AMOUNT BID					\$644,500.00	\$659,150.00	\$659,150.00	\$709,000.00	\$709,000.00