

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES
TO SERVE WOODFOREST SECTION 110
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 113
MONTGOMERY COUNTY, TEXAS
SEPTEMBER 18, 2026
LJA, INC.
A. HAMM
SEPTEMBER 18, 2026
1173-1114 (9.2)

BIDDER NAME	BASE BID	BASE BID PLUS ALTERNATE BID NO. 1 - INSTALLATION OF OWNER-PROVIDED WATER ITEMS	BASE BID PLUS ALTERNATE BID NO. 2 - WATER ITEMS
1) MTEX CONSTRUCTION, LLC	\$380,381.67	\$416,291.27	\$492,288.27
2) KENNETH LAMB CONSTRUCTION CO., LTD.	\$384,199.37	\$426,661.37	\$491,735.37
3) SOVREX, LLC	\$599,371.00	\$655,753.00	\$722,974.00

BASE BID CALENDAR DAYS - 35/50
BASE BID PLUS ALTERNATE BID NO. 1 CALENDAR DAYS - 50/65
BASE BID PLUS ALTERNATE BID NO. 2 CALENDAR DAYS - 50/65



A handwritten signature in blue ink, appearing to read "Sebastian Guio", written over a horizontal line.

I, Sebastian Guio, PE, hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES
TO SERVE WOODFOREST SECTION 110
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 113
MONTGOMERY COUNTY, TEXAS
SEPTEMBER 18, 2026
LJA, INC.
A. HAMM
SEPTEMBER 18, 2026
1173-1114 (9.2)

				1) MTEX CONSTRUCTION, LLC		2) KENNETH LAMB CONSTRUCTION CO., LTD.		3) SOVREX, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID SANITARY SEWER ITEMS									
1.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, ALL CUTS, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	1266	\$44.50	\$56,337.00	\$40.00	\$50,640.00	\$88.00	\$111,408.00
2.	SHORT SIDE SINGLE 6" PVC PIPE SERVICE LEAD, ASTM D-3034, SDR 26, INCLUDES PIPE, CEMENT STABILIZED SAND BACKFILL, DROP STRUCTURE, STACK, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ALL DEPTHS, COMPLETE IN PLACE	EA	6	\$1,400.00	\$8,400.00	\$1,416.00	\$8,496.00	\$1,200.00	\$7,200.00
3.	LONG SIDE DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEAD, ASTM D-2241, SDR 26, INCLUDES PIPE, CEMENT STABILIZED SAND BACKFILL, DROP STRUCTURE, STACK, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ALL DEPTHS, COMPLETE IN PLACE	LF	171	\$50.00	\$8,550.00	\$52.00	\$8,892.00	\$100.00	\$17,100.00
4.	TRENCH SAFETY SYSTEM FOR SANITARY SEWER, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	1437	\$2.00	\$2,874.00	\$1.00	\$1,437.00	\$1.00	\$1,437.00
5.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES ADJUSTMENTS, COMPLETE IN PLACE	EA	15	\$2,880.00	\$43,200.00	\$2,675.00	\$40,125.00	\$4,200.00	\$63,000.00
6.	EXTRA VERTICAL DEPTH FOR 4' DIAMETER SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	10	\$150.00	\$1,500.00	\$160.00	\$1,600.00	\$235.00	\$2,350.00
7.	CORE INTO EXISTING SANITARY SEWER MANHOLE AND CONNECT PROPOSED 8" SANITARY SEWER LINE, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$1,425.00	\$1,425.00	\$1,400.00	\$1,400.00	\$2,500.00	\$2,500.00
8.	DRY AUGER AND STEEL CASING FOR 8" SANITARY SEWER, INCLUDES CARRIER PIPE AND BORE PITS, ALL DEPTHS, COMPLETE IN PLACE	LF	71	\$325.00	\$23,075.00	\$315.00	\$22,365.00	\$295.00	\$20,945.00
9.	VIDEO INSPECTION OF SANITARY SEWER, ALL SIZES, INCLUDES DIGITAL COPY, COMPLETE IN PLACE	LF	1437	\$0.01	\$14.37	\$0.01	\$14.37	\$10.00	\$14,370.00
10.	DEWATERING FOR SANITARY SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	500	\$40.00	\$20,000.00	\$40.00	\$20,000.00	\$40.00	\$20,000.00
11.	SANITARY SEWER WET SAND CONSTRUCTION AS PER DETAILS AND RECOMMENDED BY GEOTECHNICAL ENGINEER, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	500	\$10.00	\$5,000.00	\$10.00	\$5,000.00	\$30.00	\$15,000.00
SUBTOTAL BASE BID SANITARY SEWER ITEMS					\$170,375.37		\$159,969.37		\$275,310.00
BASE BID DRAINAGE FACILITIES ITEMS									
1.	12" HDPE STORM SEWER, ASTM F-2306, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	54	\$35.00	\$1,890.00	\$40.00	\$2,160.00	\$75.00	\$4,050.00
2.	24" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	828	\$96.00	\$79,488.00	\$77.00	\$63,756.00	\$145.00	\$120,060.00
3.	30" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	31	\$112.00	\$3,472.00	\$106.00	\$3,286.00	\$175.00	\$5,425.00
4.	TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	873	\$2.00	\$1,746.00	\$1.00	\$873.00	\$1.00	\$873.00
5.	REINFORCED CONCRETE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	5	\$3,960.00	\$19,800.00	\$3,165.00	\$15,825.00	\$5,200.00	\$26,000.00
6.	BREAK INTO EXISTING STORM SEWER MANHOLE AND CONNECT PROPOSED 24" STORM SEWER, INCLUDES APPURTENANCES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$1,025.00	\$1,025.00	\$750.00	\$750.00	\$3,500.00	\$3,500.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES
TO SERVE WOODFOREST SECTION 110
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 113
MONTGOMERY COUNTY, TEXAS
SEPTEMBER 18, 2026
LJA, INC.
A. HAMM
SEPTEMBER 18, 2026
1173-1114 (9.2)

NO.	ITEM DESCRIPTION	UNIT	QTY	1) MTEX CONSTRUCTION, LLC		2) KENNETH LAMB CONSTRUCTION CO., LTD.		3) SOVREX, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
7.	REINFORCED CONCRETE TYPE "A" INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	7	\$3,135.00	\$21,945.00	\$3,000.00	\$21,000.00	\$3,800.00	\$26,600.00
8.	STAGE I - REINFORCED CONCRETE TYPE "C" INLET, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	3	\$1,415.00	\$4,245.00	\$1,500.00	\$4,500.00	\$4,100.00	\$12,300.00
9.	STAGE II - REINFORCED CONCRETE TYPE "C" INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	3	\$1,910.00	\$5,730.00	\$2,260.00	\$6,780.00	\$3,500.00	\$10,500.00
10.	12" CATCH BASIN (SKU#1200 OR SKU#1204) WITH 12" SQUARE GRATE, GREEN (SKU# 1212) WITH 6" UNIVERSAL LOCKING OUTLET (SKU# 1266) INCLUDE 12" CATCH BASIN FILTER, SKU 1200FF, BY N.D.S., COMPLETE IN PLACE	EA	1	\$525.00	\$525.00	\$860.00	\$860.00	\$800.00	\$800.00
11.	6' X 10' CHANNEL LOCK FOR 12" PVC STORM SEWER, INCLUDES 3:1 MIN SIDE SLOPE, EROSION PROTECTION STRUCTURE, AND GEOTEXTILE FABRIC, COMPLETE IN PLACE	SY	7	\$1,085.00	\$7,595.00	\$130.00	\$910.00	\$650.00	\$4,550.00
12.	REGRADE EXISTING DRAINAGE SWALE, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	1394	\$10.50	\$14,637.00	\$10.00	\$13,940.00	\$17.00	\$23,698.00
13.	DEWATERING FOR STORM SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	250	\$40.00	\$10,000.00	\$40.00	\$10,000.00	\$40.00	\$10,000.00
14.	STORM SEWER WET SAND CONSTRUCTION AS PER DETAILS AND RECOMMENDED BY GEOTECHNICAL ENGINEER, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	250	\$10.00	\$2,500.00	\$10.00	\$2,500.00	\$30.00	\$7,500.00
15.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	\$2,100.00	\$2,100.00	\$1,200.00	\$1,200.00	\$8,500.00	\$8,500.00
16.	AUGER, BORE AND JACK, OR TUNNEL FOR 24" RCP, (EXCLUDES LINE PIPE), INCLUDES BORE PITS, ALL DEPTHS, COMPLETE IN PLACE	LF	10	\$223.00	\$2,230.00	\$2,500.00	\$25,000.00	\$500.00	\$5,000.00
17.	AUGER, BORE AND JACK, OR TUNNEL FOR 30" RCP, (EXCLUDES LINE PIPE), INCLUDES BORE PITS, ALL DEPTHS, COMPLETE IN PLACE	LF	10	\$223.00	\$2,230.00	\$2,500.00	\$25,000.00	\$500.00	\$5,000.00
SUBTOTAL BASE BID DRAINAGE FACILITIES ITEMS					\$181,158.00		\$198,340.00		\$274,356.00
BASE BID MISCELLANEOUS ITEMS									
1.	EXTRA REINFORCED FILTER FABRIC FENCE, COMPLETE IN PLACE	LF	100	\$1.00	\$100.00	\$1.00	\$100.00	\$1.50	\$150.00
2.	EXTRA CLEARING & GRUBBING, COMPLETE IN PLACE	AC	0.5	\$5,000.00	\$2,500.00	\$5,000.00	\$2,500.00	\$6,000.00	\$3,000.00
3.	EXTRA CEMENT STABALIZED SAND BACKFILL, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00	\$85.00	\$8,500.00
4.	ADJUST EXISTING STORM SEWER MANHOLE RIM FLUSH WITH PROPOSED PAVEMENT, COMPLETE IN PLACE	EA	1	\$250.00	\$250.00	\$250.00	\$250.00	\$1,600.00	\$1,600.00
5.	WET SAND CONSTRUCTION AS PER DETAILS AND RECOMMENDED BY GEOTECHNICAL ENGINEER, ALL LINE SIZED AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LF	200	\$10.00	\$2,000.00	\$10.00	\$2,000.00	\$12.00	\$2,400.00
6.	HAUL AND DISPOSE OF UTILITY SPOILS TO DESIGNATED FILL AREAS OFFSITE, USING ON-ROAD TRUCKS (0-3.0 MILE), INCLUDES PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	LS	1	\$9,310.00	\$9,310.00	\$8,000.00	\$8,000.00	\$20,000.00	\$20,000.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES
TO SERVE WOODFOREST SECTION 110
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 113
MONTGOMERY COUNTY, TEXAS
SEPTEMBER 18, 2026
LJA, INC.
A. HAMM
SEPTEMBER 18, 2026
1173-1114 (9.2)

				1) MTEX CONSTRUCTION, LLC		2) KENNETH LAMB CONSTRUCTION CO., LTD.		3) SOVREX, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
7.	AC - EXTRA HYDROMULCH SEEDING AND FINE GRADING, INCLUDES WATERING, TO ACHIEVE 90% HOMOGENEOUS GRASS COVERAGE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	1	\$1,950.00	\$1,950.00	\$1,300.00	\$1,300.00	\$2,300.00	\$2,300.00
8.	REMOVE AND OFFSITE DISPOSAL OF EXISTING 8' WIDE CONCRETE SIDEWALK, COMPLETE IN PLACE	LF	67	\$34.90	\$2,338.30	\$20.00	\$1,340.00	\$50.00	\$3,350.00
9.	REMOVE AND OFFSITE DISPOSAL OF EXISTING ADA RAMP, COMPLETE IN PLACE	EA	1	\$800.00	\$800.00	\$800.00	\$800.00	\$255.00	\$255.00
10.	EXTRA ORANGE CONSTRUCTION FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	100	\$1.00	\$100.00	\$1.00	\$100.00	\$1.50	\$150.00
11.	DEWATERING, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	200	\$40.00	\$8,000.00	\$40.00	\$8,000.00	\$40.00	\$8,000.00
SUBTOTAL BASE BID MISCELLANEOUS ITEMS					\$28,848.30		\$25,890.00		\$49,705.00
ALTERNATE BID NO. 1 INSTALLATION OF OWNER-PROVIDED WATER ITEMS									
1.	INSTALLATION OF 1 1/2" SCHEDULE 40 PVC WATER LINE, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	181	\$16.00	\$2,896.00	\$15.00	\$2,715.00	\$20.00	\$3,620.00
2.	INSTALLATION OF 4" HDPE WATER LINE, C-906, DR 9, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	437	\$17.00	\$7,429.00	\$15.00	\$6,555.00	\$24.00	\$10,488.00
3.	INSTALLATION OF 6" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	310	\$17.00	\$5,270.00	\$15.00	\$4,650.00	\$25.00	\$7,750.00
4.	INSTALLATION OF 6" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	348	\$17.00	\$5,916.00	\$18.00	\$6,264.00	\$26.00	\$9,048.00
5.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	1276	\$0.10	\$127.60	\$3.00	\$3,828.00	\$1.00	\$1,276.00
6.	INSTALLATION OF 4" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	3	\$435.00	\$1,305.00	\$250.00	\$750.00	\$500.00	\$1,500.00
7.	INSTALLATION OF 6" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	5	\$419.00	\$2,095.00	\$275.00	\$1,375.00	\$800.00	\$4,000.00
8.	INSTALLATION OF FIRE HYDRANT UNIT, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	3	\$704.00	\$2,112.00	\$1,300.00	\$3,900.00	\$1,800.00	\$5,400.00
9.	INSTALLATION OF PVC TO HDPE ADAPTER (OWNER WILL PROVIDE ALL FITTINGS), COMPLETE IN PLACE.	EA	1	\$246.00	\$246.00	\$125.00	\$125.00	\$500.00	\$500.00
10.	INSTALLATION OF 14" X 6" TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	\$605.00	\$605.00	\$7,500.00	\$7,500.00	\$6,800.00	\$6,800.00
11.	INSTALLATION OF SHORT SIDE DOUBLE OR SINGLE SERVICE, WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	12	\$659.00	\$7,908.00	\$400.00	\$4,800.00	\$500.00	\$6,000.00
SUBTOTAL ALTERNATE BID NO. 1 INSTALLATION OF OWNER-PROVIDED WATER ITEMS					\$35,909.60		\$42,462.00		\$56,382.00
ALTERNATE BID NO. 2 WATER ITEMS									
1.	1 1/2" SCHEDULE 40 PVC WATER LINE, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	181	\$18.00	\$3,258.00	\$18.00	\$3,258.00	\$22.00	\$3,982.00
2.	4" HDPE WATER LINE, C-906, DR 9, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	437	\$22.00	\$9,614.00	\$27.00	\$11,799.00	\$39.00	\$17,043.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES
TO SERVE WOODFOREST SECTION 110
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 113
MONTGOMERY COUNTY, TEXAS
SEPTEMBER 18, 2026
LJA, INC.
A. HAMM
SEPTEMBER 18, 2026
1173-1114 (9.2)

				1) MTEX CONSTRUCTION, LLC		2) KENNETH LAMB CONSTRUCTION CO., LTD.		3) SOVREX, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
3.	6" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	310	\$42.00	\$13,020.00	\$46.00	\$14,260.00	\$47.00	\$14,570.00
4.	6" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	348	\$42.00	\$14,616.00	\$44.00	\$15,312.00	\$59.00	\$20,532.00
5.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	1276	\$0.10	\$127.60	\$1.00	\$1,276.00	\$1.00	\$1,276.00
6.	4" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	3	\$1,770.00	\$5,310.00	\$1,399.00	\$4,197.00	\$1,750.00	\$5,250.00
7.	6" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	5	\$2,025.00	\$10,125.00	\$1,662.00	\$8,310.00	\$1,850.00	\$9,250.00
8.	FIRE HYDRANT UNIT, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	3	\$7,413.00	\$22,239.00	\$7,520.00	\$22,560.00	\$7,100.00	\$21,300.00
9.	INSTALLATION OF PVC TO HDPE ADAPTER (OWNER WILL PROVIDE ALL FITTINGS), COMPLETE IN PLACE.	EA	1	\$246.00	\$246.00	\$148.00	\$148.00	\$500.00	\$500.00
10.	14" X 6" TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	\$10,527.00	\$10,527.00	\$8,500.00	\$8,500.00	\$15,500.00	\$15,500.00
11.	SHORT SIDE DOUBLE OR SINGLE SERVICE, WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	12	\$1,902.00	\$22,824.00	\$1,493.00	\$17,916.00	\$1,200.00	\$14,400.00
SUBTOTAL ALTERNATE BID NO. 2 WATER ITEMS					\$111,906.60		\$107,536.00		\$123,603.00
BID SUMMARY									
BASE BID SANITARY SEWER ITEMS					\$170,375.37		\$159,969.37		\$275,310.00
BASE BID DRAINAGE FACILITIES ITEMS					\$181,158.00		\$198,340.00		\$274,356.00
BASE BID MISCELLANEOUS ITEMS					\$28,848.30		\$25,890.00		\$49,705.00
TOTAL AMOUNT BASE BID					\$380,381.67		\$384,199.37		\$599,371.00
ALTERNATE BID NO. 1									
TOTAL AMOUNT BASE BID					\$380,381.67		\$384,199.37		\$599,371.00
INSTALLATION OF OWNER-PROVIDED WATER ITEMS					\$35,909.60		\$42,462.00		\$56,382.00
TOTAL ALTERNATE BID NO. 1 PLUS BASE BID					\$416,291.27		\$426,661.37		\$655,753.00
ALTERNATE BID NO. 2									
TOTAL AMOUNT BASE BID					\$380,381.67		\$384,199.37		\$599,371.00
WATER ITEMS					\$111,906.60		\$107,536.00		\$123,603.00
TOTAL ALTERNATE BID NO. 2 PLUS BASE BID					\$492,288.27		\$491,735.37		\$722,974.00