


BID TABULATION FOR:

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

CONSTRUCTION OF CLEARING AND GRUBBING  
TO SERVE LAKESIDE BAYOU PHASE 1  
GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 53  
CITY OF TEXAS CITY, GALVESTON COUNTY, TEXAS  
JANUARY 12, 2024  
LJA ENGINEERING, INC.  
S. YOUNG  
JANUARY 12, 2024  
1367-2910C (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) LONNIE LISCHKA COMPANY, LP	\$839,360.99
2) PLD CONSTRUCTION, LLC	\$957,476.00
3) ADVANCE SITE PREP LLC	\$1,049,207.00
4) GREAT BEAR CONSTRUCTION	\$1,163,171.00

CALENDAR DAYS 65/75



I, JORDAN IVES, P.E., hereby certify these bid tabulations to be true and correct.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF CLEARING AND GRUBBING  
 TO SERVE LAKESIDE BAYOU PHASE 1  
 GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 53  
 CITY OF TEXAS CITY, GALVESTON COUNTY, TEXAS  
 JANUARY 12, 2024  
 LJA ENGINEERING, INC.  
 S. YOUNG  
 JANUARY 12, 2024  
 1367-2910C (9.2)

				1) LONNIE LISCHKA COMPANY, LP		2) PLD CONSTRUCTION, LLC		3) ADVANCE SITE PREP LLC	
ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
CLEARING AND GRUBBING ITEMS									
1	CLEARING AND GRUBBING OF WOODED AREAS, INCLUDES REMOVING ALL STUMPS AND ROOTS, EXCAVATION OF BURN PITS (ONLY IN AREAS AS DIRECTED BY THE ENGINEER), BURNING OF CLEARED DEBRIS, HAULING OF ASHES OUTSIDE THE BOUNDARY OF THE LAKESIDE BAYOU DEVELOPMENT, CLEAN-OUT OF BURN PITS, AND BACKFILL OF BURN PITS TO 95% STANDARD PROCTOR DENSITY IN MAXIMUM 8" LIFTS, COMPLETE IN PLACE	AC	139	\$5,875.00	\$816,625.00	\$6,000.00	\$834,000.00	\$5,775.00	\$802,725.00
2	ADDITIONAL COST TO ITEM 1 FOR DISPOSAL OFFSITE OF CLEARED MATERIAL BY CHIP AND HAUL, TO BE USED ONLY IF BURNING IS NOT ALLOWABLE, IF CONTRACTOR IS REQUIRED TO CHIP AND HAUL THEY WILL BE PAID FOR BOTH ITEMS 1 AND 2, COMPLETE IN PLACE	AC	139	\$0.01	\$1.39	\$425.00	\$59,075.00	\$1,100.00	\$152,900.00
3	REINFORCED FILTER FABRIC FENCE, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	23460	\$0.01	\$234.60	\$1.85	\$43,401.00	\$2.70	\$63,342.00
4	INSTALLATION, MAINTENANCE AND REMOVAL OF STABILIZED CONSTRUCTION ENTRANCE, COMPLETE IN PLACE	EA	1	\$3,500.00	\$3,500.00	\$2,500.00	\$2,500.00	\$3,200.00	\$3,200.00
5	30 CY DUMPSTER FOR MISCELLANEOUS DEBRIS DISPOSAL OFFSITE, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	5	\$1,000.00	\$5,000.00	\$1,500.00	\$7,500.00	\$1,880.00	\$9,400.00
6	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	\$2,000.00	\$2,000.00	\$1,500.00	\$1,500.00	\$1,200.00	\$1,200.00
7	ALL REQUIRED CONSTRUCTION AND BURN PERMITS, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,500.00	\$1,500.00	\$150.00	\$150.00
8	CONSTRUCT TEMPORARY LOW WATER CROSSING AS SHOWN ON PLANS. CONTRACTOR RESPONSIBLE FOR REMOVING AND REPLACING DURING RAIN EVENTS AND RESPONSIBLE FOR REMOVAL UPON PROJECT COMPLETION, COMPLETE IN PLACE	EA	2	\$5,500.00	\$11,000.00	\$4,000.00	\$8,000.00	\$8,145.00	\$16,290.00
CLEARING AND GRUBBING ITEMS SUBTOTAL:					\$839,360.99		\$957,476.00		\$1,049,207.00
BIDDING SUMMARY									
SUBTOTAL CLEARING AND GRUBBING ITEMS					\$839,360.99		\$957,476.00		\$1,049,207.00
TOTAL AMOUNT BASE BID					\$839,360.99		\$957,476.00		\$1,049,207.00

**BID TABULATION FOR:**

CONSTRUCTION OF CLEARING AND GRUBBING  
TO SERVE LAKESIDE BAYOU PHASE 1  
GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 53  
CITY OF TEXAS CITY, GALVESTON COUNTY, TEXAS  
JANUARY 12, 2024  
LJA ENGINEERING, INC.  
S. YOUNG  
JANUARY 12, 2024  
1367-2910C (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

**4) GREAT BEAR CONSTRUCTION**

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>CLEARING AND GRUBBING ITEMS</b>					
1	CLEARING AND GRUBBING OF WOODED AREAS, INCLUDES REMOVING ALL STUMPS AND ROOTS, EXCAVATION OF BURN PITS (ONLY IN AREAS AS DIRECTED BY THE ENGINEER), BURNING OF CLEARED DEBRIS, HAULING OF ASHES OUTSIDE THE BOUNDARY OF THE LAKESIDE BAYOU DEVELOPMENT, CLEAN-OUT OF BURN PITS, AND BACKFILL OF BURN PITS TO 95% STANDARD PROCTOR DENSITY IN MAXIMUM 8" LIFTS, COMPLETE IN PLACE	AC	139	\$7,000.00	\$973,000.00
2	ADDITIONAL COST TO ITEM 1 FOR DISPOSAL OFFSITE OF CLEARED MATERIAL BY CHIP AND HAUL, TO BE USED ONLY IF BURNING IS NOT ALLOWABLE, IF CONTRACTOR IS REQUIRED TO CHIP AND HAUL THEY WILL BE PAID FOR BOTH ITEMS 1 AND 2, COMPLETE IN PLACE	AC	139	\$1,020.00	\$141,780.00
3	REINFORCED FILTER FABRIC FENCE, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	23460	\$1.50	\$35,190.00
4	INSTALLATION, MAINTENANCE AND REMOVAL OF STABILIZED CONSTRUCTION ENTRANCE, COMPLETE IN PLACE	EA	1	\$3,000.00	\$3,000.00
5	30 CY DUMPSTER FOR MISCELLANEOUS DEBRIS DISPOSAL OFFSITE, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	5	\$1,000.00	\$5,000.00
6	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00
7	ALL REQUIRED CONSTRUCTION AND BURN PERMITS, COMPLETE IN PLACE	EA	1	\$1.00	\$1.00
8	CONSTRUCT TEMPORARY LOW WATER CROSSING AS SHOWN ON PLANS. CONTRACTOR RESPONSIBLE FOR REMOVING AND REPLACING DURING RAIN EVENTS AND RESPONSIBLE FOR REMOVAL UPON PROJECT COMPLETION, COMPLETE IN PLACE	EA	2	\$2,000.00	\$4,000.00
<b>CLEARING AND GRUBBING ITEMS SUBTOTAL:</b>					<b>\$1,163,171.00</b>
<b>BIDDING SUMMARY</b>					
SUBTOTAL CLEARING AND GRUBBING ITEMS					\$1,163,171.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$1,163,171.00</b>