


BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES
TO SERVE LAKESIDE BAYOU SECTION 4
GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 53
CITY OF TEXAS CITY, GALVESTON COUNTY, TEXAS
FEBRUARY 8, 2024
LJA ENGINEERING, INC.
S. YOUNG
FEBRUARY 8, 2024
1367-2914 (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) PRECISE SERVICES INC.	\$1,089,154.00
2) PRINCIPAL PAVING CONTRACTORS, LTD.	\$1,147,767.00
3) TLC CONSTRUCTION CONTRACT SERVICES, INC.	\$1,543,264.00

CALENDAR DAYS 60/70



A handwritten signature in black ink, appearing to read "J. Ives", written over a horizontal line.

02/08/2024

I, JORDAN IVES, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES
 TO SERVE LAKESIDE BAYOU SECTION 4
 GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 53
 CITY OF TEXAS CITY, GALVESTON COUNTY, TEXAS
 FEBRUARY 8, 2024
 LJA ENGINEERING, INC.
 S. YOUNG
 FEBRUARY 8, 2024
 1367-2914 (9.2)

				1) PRECISE SERVICES INC.		2) PRINCIPAL PAVING CONTRACTORS, LTD.		3) TLC CONSTRUCTION CONTRACT SERVICES, INC.	
ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING IMPROVEMENTS									
1	ROADWAY EXCAVATION TO BE USED AS CURB BACKFILL, ROW FILL AND FRONT OF LOT FILL TO FINAL GRADE, INCLUDES STRIPPING, STOCKPILING AND RE-APPLICATION OF STRIPPINGS TO APPLICABLE AREAS, COMPLETE IN PLACE	CY	4637	\$6.00	\$27,822.00	\$7.00	\$32,459.00	\$25.00	\$115,925.00
2	6" LIME STABILIZED SUBGRADE MANIPULATION, COMPLETE IN PLACE	SY	13910	\$5.00	\$69,550.00	\$6.70	\$93,197.00	\$8.00	\$111,280.00
3	HYDRATED LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT, AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	368	\$325.00	\$119,600.00	\$330.00	\$121,440.00	\$386.00	\$142,048.00
4	6-INCH REINFORCED CONCRETE PAVING, COMPLETE IN PLACE	SY	12413	\$55.50	\$688,921.50	\$60.00	\$744,780.00	\$70.00	\$868,910.00
5	6-INCH REINFORCED CONCRETE CURB, INCLUDES TRANSITION TO 4-INCH CURB, COMPLETE IN PLACE	LF	2385	\$5.00	\$11,925.00	\$4.00	\$9,540.00	\$6.00	\$14,310.00
6	4-INCH X 12-INCH REINFORCED CONCRETE CURB, INCLUDES TRANSITION TO 6-INCH CURB, COMPLETE IN PLACE	LF	4198	\$5.00	\$20,990.00	\$4.00	\$16,792.00	\$6.00	\$25,188.00
7	STOP SIGNS WITH STREET NAMES, COMPLETE IN PLACE	EA	7	\$835.00	\$5,845.00	\$650.00	\$4,550.00	\$840.00	\$5,880.00
8	CONNECT PROPOSED CONCRETE PAVEMENT TO EXISTING CONCRETE PAVEMENT, COMPLETE IN PLACE	EA	2	\$1,250.00	\$2,500.00	\$1,500.00	\$3,000.00	\$986.00	\$1,972.00
9	PROPOSED PAVING HEADER, COMPLETE IN PLACE	LF	90	\$22.50	\$2,025.00	\$25.00	\$2,250.00	\$35.00	\$3,150.00
10	PROPOSED TYPE III BARRICADE, COMPLETE IN PLACE	EA	3	\$1,400.00	\$4,200.00	\$1,000.00	\$3,000.00	\$1,260.00	\$3,780.00
11	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$100.00	\$200.00	\$50.00	\$100.00	\$60.00	\$120.00
12	GRADING FOR RESERVES, COMPLETE IN PLACE	EA	4	\$1,100.00	\$4,400.00	\$300.00	\$1,200.00	\$1,443.00	\$5,772.00
13	GRADING FOR LOTS, COMPLETE IN PLACE	EA	92	\$235.00	\$21,620.00	\$300.00	\$27,600.00	\$1,443.00	\$132,756.00
14	WHEELCHAIR RAMPS, COMPLETE IN PLACE	EA	14	\$1,800.00	\$25,200.00	\$1,600.00	\$22,400.00	\$3,084.00	\$43,176.00
15	2-WAY REFLECTORIZED BLUE RAISED PAVEMENT MARKERS, COMPLETE IN PLACE	EA	7	\$20.00	\$140.00	\$10.00	\$70.00	\$18.00	\$126.00
16	QUADRUPL 3-INCH PVC ELECTRICAL CONDUIT, SCHEDULE 40 (GRAY), INCLUDES BENDS FITTINGS AND CEMENT STABILIZED SAND AT ALL PAVEMENT CROSSINGS, COMPLETE IN PLACE	LF	320	\$82.50	\$26,400.00	\$45.00	\$14,400.00	\$85.00	\$27,200.00
17	6-INCH PVC, SCHEDULE 40 (BLUE), INCLUDES BENDS FITTINGS AND CEMENT STABILIZED SAND AT ALL PAVEMENT CROSSINGS, COMPLETE IN PLACE	LF	320	\$55.00	\$17,600.00	\$40.00	\$12,800.00	\$67.00	\$21,440.00
PAVING IMPROVEMENTS SUBTOTAL:					\$1,048,938.50		\$1,109,578.00		\$1,523,033.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES
TO SERVE LAKESIDE BAYOU SECTION 4
GALVESTON COUNTY MUNICIPAL UTILITY DISTRICT NO. 53
CITY OF TEXAS CITY, GALVESTON COUNTY, TEXAS
FEBRUARY 8, 2024
LJA ENGINEERING, INC.
S. YOUNG
FEBRUARY 8, 2024
1367-2914 (9.2)

				1) PRECISE SERVICES INC.		2) PRINCIPAL PAVING CONTRACTORS, LTD.		3) TLC CONSTRUCTION CONTRACT SERVICES, INC.	
ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
MISCELLANEOUS ITEMS									
1	MAINTAIN, REMOVE AND DISPOSE OF STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$2,150.00	\$2,150.00	\$3,900.00	\$3,900.00
2	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$3,120.00	\$3,120.00
3	PERMANENT TRAFFIC CONTROL MARKERS & BUTTONS, COMPLETE IN PLACE	LS	1	\$2,250.00	\$2,250.00	\$2,500.00	\$2,500.00	\$3,600.00	\$3,600.00
4	ALL REQUIRED TEXAS CITY CONSTRUCTION PERMITS, COMPLETE IN PLACE	LS	1	\$21,800.00	\$21,800.00	\$22,800.00	\$22,800.00	\$4,800.00	\$4,800.00
5	CONCRETE TRUCK WASHOUT, INCLUDING INSTALLATION, MAINTENANCE, AND REMOVAL, COMPELTE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$2,500.00	\$2,500.00	\$780.00	\$780.00
6	18" CONCRETE RIP RAP ON EXISTING CHANNEL SIDE SLOPE, INCLUDES GEOTEXTILE FABRIC, AS SHOWN ON PLANS, COMPLETE IN PLACE	SY	16	\$180.00	\$2,880.00	\$125.00	\$2,000.00	\$125.00	\$2,000.00
7	REGRADE EXISTING BACK OF LOT SWALE, AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	LF	677	\$11.50	\$7,785.50	\$7.00	\$4,739.00	\$3.00	\$2,031.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$40,215.50		\$38,189.00		\$20,231.00
BIDDING SUMMARY									
SUBTOTAL PAVING IMPROVEMENTS					\$1,048,938.50		\$1,109,578.00		\$1,523,033.00
SUBTOTAL MISCELLANEOUS ITEMS					\$40,215.50		\$38,189.00		\$20,231.00
TOTAL AMOUNT BASE BID					\$1,089,154.00		\$1,147,767.00		\$1,543,264.00