


**BID TABULATION FOR:**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
TO SERVE POLLARD BOULEVARD PHASE 2  
BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
MARCH 11, 2020  
LJA ENGINEERING, INC.  
J. RIVERA  
MARCH 11, 2020  
1406-3819C (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

BIDDER'S NAME	TOTAL BID AMOUNT	TOTAL AMOUNT BID INCL. ALTERNATE
1) PRECISE SERVICES, INC.	\$520,008.37	\$613,173.02
2) TRIPLE B SERVICES, LLP	\$520,613.45	\$583,661.45
3) DURWOOD GREENE CONSTRUCTION CO.	\$544,601.50	\$615,171.50
4) HARRIS CONSTRUCTION COMPANY, LTD	\$671,215.75	\$767,456.75

CALENDAR DAYS - 30/40



3/13/2020

I, Everett Deao, P.E., hereby certify these bid tabulations to be true and correct.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE POLLARD BOULEVARD PHASE 2  
 BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
 CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
 MARCH 11, 2020  
 LJA ENGINEERING, INC.  
 J. RIVERA  
 MARCH 11, 2020  
 1406-3819C (9.2)

ITEM DESCRIPTION	UNIT	QTY	1) PRECISE SERVICES, INC.		2) TRIPLE B SERVICES, LLP		3) DURWOOD GREENE CONSTRUCTION CO.		
			UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	
<b>PAVING IMPROVEMENT ITEMS</b>									
1. 7" REINFORCED CONCRETE PAVEMENT, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	5,667	\$48.75	\$276,266.25	\$48.40	\$274,282.80	\$50.00	\$283,350.00	
2. 8" LIME STABILIZED SUB-GRADE (MANIPULATION), COMPLETE IN PLACE	SY	6,185	\$1.50	\$9,277.50	\$3.00	\$18,555.00	\$3.00	\$18,555.00	
3. HYDRATED LIME FOR 8" STABILIZED SUB-GRADE (\$3 LBS/SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	162	\$250.00	\$40,500.00	\$180.00	\$29,160.00	\$200.00	\$32,400.00	
4. PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00	\$2,000.00	\$2,000.00	
5. 4' REINFORCED CONCRETE SIDEWALK, 4 1/2" THICK, COMPLETE IN PLACE	LF	22	\$66.00	\$1,452.00	\$5.70	\$125.40	\$24.00	\$528.00	
6. 12' REINFORCED CONCRETE SIDEWALK, 4 1/2" THICK, COMPLETE IN PLACE	LF	1,754	\$53.00	\$92,962.00	\$68.00	\$119,272.00	\$63.00	\$110,502.00	
7. WHEELCHAIR RAMPS FOR 12' REINFORCED CONCRETE SIDEWALK, PER DETAIL IN CONSTRUCTION PLANS, COMPLETE IN PLACE	EA	4	\$4,750.00	\$19,000.00	\$3,000.00	\$12,000.00	\$4,000.00	\$16,000.00	
8. WHEELCHAIR RAMPS FOR 4' REINFORCED CONCRETE SIDEWALK, PER DETAIL IN CONSTRUCTION PLANS, COMPLETE IN PLACE	EA	2	\$1,800.00	\$3,600.00	\$2,000.00	\$4,000.00	\$1,800.00	\$3,600.00	
9. PERMANENT TRAFFIC CONTROL SIGNS, INCLUDING STOP SIGNS, WITH STREET NAMES, DIRECTIONAL SIGNS WITH SUPPLEMENTS, ETC., COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$450.00	\$450.00	\$800.00	\$800.00	
10. PAVING HEADER, PER DETAIL TO INCLUDED THE EXTENSION OF REINFORCING STEEL 15" PAST EDGE OF CONCRETE, REINFORCING STEEL THAT IS EXTENDED IS TO BE COATED IN ASPHALT AND WRAPPED IN BURLAP, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	50	\$15.00	\$750.00	\$15.00	\$750.00	\$25.00	\$1,250.00	
11. CONNECT PROPOSED PAVEMENT TO EXISTING PAVEMENT HEADER, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	3	\$740.00	\$2,220.00	\$375.00	\$1,125.00	\$1,500.00	\$4,500.00	
12. ROADWAY & LOT EXCAVATION, TO INCLUDE STRIPPING & PROOFROLLING, COMPLETE IN PLACE	CY	979	\$4.00	\$3,916.00	\$4.35	\$4,258.65	\$6.00	\$5,874.00	
13. ROADWAY, R.O.W. LOTS AND RESERVES FILL, (IN PLACE) TO INCLUDE STRIPPING & PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS, COMPLETE IN PLACE	CY	979	\$3.00	\$2,937.00	\$6.00	\$5,874.00	\$6.00	\$5,874.00	
14. TYPE III BARRICADE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	2	\$900.00	\$1,800.00	\$850.00	\$1,700.00	\$1,600.00	\$3,200.00	
15. REMOVE AND DISPOSE OF TYPE III BARRICADE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	2	\$100.00	\$200.00	\$55.00	\$110.00	\$200.00	\$400.00	
16. 2' SAWCUT, REMOVAL AND OFFSITE DISPOSAL OF EXISTING 7" CONCRETE PAVEMENT, EXPOSE, CLEAN AND TIE EXISTING REBAR INTO PROPOSED 7" CONCRETE PAVEMENT, TO INCLUDE ANY BARRELS OR TRAFFIC CONTROL FOR CONNECTING TO PROPOSED PAVEMENT, COMPLETE IN PLACE	LF	140	\$25.00	\$3,500.00	\$8.70	\$1,218.00	\$40.00	\$5,600.00	
17. 6" REINFORCED CONCRETE PAVEMENT FOR LIFT STATION ACCESS ROAD, COMPLETE IN PLACE	SY	83	\$65.00	\$5,395.00	\$41.80	\$3,469.40	\$48.00	\$3,984.00	
18. 6" REINFORCED CONCRETE PAVEMENT FOR PROPOSED DRIVEWAYS 4 & 5, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	202	\$82.50	\$16,665.00	\$61.00	\$12,322.00	\$48.00	\$9,696.00	
19. 8" LIME STABILIZED SUB-GRADE FOR PROPOSED DRIVEWAY 4&5 (MANIPULATION), COMPLETE IN PLACE	SY	242	\$16.00	\$3,872.00	\$3.00	\$726.00	\$10.00	\$2,420.00	
20. HYDRATED LIME FOR 8" STABILIZED SUBGRADE (\$3 LBS/SY) FOR PROPOSED DRIVEWAY 4 & 5 AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TONS	7	\$0.01	\$0.07	\$180.00	\$1,260.00	\$200.00	\$1,400.00	

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE POLLARD BOULEVARD PHASE 2  
 BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
 CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
 MARCH 11, 2020  
 LJA ENGINEERING, INC.  
 J. RIVERA  
 MARCH 11, 2020  
 1406-3819C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) PRECISE SERVICES, INC.		2) TRIPLE B SERVICES, LLP		3) DURWOOD GREENE CONSTRUCTION CO.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
21.	2' SAWCUT, REMOVAL AND OFFSITE DISPOSAL OF EXISTING 6" CONCRETE PAVEMENT, EXPOSE, CLEAN AND TIE EXISTING REBAR INTO PROPOSED 6" CONCRETE PAVMENT, TO INCLUDE ANY BARRELS OR TRAFFIC CONTROL FOR CONNECTING TO PROPOSED PAVEMENT, COMPLETE IN PLACE	LF	156	\$15.00	\$2,340.00	\$8.70	\$1,357.20	\$40.00	\$6,240.00
<b>SUBTOTAL PAVING IMPROVEMENT ITEMS</b>					<b>\$488,152.82</b>		<b>\$493,015.45</b>		<b>\$518,173.00</b>
<b>MISCELLANEOUS ITEMS</b>									
1.	STORMWATER POLLUTION PREVENTION PLAN COMPLIANCE, INSPECTIONS, MAINTENANCE OF ENTRANCE AND FENCE, NOI, NOT AND ALL OTHER ITEMS NOT SPECIFICALLY LISTED ABOVE, COMPLETE IN PLACE	LS	1	\$1,900.00	\$1,900.00	\$900.00	\$900.00	\$1,500.00	\$1,500.00
2.	DUAL 6" IRRIGATION SLEEVES, PVC SCHEDULE 40, TO INCLUDE BEND RISER AND MARKER, COMPLETE IN PLACE	LF	232	\$30.00	\$6,960.00	\$47.00	\$10,904.00	\$32.00	\$7,424.00
3.	INSTALL AND MAINTAIN REINFORCED FILTER FABRIC FENCE ALONG BACK OF CURB (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	3,476	\$1.60	\$5,561.60	\$1.25	\$4,345.00	\$1.25	\$4,345.00
4.	INSTALL AND MAINTAIN FILTER FABRIC FENCE ALONG BOUNDARY BEFORE CONSTRUCTION STARTS (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	1,722	\$1.60	\$2,755.20	\$1.00	\$1,722.00	\$1.00	\$1,722.00
5.	STABILIZED CONSTRUCTION EXIT, INSTALLATION, MAINTENANCE, AND REMOVAL (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00
6.	STAGE II - INLET PROTECTION BARRIERS, (PER CITY OF MANVEL DETAIL) PROPOSED AND EXISTING INLETS, COMPLETE IN PLACE	EA	14	\$60.00	\$840.00	\$60.00	\$840.00	\$60.00	\$840.00
7.	HYDROMULCH SEEDING, FINE GRADING AND WATERING (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	AC	1.4	\$1,650.00	\$2,310.00	\$1,200.00	\$1,680.00	\$1,200.00	\$1,680.00
8.	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$650.00	\$650.00	\$1,000.00	\$1,000.00	\$1,500.00	\$1,500.00
9.	24" WIDE BERMUDA SOD STRIP TO BE PLACED BEHIND BACK OF CURB (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	3,435	\$2.25	\$7,728.75	\$1.20	\$4,122.00	\$0.50	\$1,717.50
10.	TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT (AS DIRECTED BY THE ENGINEER), TO INCLUDE INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$1,250.00	\$1,250.00	\$885.00	\$885.00	\$4,500.00	\$4,500.00
<b>SUBTOTAL MISCELLANEOUS ITEMS</b>					<b>\$31,855.55</b>		<b>\$27,598.00</b>		<b>\$26,428.50</b>
<b>PAVING IMPROVEMENT ALTERNATE ITEMS (DRIVEWAYS 1 - 3) ITEMS</b>									
1.	ADDITIONAL 7" REINFORCED CONCRETE PAVEMENT FOR PROPOSED DRIVEWAYS 1 -3, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	502	\$96.25	\$48,317.50	\$74.00	\$37,148.00	\$52.00	\$26,104.00
2.	ADDITIONAL 8" SUB-GRADE (MANIPULATED) FOR PROPOSED DRIVEWAYS 1 - 3, COMPLETE IN PLACE	SY	582	\$16.00	\$9,312.00	\$3.00	\$1,746.00	\$8.00	\$4,656.00
3.	ADDITIONAL HYDRATED LIME FOR 8" STABILIZED SUB-GRADE (53 LBS/SY) FOR PROPOSED DRIVEWAYS 1 - 3 AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TONS	15	\$0.01	\$0.15	\$180.00	\$2,700.00	\$200.00	\$3,000.00
4.	ADDITIONAL WHEELCHAIR RAMPS FOR 12" REINFORCED CONCRETE SIDEWALKS, PER DETAIL IN CONSTRUCTION PLANS, COMPLETE IN PLACE	EA	6	\$4,750.00	\$28,500.00	\$3,000.00	\$18,000.00	\$4,000.00	\$24,000.00
5.	REMOVAL AND OFFSITE DISPOSAL OF EXISTING 12' SIDEWALK, COMPLETE IN PLACE	LF	105	\$25.00	\$2,625.00	\$11.00	\$1,155.00	\$10.00	\$1,050.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE POLLARD BOULEVARD PHASE 2  
 BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
 CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
 MARCH 11, 2020  
 LJA ENGINEERING, INC.  
 J. RIVERA  
 MARCH 11, 2020  
 1406-3819C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) PRECISE SERVICES, INC.		2) TRIPLE B SERVICES, LLP		3) DURWOOD GREENE CONSTRUCTION CO.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
6.	ADDITIONAL 2" SAWCUT, REMOVAL AND OFFSITE DISPOSAL OF EXISTING 7" CONCRETE PAVEMENT, EXPOSE, CLEAN AND TIE EXISTING REBAR INTO PROPOSED 7" CONCRETE PAVEMENT, TO INCLUDE ANY BARRELS OR TRAFFIC CONTROL FOR CONNECTING TO PROPOSED PAVEMENT, COMPLETE IN PLACE	LF	294	\$15.00	\$4,410.00	\$8.50	\$2,499.00	\$40.00	\$11,760.00
<b>SUBTOTAL PAVING IMPROVEMENT ALTERNATE ITEMS (DRIVEWAYS 1 - 3) ITEMS</b>					<b>\$93,164.65</b>	<b>\$63,248.00</b>			<b>\$70,570.00</b>
<b>BID SUMMARY</b>									
SUBTOTAL PAVING IMPROVEMENT ITEMS					\$488,152.82	\$493,015.45			\$518,173.00
SUBTOTAL MISCELLANEOUS ITEMS					\$31,855.55	\$27,598.00			\$26,428.50
<b>TOTAL AMOUNT BID</b>					<b>\$520,008.37</b>	<b>\$520,613.45</b>			<b>\$544,601.50</b>
<b>ALTERNATE BID</b>									
<b>TOTAL AMOUNT BID</b>					<b>\$520,008.37</b>	<b>\$520,613.45</b>			<b>\$544,601.50</b>
SUBTOTAL PAVING IMPROVEMENTS ALTERNATE ITEMS (DRIVEWAYS 1 - 3)					\$93,164.65	\$63,248.00			\$70,570.00
<b>TOTAL AMOUNT BID INCLUDING ALTERNATE BID</b>					<b>\$613,173.02</b>	<b>\$583,861.45</b>			<b>\$615,171.50</b>

LJA Engineering, Inc.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE POLLARD BOULEVARD PHASE 2  
 BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
 CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
 MARCH 11, 2020  
 LJA ENGINEERING, INC.  
 J. RIVERA  
 MARCH 11, 2020  
 1406-3819C (9.2)

4) HARRIS CONSTRUCTION COMPANY, LTD

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>PAVING IMPROVEMENT ITEMS</b>					
1.	7" REINFORCED CONCRETE PAVEMENT, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	5,667	\$54.00	\$306,018.00
2.	8" LIME STABILIZED SUB-GRADE (MANIPULATION), COMPLETE IN PLACE	SY	6,185	\$2.90	\$17,936.50
3.	HYDRATED LIME FOR 8" STABILIZED SUB-GRADE (53 LBS/SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	162	\$245.00	\$39,690.00
4.	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$3,925.00	\$3,925.00
5.	4' REINFORCED CONCRETE SIDEWALK, 4 1/2" THICK, COMPLETE IN PLACE	LF	22	\$30.00	\$660.00
6.	12' REINFORCED CONCRETE SIDEWALK, 4 1/2" THICK, COMPLETE IN PLACE	LF	1,754	\$100.00	\$175,400.00
7.	WHEELCHAIR RAMPS FOR 12' REINFORCED CONCRETE SIDEWALK, PER DETAIL IN CONSTRUCTION PLANS, COMPLETE IN PLACE	EA	4	\$3,350.00	\$13,400.00
8.	WHEELCHAIR RAMPS FOR 4' REINFORCED CONCRETE SIDEWALK, PER DETAIL IN CONSTRUCTION PLANS, COMPLETE IN PLACE	EA	2	\$1,500.00	\$3,000.00
9.	PERMANENT TRAFFIC CONTROL SIGNS, INCLUDING STOP SIGNS, WITH STREET NAMES, DIRECTIONAL SIGNS WITH SUPPLEMENTS, ETC., COMPLETE IN PLACE	EA	1	\$995.00	\$995.00
10.	PAVING HEADER, PER DETAIL TO INCLUDE THE EXTENSION OF REINFORCING STEEL 15" PAST EDGE OF CONCRETE, REINFORCING STEEL THAT IS EXTENDED IS TO BE COATED IN ASPHALT AND WRAPPED IN BURLAP, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	50	\$8.00	\$400.00
11.	CONNECT PROPOSED PAVEMENT TO EXISTING PAVEMENT HEADER, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	3	\$1,500.00	\$4,500.00
12.	ROADWAY & LOT EXCAVATION, TO INCLUDE STRIPPING & PROOFROLLING, COMPLETE IN PLACE	CY	979	\$5.00	\$4,895.00
13.	ROADWAY, R.O.W. LOTS AND RESERVES FILL (IN PLACE) TO INCLUDE STRIPPING & PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS, COMPLETE IN PLACE	CY	979	\$5.00	\$4,895.00
14.	TYPE III BARRICADE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	2	\$1,100.00	\$2,200.00
15.	REMOVE AND DISPOSE OF TYPE III BARRICADE, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	2	\$200.00	\$400.00
16.	2' SAWCUT, REMOVAL AND OFFSITE DISPOSAL OF EXISTING 7" CONCRETE PAVEMENT, EXPOSE, CLEAN AND TIE EXISTING REBAR INTO PROPOSED 7" CONCRETE PAVEMENT, TO INCLUDE ANY BARRELS OR TRAFFIC CONTROL FOR CONNECTING TO PROPOSED PAVEMENT, COMPLETE IN PLACE	LF	140	\$45.00	\$6,300.00
17.	6" REINFORCED CONCRETE PAVEMENT FOR LIFT STATION ACCESS ROAD, COMPLETE IN PLACE	SY	83	\$254.25	\$21,102.75
18.	6" REINFORCED CONCRETE PAVEMENT FOR PROPOSED DRIVEWAYS 4 & 5, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	202	\$58.50	\$11,817.00
19.	8" LIME STABILIZED SUB-GRADE FOR PROPOSED DRIVEWAY 4&5 (MANIPULATION), COMPLETE IN PLACE	SY	242	\$21.75	\$5,263.50
20.	HYDRATED LIME FOR 8" STABILIZED SUBGRADE (53 LBS/SY) FOR PROPOSED DRIVEWAY 4 & 5 AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TONS	7	\$325.00	\$2,275.00

**BID TABULATION FOR:**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE POLLARD BOULEVARD PHASE 2  
 BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
 CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
 MARCH 11, 2020  
 LJA ENGINEERING, INC.  
 J. RIVERA  
 MARCH 11, 2020  
 1406-3819C (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

4) HARRIS CONSTRUCTION COMPANY, LTD

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
21.	2' SAWCUT, REMOVAL AND OFFSITE DISPOSAL OF EXISTING 6" CONCRETE PAVEMENT, EXPOSE, CLEAN AND TIE EXISTING REBAR INTO PROPOSED 6" CONCRETE PAVMENT, TO INCLUDE ANY BARRELS OR TRAFFIC CONTROL FOR CONNECTING TO PROPOSED PAVEMENT, COMPLETE IN PLACE	LF	158	\$38.00	\$5,928.00
<b>SUBTOTAL PAVING IMPROVEMENT ITEMS</b>					<b>\$631,000.75</b>
<b>MISCELLANEOUS ITEMS</b>					
1.	STORMWATER POLLUTION PREVENTION PLAN COMPLIANCE, INSPECTIONS, MAINTENANCE OF ENTRANCE AND FENCE, NOI, NOT AND ALL OTHER ITEMS NOT SPECIFICALLY LISTED ABOVE, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00
2.	DUAL 6" IRRIGATION SLEEVES, PVC SCHEDULE 40, TO INCLUDE BEND RISER AND MARKER, COMPLETE IN PLACE	LF	232	\$24.00	\$5,568.00
3.	INSTALL AND MAINTAIN REINFORCED FILTER FABRIC FENCE ALONG BACK OF CURB (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	3,478	\$1.25	\$4,345.00
4.	INSTALL AND MAINTAIN FILTER FABRIC FENCE ALONG BOUNDARY BEFORE CONSTRUCTION STARTS (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	1,722	\$1.00	\$1,722.00
5.	STABILIZED CONSTRUCTION EXIT, INSTALLATION, MAINTENANCE, AND REMOVAL (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,200.00	\$1,200.00
6.	STAGE II - INLET PROTECTION BARRIERS, (PER CITY OF MANVEL DETAIL) PROPOSED AND EXISTING INLETS, COMPLETE IN PLACE	EA	14	\$60.00	\$840.00
7.	HYDROMULCH SEEDING, FINE GRADING AND WATERING (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	AC	1.4	\$4,000.00	\$5,600.00
8.	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00
9.	24" WIDE BERMUDA SOD STRIP TO BE PLACED BEHIND BACK OF CURB (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	3,435	\$4.00	\$13,740.00
10.	TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT (AS DIRECTED BY THE ENGINEER), TO INCLUDE INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00
<b>SUBTOTAL MISCELLANEOUS ITEMS</b>					<b>\$40,215.00</b>
<b>PAVING IMPROVEMENT ALTERNATE ITEMS (DRIVEWAYS 1 - 3) ITEMS</b>					
1.	ADDITIONAL 7" REINFORCED CONCRETE PAVEMENT FOR PROPOSED DRIVEWAYS 1 -3, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	502	\$82.00	\$41,164.00
2.	ADDITIONAL 8" SUB-GRADE (MANIPULATED) FOR PROPOSED DRIVEWAYS 1 - 3, COMPLETE IN PLACE	SY	582	\$24.75	\$14,404.50
3.	ADDITIONAL HYDRATED LIME FOR 8" STABILIZED SUB-GRADE (53 LBS/SY) FOR PROPOSED DRIVEWAYS 1 - 3 AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TONS	15	\$325.00	\$4,875.00
4.	ADDITIONAL WHEELCHAIR RAMPS FOR 12' REINFORCED CONCRETE SIDEWALKS, PER DETAIL IN CONSTRUCTION PLANS, COMPLETE IN PLACE	EA	6	\$3,350.00	\$20,100.00
5.	REMOVAL AND OFFSITE DISPOSAL OF EXISTING 12' SIDEWALK, COMPLETE IN PLACE	LF	105	\$37.50	\$3,937.50

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
TO SERVE POLLARD BOULEVARD PHASE 2  
BRAZORIA COUNTY MUNICIPAL UTILITY DISTRICT NO. 66  
CITY OF MANVEL, BRAZORIA COUNTY, TEXAS  
MARCH 11, 2020  
LJA ENGINEERING, INC.  
J. RIVERA  
MARCH 11, 2020  
1406-3819C (9.2)

4) HARRIS CONSTRUCTION COMPANY, LTD

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
6.	ADDITIONAL 2' SAWCUT, REMOVAL AND OFFSITE DISPOSAL OF EXISTING 7" CONCRETE PAVEMENT, EXPOSE, CLEAN AND TIE EXISTING REBAR INTO PROPOSED 7" CONCRETE PAVEMENT, TO INCLUDE ANY BARRIELS OR TRAFFIC CONTROL FOR CONNECTING TO PROPOSED PAVEMENT, COMPLETE IN PLACE	LF	294	\$40.00	\$11,760.00
<b>SUBTOTAL PAVING IMPROVEMENT ALTERNATE ITEMS (DRIVEWAYS 1 - 3) ITEMS</b>					<b>\$96,241.00</b>
<b>BID SUMMARY</b>					
SUBTOTAL PAVING IMPROVEMENT ITEMS					\$631,000.75
SUBTOTAL MISCELLANEOUS ITEMS					\$40,215.00
<b>TOTAL AMOUNT BID</b>					<b>\$671,215.75</b>
<u>ALTERNATE BID</u>					
<b>TOTAL AMOUNT BID</b>					<b>\$671,215.75</b>
SUBTOTAL PAVING IMPROVEMENTS ALTERNATE ITEMS (DRIVEWAYS 1 - 3)					\$96,241.00
<b>TOTAL AMOUNT BID INCLUDING ALTERNATE BID</b>					<b>\$767,456.75</b>

LJA Engineering, Inc.