

BID TABULATION FOR:


CONSTRUCTION OF THE ROADWAY CONSTRUCTION  
TO SERVE SIENNA PLANTATION SECTION 12  
SIENNA MUNICIPAL UTILITY DISTRICT NO. 4  
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
SEPTEMBER 17, 2021  
LJA ENGINEERING, INC.  
C. DURHAM  
SEPTEMBER 20, 2021  
1414-0200 (9.2)

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID
1) INFRASTRUCTURE CONSTRUCTION SERVICES	\$88,005.00

CALENDAR DAYS 30/40

*Amanda Carriage*  
\_\_\_\_\_  
Amanda Carriage, P.E., hereby certify these bid tabulations to be true and correct.



*Amanda Carriage*  
*9/27/21*

LJA Engineering, Inc.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE ROADWAY CONSTRUCTION  
 TO SERVE SIENNA PLANTATION SECTION 12  
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 4  
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
 SEPTEMBER 17, 2021  
 LJA ENGINEERING, INC.  
 C. DURHAM  
 SEPTEMBER 20, 2021  
 1414-0200 (9.2)

1) INFRASTRUCTURE CONSTRUCTION SERVICES

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>SIENNA PLANTATION SECTION 12 (SIENNA MUD NO. 4)</b>					
1	MOBILIZATION, COMPLETE IN PLACE	LS	1	\$2,100.00	\$2,100.00
2	REPAIR EXISTING BIRD BATH BY GRINDING THROUGHOUT THE SECTION (AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	40	\$65.00	\$2,600.00
3	REPAIR INLET, COMPLETE IN PLACE	EA	4	\$1,100.00	\$4,400.00
4	REMOVE AND REPLACE BROKEN 6" OR 4" X 12" REINFORCED CONCRETE CURB THROUGHOUT THE SECTION, COMPLETE IN PLACE	LF	130	\$38.50	\$5,005.00
5	SEAL SURFACE CRACKS THROUGHOUT SECTION USING FORT BEND COUNTY APPROVED GRAVITY FEED EUCLID 355, COMPLETE IN PLACE	LF	825	\$8.00	\$6,600.00
6	CLEAN AND SEAL EXPANSION JOINTS THROUGHOUT SECTION WITH MASTIC, COMPLETE IN PLACE	LF	100	\$10.00	\$1,000.00
7	RESTRIPE ENTIRE SECTION AS PER TRAFFIC CONTROL PLAN, COMPLETE IN PLACE	EA	8	\$450.00	\$3,600.00
8	FURNISH AND INSTALL RAISED PAVEMENT MARKERS THROUGHOUT, COMPLETE IN PLACE	EA	90	\$9.00	\$810.00
9	INSTALL CURB EAR, COMPLETE IN PLACE	EA	1	\$300.00	\$300.00
10	REMOVAL AND DISPOSE OF CONCRETE PAVEMENT SECTION, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER) AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF CONCRETE PAVEMENT, INCLUDING ALL NECESSARY DOWEL, ONLY TO BE USED IN LIEU OF ITEM NO. 2, COMPLETE IN PLACE	SY	140	\$220.00	\$30,800.00
11	REMOVE AND REPLACE WHEEL CHAIR RAMP, COMPLETE IN PLACE	EA	10	\$1,950.00	\$19,500.00
12	REMOVE AND REPLACE EXISTING SIDEWALK FOR WHEEL CHAIR RAMP, COMPLETE IN PLACE	SY	56	\$115.00	\$6,440.00
13	INSPECTION WATER PROVIDED BY OTHERS, INCLUDES FLOODING STREETS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	EA	1	\$450.00	\$450.00
14	REMOVE CONCRETE SPILLS THROUGHOUT, COMPLETE IN PLACE	EA	1	\$750.00	\$750.00
15	TEMPORARY TRAFFIC CONTROL, COMPLETE IN PLACE	EA	1	\$2,650.00	\$2,650.00
16	FORT BEND COUNTY RE-INSPECTION FEE, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00
<b>SIENNA PLANTATION SECTION 12 (SIENNA MUD NO. 4) SUBTOTAL:</b>					<b>\$88,005.00</b>
<b><u>BIDDING SUMMARY</u></b>					
<b>SUBTOTAL SIENNA PLANTATION SECTION 12 (SIENNA MUD NO. 4)</b>					<b>\$88,005.00</b>
<b>TOTAL AMOUNT BASE BID</b>					<b>\$88,005.00</b>