

BID TABULATION FOR:


CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 19
SIENNA MUNICIPAL UTILITY DISTRICT NO. 4
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
SEPTEMBER 2, 2021
LJA ENGINEERING, INC.
D. FORREST
SEPTEMBER 2, 2021
1414-1519P (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID	BID INCLUDING ALTERNATE BID NO. 1 - FIELD CONDITIONS ITEMS
1) R CONSTRUCTION CIVIL	\$939,810.00	\$1,023,440.00
2) MH2 CONSTRUCTION SERVICES, LLC	\$965,979.84	\$1,049,609.84
3) NORTHTEX CONSTRUCTION, LLC.	\$1,020,143.55	\$1,103,773.55
4) HARRIS CONSTRUCTION COMPANY, LLC	\$1,051,354.30	\$1,134,984.30
5) TRIPLE B SERVICES, LLP	\$1,075,352.35	\$1,203,553.85
6) DACO PAVING, INC.	\$1,120,220.70	\$1,252,623.70

CALENDAR DAYS - 60/70

for Scott Frankovich
I, Amanda Carriage, P.E., hereby certify these bid tabulations to be true and correct



Scott Frankovich
9/2/2021

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 19
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 4
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 SEPTEMBER 2, 2021
 LJA ENGINEERING, INC.
 D. FORREST
 SEPTEMBER 2, 2021
 1414-1519P (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) R CONSTRUCTION CIVIL		2) MH2 CONSTRUCTION SERVICES, LLC		3) NORTHTEX CONSTRUCTION, LLC.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 4)									
1	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GENE BAKER, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$5,263.00	\$5,263.00	\$5,263.00	\$5,263.00	\$5,263.00	\$5,263.00
2	6" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	11830	\$46.00	\$544,180.00	\$51.88	\$613,740.40	\$50.50	\$597,415.00
3	7" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	460	\$58.00	\$26,680.00	\$54.88	\$25,244.80	\$56.00	\$25,780.00
4	4" X 12" REINFORCED MOUNTABLE CURB WITH POLYETHYLENE FIBERS, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	3814	\$4.00	\$14,456.00	\$3.28	\$11,853.92	\$4.85	\$17,527.90
5	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	2909	\$4.00	\$11,636.00	\$3.28	\$9,541.52	\$4.85	\$14,108.65
6	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	14005	\$3.00	\$42,015.00	\$2.88	\$40,334.40	\$3.75	\$52,518.75
7	LIME FOR SUBGRADE PREPARATION, (8% BY DRY WEIGHT), (44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	309	\$200.00	\$61,800.00	\$238.00	\$73,542.00	\$250.00	\$77,250.00
8	COMMON ROADWAY AND LOT EXCAVATION TO BE USED FOR ONSITE FILL, INCLUDES EXCAVATION, HAULING, PLACING AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8' LIFTS, COMPLETE IN PLACE	CY	20031	\$4.00	\$80,124.00	\$3.88	\$77,720.28	\$4.75	\$95,147.25
9	WHEELCHAIR RAMPS AS PER COMC DETAIL, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	14	\$2,000.00	\$28,000.00	\$1,800.00	\$25,200.00	\$1,450.00	\$20,300.00
10	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, STREET SIGNS, STOP SIGNS, PAVEMENT STRIPING, MARKER, ETC., COMPLETE IN PLACE	LS	1	\$6,000.00	\$6,000.00	\$8,888.00	\$8,888.00	\$5,100.00	\$5,100.00
11	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	12	\$12.00	\$144.00	\$10.00	\$120.00	\$12.50	\$150.00
12	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
13	CITY OF MISSOURI CITY (COMC) CONSTRUCTION PERMIT FOR CONSTRUCTION OF PAVING OF INTERNAL SECTION, (PERCENTAGE OF PAVING CONSTRUCTION COST AS REQUIRED BY COMC), COMPLETE IN PLACE	LS	1	\$10,000.00	\$10,000.00	\$12,000.00	\$12,000.00	\$14,000.00	\$14,000.00
14	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$214,440.10, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$8,488.00	\$8,488.00	\$5,100.00	\$5,100.00
15	IRRIGATION SLEEVE, 6" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	307	\$30.00	\$9,210.00	\$28.00	\$8,596.00	\$25.00	\$7,675.00
16	CONNECT PROPOSED 7" PAVEMENT TO EXISTING 7" PAVEMENT, INCLUDES DISPOSAL OF EXISTING SUBGRADE, PAVEMENT AND 2 FT SAWCUT TO FULL DEPTH, DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	120	\$30.00	\$3,600.00	\$28.00	\$3,360.00	\$31.50	\$3,780.00
17	FINAL LOT GRADING OF 54 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$17,500.00	\$17,500.00	\$8,888.00	\$9,888.00	\$20,500.00	\$20,500.00
18	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$17,500.00	\$17,500.00	\$1,500.00	\$1,500.00	\$12,000.00	\$12,000.00
19	CONTRACTOR SHALL REMOVE AND REPLACE EXISTING 8' SIDEWALK, TO EXISTING CONDITIONS OR BETTER, COMPLETE IN PLACE	LF	238	\$70.00	\$16,660.00	\$8.88	\$2,113.44	\$90.50	\$21,539.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 19
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 4
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 SEPTEMBER 2, 2021
 LJA ENGINEERING, INC.
 D. FORREST
 SEPTEMBER 2, 2021
 1414-1519P (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) R CONSTRUCTION CIVIL		2) MH2 CONSTRUCTION SERVICES, LLC		3) NORTHTEX CONSTRUCTION, LLC.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
20	REMOVE AND DISPOSE OF EXISTING 8" CURB, COMPLETE IN PLACE	LF	120	\$6.00	\$720.00	\$8.88	\$1,065.80	\$5.00	\$600.00
21	CONNECT 8" REINFORCED CONCRETE CURB TO EXISTING 7" CONCRETE PAVING, INCLUDING DOWELS AND UNDERCUT, AS PER MISSOURI CITY SPECIFICATIONS AND DETAILS, COMPLETE IN PLACE	LF	76	\$25.00	\$1,900.00	\$28.00	\$2,128.00	\$34.50	\$2,622.00
22	REMOVE AND DISPOSE OF 7 INCH PAVEMENT, COMPLETE IN PLACE	SY	106	\$12.00	\$1,272.00	\$8.88	\$941.28	\$50.50	\$5,353.00
23	COMMON ROADWAY AND LOT EXCAVATION TO BE HAULED USING ON ROAD TRUCKS FOR 1.0 MILE TO DESIGNATED LOCATION, INCLUDES HAULING, PLACING AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	1965	\$10.00	\$19,650.00	\$11.68	\$22,951.20	\$7.60	\$14,934.00
PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 4) SUBTOTAL:					\$939,810.00		\$965,979.84		\$1,020,143.55
MISCELLANEOUS ITEMS									
1	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00	\$0.00
2	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	\$125.00	\$0.00	\$125.00	\$0.00	\$125.00	\$0.00
3	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	0	\$10.00	\$0.00	\$10.00	\$0.00	\$10.00	\$0.00
4	STANDARD DEDUCT FOR DAMAGE TO TREE MARKED FOR PRESERVATION, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00	\$0.00
5	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE FEES, COMPLETE IN PLACE	EA	0	\$500.00	\$0.00	\$500.00	\$0.00	\$500.00	\$0.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$0.00		\$0.00		\$0.00
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS									
1	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	14005	\$2.00	\$28,010.00	\$2.00	\$28,010.00	\$2.00	\$28,010.00
2	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	309	\$180.00	\$55,620.00	\$180.00	\$55,620.00	\$180.00	\$55,620.00
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS SUBTOTAL:					\$83,630.00		\$83,630.00		\$83,630.00
BIDDING SUMMARY									
SUBTOTAL PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 4)					\$939,810.00		\$965,979.84		\$1,020,143.55
SUBTOTAL MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$939,810.00		\$965,979.84		\$1,020,143.55
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS									
TOTAL AMOUNT BASE BID					\$939,810.00		\$965,979.84		\$1,020,143.55
SUBTOTAL ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS					\$83,630.00		\$83,630.00		\$83,630.00
TOTAL AMOUNT INCLUDING ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS					\$1,023,440.00		\$1,049,609.84		\$1,103,773.55

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 19
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 4
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 SEPTEMBER 2, 2021
 LJA ENGINEERING, INC.
 D. FORREST
 SEPTEMBER 2, 2021
 1414-1519P (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	4) HARRIS CONSTRUCTION COMPANY, LLC		5) TRIPLE B SERVICES, LLP		6) DACO PAVING, INC.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 4)									
1	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GENE BAKER, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$5,263.00	\$5,263.00	\$5,263.00	\$5,263.00	\$5,263.00	\$5,263.00
2	6" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	11830	\$50.75	\$600,372.50	\$48.00	\$567,840.00	\$51.50	\$609,245.00
3	7" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	460	\$57.75	\$26,565.00	\$70.00	\$32,200.00	\$57.00	\$26,220.00
4	4" X 12" REINFORCED MOUNTABLE CURB WITH POLYETHYLENE FIBERS, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	3614	\$3.95	\$14,275.30	\$4.60	\$16,624.40	\$4.60	\$16,624.40
5	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	2909	\$3.95	\$11,490.55	\$4.65	\$13,526.85	\$4.60	\$13,381.40
6	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	14005	\$3.90	\$54,619.50	\$4.30	\$60,221.50	\$4.60	\$64,423.00
7	LIME FOR SUBGRADE PREPARATION, (8% BY DRY WEIGHT), (44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	309	\$265.00	\$81,885.00	\$220.00	\$67,980.00	\$220.00	\$67,980.00
8	COMMON ROADWAY AND LOT EXCAVATION TO BE USED FOR ONSITE FILL, INCLUDES EXCAVATION, HAULING, PLACING AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	20031	\$4.20	\$84,130.20	\$7.60	\$152,235.60	\$7.40	\$148,229.40
9	WHEELCHAIR RAMPS AS PER COMC DETAIL, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	14	\$1,875.00	\$26,250.00	\$2,000.00	\$28,000.00	\$2,200.00	\$30,800.00
10	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, STREET SIGNS, STOP SIGNS, PAVEMENT STRIPING, MARKER, ETC., COMPLETE IN PLACE	LS	1	\$14,250.00	\$14,250.00	\$7,500.00	\$7,500.00	\$7,500.00	\$7,500.00
11	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	12	\$12.00	\$144.00	\$12.50	\$150.00	\$20.00	\$240.00
12	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$3,680.00	\$3,680.00	\$3,600.00	\$3,600.00
13	CITY OF MISSOURI CITY (COMC) CONSTRUCTION PERMIT FOR CONSTRUCTION OF PAVING OF INTERNAL SECTION, (PERCENTAGE OF PAVING CONSTRUCTION COST AS REQUIRED BY COMC), COMPLETE IN PLACE	LS	1	\$14,125.00	\$14,125.00	\$12,860.00	\$12,860.00	\$13,500.00	\$13,500.00
14	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$214,440.10, COMPLETE IN PLACE	LS	1	\$22,500.00	\$22,500.00	\$5,790.00	\$5,790.00	\$6,500.00	\$6,500.00
15	IRRIGATION SLEEVE, 6" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	307	\$54.00	\$16,578.00	\$36.00	\$11,052.00	\$46.00	\$14,122.00
16	CONNECT PROPOSED 7" PAVEMENT TO EXISTING 7" PAVEMENT, INCLUDES DISPOSAL OF EXISTING SUBGRADE, PAVEMENT AND 2 FT SAWCUT TO FULL DEPTH, DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	120	\$82.95	\$9,954.00	\$50.00	\$6,000.00	\$34.00	\$4,080.00
17	FINAL LOT GRADING OF 54 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$9,275.00	\$9,275.00	\$20,000.00	\$20,000.00	\$27,000.00	\$27,000.00
18	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$7,500.00	\$7,500.00	\$18,500.00	\$18,500.00	\$6,000.00	\$6,000.00
19	CONTRACTOR SHALL REMOVE AND REPLACE EXISTING 8" SIDEWALK, TO EXISTING CONDITIONS OR BETTER, COMPLETE IN PLACE	LF	238	\$105.00	\$24,990.00	\$75.00	\$17,850.00	\$110.00	\$26,180.00

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 19
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 4
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 SEPTEMBER 2, 2021
 LJA ENGINEERING, INC.
 D. FORREST
 SEPTEMBER 2, 2021
 1414-1519P (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

4) HARRIS CONSTRUCTION COMPANY, LLC

5) TRIPLE B SERVICES, LLP

6) DACO PAVING, INC.

ITEM	DESCRIPTION	UNIT	QTY	4) HARRIS CONSTRUCTION COMPANY, LLC		5) TRIPLE B SERVICES, LLP		6) DACO PAVING, INC.	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
20	REMOVE AND DISPOSE OF EXISTING 8" CURB, COMPLETE IN PLACE	LF	120	\$16.25	\$1,950.00	\$1.00	\$120.00	\$10.00	\$1,200.00
21	CONNECT 6" REINFORCED CONCRETE CURB TO EXISTING 7" CONCRETE PAVING, INCLUDING DOWELS AND UNDERCUT, AS PER MISSOURI CITY SPECIFICATIONS AND DETAILS, COMPLETE IN PLACE	LF	76	\$33.25	\$2,527.00	\$50.00	\$3,800.00	\$15.00	\$1,140.00
22	REMOVE AND DISPOSE OF 7 INCH PAVEMENT, COMPLETE IN PLACE	SY	106	\$17.50	\$1,855.00	\$24.00	\$2,544.00	\$60.00	\$6,360.00
23	COMMON ROADWAY AND LOT EXCAVATION TO BE HAULED USING ON ROAD TRUCKS FOR 1.0 MILE TO DESIGNATED LOCATION, INCLUDES HAULING, PLACING AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	1965	\$9.85	\$19,355.25	\$11.00	\$21,615.00	\$10.50	\$20,632.50
PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 4) SUBTOTAL:					\$1,051,354.30		\$1,075,352.35		\$1,120,220.70
MISCELLANEOUS ITEMS									
1	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00	\$0.00
2	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	\$125.00	\$0.00	\$125.00	\$0.00	\$125.00	\$0.00
3	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	0	\$10.00	\$0.00	\$10.00	\$0.00	\$10.00	\$0.00
4	STANDARD DEDUCT FOR DAMAGE TO TREE MARKED FOR PRESERVATION, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00	\$0.00
5	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE FEES, COMPLETE IN PLACE	EA	0	\$500.00	\$0.00	\$500.00	\$0.00	\$500.00	\$0.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$0.00		\$0.00		\$0.00
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS									
1	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	14005	\$2.00	\$28,010.00	\$4.30	\$60,221.50	\$4.60	\$64,423.00
2	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	309	\$180.00	\$55,620.00	\$220.00	\$67,980.00	\$220.00	\$67,980.00
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS SUBTOTAL:					\$83,630.00		\$128,201.50		\$132,403.00
BIDDING SUMMARY									
SUBTOTAL PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 4)					\$1,051,354.30		\$1,075,352.35		\$1,120,220.70
SUBTOTAL MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$1,051,354.30		\$1,075,352.35		\$1,120,220.70
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS									
TOTAL AMOUNT BASE BID					\$1,051,354.30		\$1,075,352.35		\$1,120,220.70
SUBTOTAL ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS					\$83,630.00		\$128,201.50		\$132,403.00
TOTAL AMOUNT INCLUDING ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS					\$1,134,984.30		\$1,203,553.85		\$1,252,623.70