


BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA PARKWAY PHASE 7
SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
JUNE 11, 2026
LJA ENGINEERING, INC.
C CORTEZ
JUNE 11, 2026
1415-1507B (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER NAME	BASE BID	ALTERNATE NO. 1 PLUS BASE BID
1) ICON GC LLC	\$1,656,690.00	\$1,736,040.00
2) MH2 CONSTRUCTION SERVICES, LLC	\$2,060,650.00	\$2,140,000.00

90/10 CALENDAR DAYS



Tyler Volk

6/11/2026

Tyler Volk
for I, RICHARD STANFIELD, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA PARKWAY PHASE 7
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JUNE 11, 2026
 LJA ENGINEERING, INC.
 C CORTEZ
 JUNE 11, 2026
 1415-1507B (9.2)

BID OPENING DATE:
 BID OPENING LOCATION:
 TABULATION BY:
 TABULATION DATE:
 LJA JOB NO.

NO.	ITEM DESCRIPTION	UNIT	QTY	1) ICON GC LLC		2) MH2 CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) PHASE 1 --SIENNA MUD NO. 5							
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$3,561.00	\$3,561.00	\$3,561.00	\$3,561.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00
3.	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$133,310.10, COMPLETE IN PLACE	LS	1	\$0.00	\$0.00	\$6,058.96	\$6,058.96
4.	CITY OF MISSOURI CITY (COMC) CONSTRUCTION PERMIT FOR CONSTRUCTION OF PAVING, (PERCENTAGE OF PAVING CONSTRUCTION COST AS REQUIRED BY COMC), COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$12,956.00	\$12,956.00
5.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00
6.	8" STAMPED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, DYED TO OWNER SPECIFIED COLOR (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	220	\$150.00	\$33,000.00	\$148.00	\$32,560.00
7.	8" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	7801	\$56.00	\$436,856.00	\$61.18	\$477,265.18
8.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	8144	\$5.00	\$40,720.00	\$4.32	\$35,182.08
9.	8" CEMENT STABILIZED SUBGRADE, COMPLETE IN PLACE	SY	1484	\$5.00	\$7,420.00	\$21.88	\$32,469.92
10.	LIME FOR SUBGRADE PREPARATION, (8% BY WEIGHT, 44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	180	\$385.00	\$69,300.00	\$362.58	\$65,264.40
11.	3" TYPE "D" HOT MIX ASPHALT CONCRETE, COMPLETE IN PLACE	SY	1476	\$40.00	\$59,040.00	\$76.18	\$112,441.68
12.	8" BLACK BASE, COMPLETE IN PLACE	SY	1745	\$65.00	\$113,425.00	\$154.78	\$270,091.10
13.	8" STABILIZED CRUSHED CONCRETE, COMPLETE IN PLACE	SY	2040	\$35.00	\$71,400.00	\$35.36	\$72,134.40
14.	LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT, 44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), FOR ASPHALT, COMPLETE IN PLACE	TON	45	\$385.00	\$17,325.00	\$362.58	\$16,316.10
15.	CONTRACTOR TO REMOVE AND DISPOSE OF EXISTING CONSTRUCTION ACCESS DRIVE, COMPLETE IN PLACE	LS	1	\$850.00	\$850.00	\$1,988.00	\$1,988.00
16.	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	4752	\$4.00	\$19,008.00	\$3.50	\$16,632.00
17.	4"x18" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	234	\$4.00	\$936.00	\$6.48	\$1,516.32
18.	REMOVE AND OFFSITE DISPOSAL OF EXISTING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1238	\$3.00	\$3,714.00	\$1.00	\$1,238.00
19.	CONNECT PROPOSED 8" REINFORCED CONCRETE PAVEMENT TO EXISTING REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	50	\$15.00	\$750.00	\$55.00	\$2,750.00
20.	CONNECT PROPOSED 8" ASPHALT TO EXISTING 8" PAVEMENT, INCLUDES DISPOSAL OF EXISTING SUBGRADE, AND ANY OTHER APPURTENANCES, COMPLETE IN PLACE	LF	578	\$10.00	\$5,780.00	\$28.00	\$16,184.00
21.	CONNECT PROPOSED 8" PAVEMENT TO EXISTING 8" PAVEMENT INCLUDES DOWEL INTO EXISTING CONCRETE, AND ANY OTHER APPURTENANCES, COMPLETE IN PLACE	LF	972	\$15.00	\$14,580.00	\$10.88	\$10,575.36
22.	6" MONOLITHIC CURB ON ROUNDABOUT, COMPLETE IN PLACE	LF	234	\$6.00	\$1,404.00	\$55.48	\$12,982.32
23.	CONNECT PROPOSED 8" PAVEMENT TO EXISTING 8" PAVEMENT, INCLUDES DISPOSAL OF EXISTING SUBGRADE, PAVEMENT AND 2 FT OF SAWCUT TO FULL DEPTH, DOWEL INTO EXISTING CONCRETE PAVEMENT, AND ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	1261	\$12.00	\$15,132.00	\$10.88	\$13,719.68
24.	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$50.00	\$100.00	\$0.50	\$1.00
25.	PAVING HEADER, AS PER CITY OF MISSOURI CITY CRITERIA, COMPLETE IN PLACE	LF	221	\$12.00	\$2,652.00	\$12.00	\$2,652.00

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA PARKWAY PHASE 7
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JUNE 11, 2026
 LJA ENGINEERING, INC.
 C CORTEZ
 JUNE 11, 2026
 1415-1507B (9.2)

BID OPENING DATE:
 BID OPENING LOCATION:
 TABULATION BY:
 TABULATION DATE:
 LJA JOB NO.

NO.	ITEM DESCRIPTION	UNIT	QTY	1) ICON GC LLC		2) MH2 CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL
26.	TYPE III BARRICADE, ONLY AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	EA	6	\$2,200.00	\$13,200.00	\$1,218.00	\$7,308.00
27.	IMPORT OF ADJACENT STOCKPILE, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, HAUL, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	2969	\$8.00	\$23,752.00	\$8.28	\$24,583.32
28.	COMMON ROADWAY EXCAVATION TO BE USED FOR ONSITE FILL, INCLUDES EXCAVATION, HAULING, PLACING AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	1163	\$6.00	\$6,978.00	\$4.56	\$5,303.28
29.	FINAL GRADING OF ROADWAY AND RESERVES, COMPLETE IN PLACE	LS	1	\$8,500.00	\$8,500.00	\$5,288.00	\$5,288.00
30.	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
31.	WHEELCHAIR RAMPS AS PER COMC DETAIL, ALL SIZES, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	4	\$1,650.00	\$6,600.00	\$1,428.00	\$5,712.00
32.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	7	\$18.00	\$126.00	\$8.00	\$56.00
33.	IRRIGATION SLEEVE 4" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	328	\$24.00	\$7,872.00	\$29.78	\$9,767.84
34.	IRRIGATION SLEEVE, 6" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	328	\$26.00	\$8,528.00	\$33.08	\$10,850.24
35.	BORE AND JACK OR AUGER (WET BORE) OF 4" & 6" IRRIGATION SLEEVES, ALL DEPTHS, ALL SIZES, EXCLUDES CARRIER PIPE, (TO ONLY BE USED AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	76	\$34.00	\$2,584.00	\$68.00	\$5,168.00
36.	BORE PITS FOR IRRIGATION SLEEVES LINE BORE, INCLUDES BORE PIT, DEWATERING OF BORE PIT, TRENCH SAFETY FOR BORE PIT, & FILLED WITH 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	EA	6	\$500.00	\$3,000.00	\$278.00	\$1,668.00
37.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$38,500.00	\$38,500.00	\$37,268.00	\$37,268.00
38.	LANDSCAPING AND IRRIGATION RESTORATION, COMPLETE IN PLACE	LS	1	\$70,000.00	\$70,000.00	\$70,000.00	\$70,000.00
39.	INSTALL CONCRETE BARRIER, TO REMAIN IN PLACE BEYOND COMPLETION OF PROJECT, COMPLETE IN PLACE	LF	1095	\$80.00	\$87,600.00	\$98.00	\$107,310.00
40.	PORTABLE MESSAGE SIGN, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE	WK	15	\$375.00	\$5,625.00	\$588.00	\$8,820.00
41.	TEMPORARY TRAFFIC CONTROL AS PER COMC STANDARDS FOR PHASE 1, INCLUDING BARRELS, CONES, FLAGMEN, STRIPING, BUTTONS, TEMPORARY SIGNAGE, ETC. AS NEEDED TO CONSTRUCT PHASE 1, INCLUDES MAINTAINING ALL TEMPORARY TRAFFIC CONTROL ITEMS THROUGH LIFE OF PHASE 1, COMPLETE IN PLACE	LS	1	\$15,000.00	\$15,000.00	\$20,108.00	\$20,108.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) PHASE 1 –SIENNA MUD NO. 5					\$1,227,318.00		\$1,540,250.18
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) PHASE 2 –SIENNA MUD NO. 5							
1.	8" STAMPED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, DYED TO OWNER SPECIFIED COLOR, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	123	\$170.00	\$20,910.00	\$148.00	\$18,204.00
2.	8" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	3045	\$60.00	\$182,700.00	\$61.18	\$186,293.10
3.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	2031	\$5.00	\$10,155.00	\$4.32	\$8,773.92
4.	8" CEMENT STABILIZED SUBGRADE, COMPLETE IN PLACE	SY	2102	\$5.00	\$10,510.00	\$21.88	\$45,991.76

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA PARKWAY PHASE 7
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JUNE 11, 2026
 LJA ENGINEERING, INC.
 C CORTEZ
 JUNE 11, 2026
 1415-1507B (9.2)

BID OPENING DATE:
 BID OPENING LOCATION:
 TABULATION BY:
 TABULATION DATE:
 LJA JOB NO.

NO.	ITEM DESCRIPTION	UNIT	QTY	1) ICON GC LLC		2) MH2 CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL
5.	LIME FOR SUBGRADE PREPARATION, (8% BY WEIGHT, 44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	45	\$385.00	\$17,325.00	\$362.58	\$16,316.10
6.	REMOVE AND OFFSITE DISPOSAL OF EXISTING 8" REINFORCED CONCRETE, HAULED OUTSIDE OF SIENNA DEVELOPMENT, COMPLETE IN PLACE	SY	1037	\$5.00	\$5,185.00	\$8.88	\$9,208.56
7.	REMOVE & DISPOSE 8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), HAULED OUTSIDE OF SIENNA DEVELOPMENT, COMPLETE IN PLACE	SY	1285	\$5.00	\$6,425.00	\$8.88	\$11,410.80
8.	REMOVE AND OFFSITE DISPOSAL OF EXISTING ASPHALT PAVING AND SUBGRADE, HAULED OUTSIDE OF SIENNA DEVELOPMENT, INCLUDES BASE, COMPLETE IN PLACE	SY	1993	\$5.00	\$9,965.00	\$8.88	\$17,697.84
9.	REMOVE AND OFFSITE DISPOSAL OF PHASE 1 ASPHALT PAVING AND SUBGRADE, INCLUDES BASE, HAULED OUTSIDE OF SIENNA DEVELOPMENT, COMPLETE IN PLACE	SY	1476	\$5.00	\$7,380.00	\$8.88	\$13,106.88
10.	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	2787	\$4.00	\$11,148.00	\$3.50	\$9,754.50
11.	4"X18" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	131	\$4.00	\$524.00	\$6.48	\$848.88
12.	CONNECT PROPOSED 8" PAVEMENT TO EXISTING 8" PAVEMENT, INCLUDES DISPOSAL OF EXISTING SUBGRADE, PAVEMENT AND 2 FT OF SAWCUT TO FULL DEPTH, DOWEL INTO EXISTING CONCRETE PAVEMENT, AND ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	934	\$12.00	\$11,208.00	\$10.88	\$10,161.92
13.	6" REINFORCED CONCRETE CURB DOWELED INTO EXISTING PAVEMENT, COMPLETE IN PLACE	LF	974	\$11.00	\$10,714.00	\$5.08	\$4,947.92
14.	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
15.	REMOVE AND OFFSITE DISPOSAL OF EXISTING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2250	\$2.00	\$4,500.00	\$1.00	\$2,250.00
16.	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$50.00	\$100.00	\$0.50	\$1.00
17.	PAVING HEADER, AS PER CITY OF MISSOURI CITY CRITERIA, COMPLETE IN PLACE	LF	36	\$15.00	\$540.00	\$12.00	\$432.00
18.	TYPE III BARRICADE, ONLY AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	EA	2	\$2,200.00	\$4,400.00	\$1,218.00	\$2,436.00
19.	CONNECT PROPOSED 8" PAVEMENT TO EXISTING 8" PAVEMENT, COMPLETE IN PLACE	LF	138	\$12.00	\$1,656.00	\$55.00	\$7,590.00
20.	CONNECT PROPOSED 8" PAVEMENT TO EXISTING 8" PAVEMENT, INCLUDES DOWEL INTO EXISTING CONCRETE, AND ANY OTHER APPURTENANCES, COMPLETE IN PLACE	LF	1305	\$15.00	\$19,575.00	\$10.88	\$14,198.40
21.	FINAL GRADING OF ROADWAY AND RESERVES, COMPLETE IN PLACE	LS	1	\$8,500.00	\$8,500.00	\$5,288.00	\$5,288.00
22.	6" MONOLITHIC CURB ON ROUNDABOUT, COMPLETE IN PLACE	LF	104	\$12.00	\$1,248.00	\$55.48	\$5,769.92
23.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	3	\$18.00	\$54.00	\$8.00	\$24.00
24.	FINAL AJUSTMENT TO EXISTING FIRE HYDRANT, COMPLETE IN PLACE	EA	1	\$1,850.00	\$1,850.00	\$1,800.00	\$1,800.00
25.	WHEELCHAIR RAMPS AS PER COMC DETAIL, ALL SIZES, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	4	\$1,650.00	\$6,600.00	\$1,428.00	\$5,712.00
26.	IRRIGATION SLEEVE 4" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	312	\$24.00	\$7,488.00	\$29.78	\$9,291.36
27.	IRRIGATION SLEEVE, 6" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	312	\$26.00	\$8,112.00	\$33.08	\$10,320.96

BID TABULATION FOR:

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA PARKWAY PHASE 7
SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
JUNE 11, 2026
LJA ENGINEERING, INC.
C CORTEZ
JUNE 11, 2026
1415-1507B (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) ICON GC LLC		2) MHZ CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL
28.	BORE AND JACK OR AUGER (WET BORE) OF 4" & 6" IRRIGATION SLEEVES, ALL DEPTHS, ALL SIZES, EXCLUDES CARRIER PIPE, (TO ONLY BE USED AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	220	\$30.00	\$6,600.00	\$68.00	\$14,960.00
29.	BORE PITS FOR IRRIGATION SLEEVES LINE BORE, INCLUDES BORE PIT, DEWATERING OF BORE PIT, TRENCH SAFETY FOR BORE PIT, & FILLED WITH 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	EA	2	\$500.00	\$1,000.00	\$278.00	\$556.00
30.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$10,500.00	\$10,500.00	\$19,968.00	\$19,968.00
31.	REMOVE EXISTING STRIPING, BUTTONS, AND SIGNAGE, COMPLETE IN PLACE	LS	1	\$3,500.00	\$3,500.00	\$4,298.00	\$4,298.00
32.	RELOCATION OF EXISTING UTILITY POLES AND GUY WIRES IN MEDIAN INCLUDES COORDINATION, ADJUSTMENT, RELOCATION, TEMPORARY SUPPORT, REMOVAL AND REINSTALLATION OF EXISTING UTILITY POLES, GUY WIRES, ANCHORS, AND ASSOCIATED APPURTENANCES WITHIN THE CONSTRUCTION LIMITS, COMPLETE IN PLACE.	LS	1	\$7,500.00	\$7,500.00	\$18,000.00	\$18,000.00
33.	REMOBILIZATION TO COMPLETE CONSTRUCTION OF PHASE II OF PAVING AND APPURTENANCES, INCLUDES ADDITIONAL COST FOR REMOBILIZATION, AND ANY ADDITIONAL COSTS ASSOCIATED WITH CONSTRUCTING PORTION OF PROJECT AT A LATER DATE, COMPLETE IN PLACE	LS	1	\$15,000.00	\$15,000.00	\$12,000.00	\$12,000.00
34.	TEMPORARY TRAFFIC CONTROL AS PER COMC STANDARDS FOR PHASE 2, INCLUDING BARRELS, CONES, FLAGMEN, STRIPING, BUTTONS, TEMPORARY SIGNAGE, ETC. AS NEEDED TO CONSTRUCT PHASE 2, INCLUDES MAINTAINING ALL TEMPORARY TRAFFIC CONTROL ITEMS THROUGH LIFE OF PHASE 2, COMPLETE IN PLACE	LS	1	\$15,000.00	\$15,000.00	\$31,288.00	\$31,288.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) PHASE 2--SIENNA MUD NO. 5					\$429,372.00		\$520,399.82
BASE BID MISCELLANEOUS ITEMS							
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO TREE MARKED FOR PRESERVATION, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00	-\$500.00	\$0.00
SUBTOTAL BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00
ALTERNATE NO. 1 PAVING FIELD CONDITIONS ITEMS							
1.	ADDITIONAL 8" LIME STABILIZED ROADWAY AND ASPHALT SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	11635	\$2.00	\$23,270.00	\$2.00	\$23,270.00
2.	ADDITIONAL LIME FOR ROADWAY AND ASPHALT SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	256	\$180.00	\$46,080.00	\$180.00	\$46,080.00
3.	HEAVY CLEARING AND GRUBBING OF RESERVES, INCLUDES ROOT RAKING AND BACK DRAGGING, COMPLETE IN PLACE	AC	1	\$10,000.00	\$10,000.00	\$10,000.00	\$10,000.00
SUBTOTAL ALTERNATE NO. 1 PAVING FIELD CONDITIONS ITEMS					\$79,350.00		\$79,350.00



BID TABULATION FOR:

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA PARKWAY PHASE 7
SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
JUNE 11, 2026
LJA ENGINEERING, INC.
C CORTEZ
JUNE 11, 2026
1415-1507B (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) ICON GC LLC		2) MH2 CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL

BID SUMMARY

BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) PHASE 1 –SIENNA MUD NO. 5	\$1,227,318.00	\$1,540,250.18
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) PHASE 2 –SIENNA MUD NO. 5	\$429,372.00	\$520,399.82
BASE BID MISCELLANEOUS ITEMS	\$0.00	\$0.00
TOTAL AMOUNT BASE BID	\$1,656,690.00	\$2,060,650.00

ALTERNATE NO. 1

TOTAL AMOUNT BASE BID	\$1,656,690.00	\$2,060,650.00
PAVING FIELD CONDITIONS ITEMS	\$79,350.00	\$79,350.00
TOTAL ALTERNATE NO. 1 PLUS BASE BID	\$1,736,040.00	\$2,140,000.00

LJA Engineering, Inc