

BID TABULATION FOR:

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.


CONSTRUCTION OF PAVING AND APPURTENANCES  
TO SERVE SIENNA SECTION 33C  
SIENNA MUNICIPAL UTILITY DISTRICT NO. 6  
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
MARCH 23, 2021  
LJA ENGINEERING, INC.  
D. FORREST  
MARCH 24, 2021  
1416-1533CP (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID	BID INCLUDING ALTERNATE BID NO. 1 - FIELD CONDITIONS ITEMS
1) MH2 CONSTRUCTION SERVICES, LLC	\$385,177.19	\$401,193.19
2) HARRIS CONSTRUCTION COMPANY, LLC	\$400,981.80	\$416,631.00
3) TRIPLE B SERVICES, LLP	\$433,722.90	\$487,680.30
4) PRECISE SERVICES INC.	\$493,882.50	\$535,483.50

CALENDAR DAYS - 40/50

*Amanda Carriage*

I, Amanda Carriage, P.E., hereby certify these bid tabulations to be true and correct.



*Amanda Carriage*  
*3/24/21*

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF PAVING AND APPURTENANCES  
 TO SERVE SIENNA SECTION 33C  
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 6  
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
 MARCH 23, 2021  
 LJA ENGINEERING, INC.  
 D. FORREST  
 MARCH 24, 2021  
 1416-1533CP (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) MH2 CONSTRUCTION SERVICES, LLC		2) HARRIS CONSTRUCTION COMPANY, LLC		3) TRIPLE B SERVICES, LLP	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>PAVING IMPROVEMENT ITEMS (INTERNAL) -- (SIENNA M.U.D. NO. 6)</b>									
1	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GENE BAKER, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,451.00	\$2,451.00	\$2,451.00	\$2,451.00	\$2,451.00	\$2,451.00
2	6" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	5264	\$43.66	\$229,826.24	\$42.25	\$222,404.00	\$43.85	\$230,826.40
3	4" X 12" REINFORCED MOUNTABLE CURB WITH POLYETHYLENE FIBERS, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	1964	\$3.08	\$6,049.12	\$3.55	\$6,972.20	\$4.30	\$8,445.20
4	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	1188	\$3.08	\$3,659.04	\$3.55	\$4,217.40	\$4.30	\$5,108.40
5	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	6356	\$2.98	\$18,940.88	\$2.45	\$15,572.20	\$4.15	\$26,377.40
6	LIME FOR SUBGRADE PREPARATION, (8% BY DRY WEIGHT), (44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	140	\$219.88	\$30,783.20	\$225.00	\$31,500.00	\$197.00	\$27,580.00
7	COMMON ROADWAY AND LOT EXCAVATION TO BE HAULED USING OFF ROAD TRUCKS TO DISPOSAL SITE 0.3 MILES FROM THE PROJECT, INCLUDES EXCAVATION, HAULING, TO BE STOCKPILED, COMPLETE IN PLACE	CY	7050	\$3.86	\$27,213.00	\$4.00	\$28,200.00	\$5.80	\$40,890.00
8	WHEELCHAIR RAMPS AS PER COMC DETAIL, ALL SIZES, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	6	\$1,066.00	\$6,396.00	\$1,150.00	\$6,900.00	\$1,375.00	\$8,250.00
9	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, STREET SIGNS, STOP SIGNS, PAVEMENT STRIPING, MARKER, ETC., COMPLETE IN PLACE	LS	1	\$5,688.00	\$5,688.00	\$11,250.00	\$11,250.00	\$5,850.00	\$5,850.00
10	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	5	\$6.00	\$30.00	\$12.00	\$60.00	\$15.00	\$75.00
11	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
12	CITY OF MISSOURI CITY (COMC) CONSTRUCTION PERMIT FOR CONSTRUCTION OF PAVING OF INTERNAL SECTION, (PERCENTAGE OF PAVING CONSTRUCTION COST AS REQUIRED BY COMC), COMPLETE IN PLACE	LS	1	\$6,200.00	\$6,200.00	\$6,000.00	\$6,000.00	\$7,000.00	\$7,000.00
13	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$119,325.50, COMPLETE IN PLACE	LS	1	\$3,463.88	\$3,463.88	\$17,250.00	\$17,250.00	\$3,000.00	\$3,000.00
14	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	4	\$0.50	\$2.00	\$200.00	\$800.00	\$100.00	\$400.00
15	CONNECT PROPOSED 6" PAVEMENT TO EXISTING 6" PAVEMENT AND DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	112	\$34.00	\$3,808.00	\$20.25	\$2,268.00	\$25.00	\$2,800.00
16	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$5,000.00	\$5,000.00	\$11,800.00	\$11,800.00
17	FINAL LOT GRADING OF 35 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$5,750.00	\$5,750.00	\$8,700.00	\$8,700.00

**BID TABULATION FOR:**

CONSTRUCTION OF PAVING AND APPURTENANCES  
 TO SERVE SIENNA SECTION 33C  
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 6  
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
 MARCH 23, 2021  
 LJA ENGINEERING, INC.  
 D. FORREST  
 MARCH 24, 2021  
 1416-1533CP (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

ITEM	DESCRIPTION	UNIT	QTY	1) MH2 CONSTRUCTION SERVICES, LLC		2) HARRIS CONSTRUCTION COMPANY, LLC		3) TRIPLE B SERVICES, LLP	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
18	COMMON ROADWAY AND LOT EXCAVATION TO BE USED FOR ONSITE FILL, AS PER GRADING PLAN, INCLUDES EXCAVATION, HAULING, PLACING AND COMPACTING TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	560	\$3.86	\$2,161.60	\$3.00	\$1,680.00	\$5.80	\$3,248.00
19	COMMON ROADWAY AND LOT EXCAVATION TO BE HAULED USING ON ROAD TRUCKS TO A DISPOSAL SITE 1.5 MILES FROM THE PROJECT, PLACED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	3677	\$5.99	\$22,025.23	\$6.00	\$22,062.00	\$9.50	\$34,931.50
20	HIGH PERFORMANCE TURF REINFORCEMENT MAT (PYROMAT, 972.439.2355), OR APPROVED EQUAL, AS PER PLANS, COMPLETE IN PLACE	SY	133	\$60.00	\$7,980.00	\$65.00	\$8,645.00	\$30.00	\$3,990.00
<b>PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 6) SUBTOTAL:</b>					<b>\$384,677.19</b>		<b>\$400,481.80</b>		<b>\$433,222.90</b>
<b>MISCELLANEOUS ITEMS</b>									
1	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00
3	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00	-\$10.00	\$0.00	-\$10.00	\$0.00
4	STANDARD DEDUCT FOR DAMAGE TO TREE MARKED FOR PRESERVATION, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
5	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$500.00</b>		<b>\$500.00</b>		<b>\$500.00</b>
<b>ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS</b>									
1	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	6356	\$1.00	\$6,356.00	\$0.70	\$4,449.20	\$4.15	\$26,377.40
2	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	140	\$69.00	\$9,660.00	\$80.00	\$11,200.00	\$197.00	\$27,580.00
<b>ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS SUBTOTAL:</b>					<b>\$16,016.00</b>		<b>\$15,649.20</b>		<b>\$53,957.40</b>
<b>BIDDING SUMMARY</b>									
SUBTOTAL PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 6)					\$384,677.19		\$400,481.80		\$433,222.90
SUBTOTAL MISCELLANEOUS ITEMS					\$500.00		\$500.00		\$500.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$385,177.19</b>		<b>\$400,981.80</b>		<b>\$433,722.90</b>
<b>ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS</b>									
TOTAL AMOUNT BASE BID					\$385,177.19		\$400,981.80		\$433,722.90
SUBTOTAL ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS					\$16,016.00		\$15,649.20		\$53,957.40
<b>TOTAL AMOUNT INCLUDING ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS</b>					<b>\$401,193.19</b>		<b>\$416,631.00</b>		<b>\$487,680.30</b>

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF PAVING AND APPURTENANCES  
 TO SERVE SIENNA SECTION 33C  
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 6  
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
 MARCH 23, 2021  
 LJA ENGINEERING, INC.  
 D. FORREST  
 MARCH 24, 2021  
 1416-1533CP (9.2)

4) PRECISE SERVICES INC.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 6)</b>					
1	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GENE BAKER, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,451.00	\$2,451.00
2	6" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	5264	\$46.00	\$242,144.00
3	4" X 12" REINFORCED MOUNTABLE CURB WITH POLYETHYLENE FIBERS, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	1964	\$4.00	\$7,856.00
4	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	1188	\$4.00	\$4,752.00
5	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	6356	\$3.00	\$19,068.00
6	LIME FOR SUBGRADE PREPARATION, (8% BY DRY WEIGHT), (44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	140	\$220.00	\$30,800.00
7	COMMON ROADWAY AND LOT EXCAVATION TO BE HAULED USING OFF ROAD TRUCKS TO DISPOSAL SITE 0.3 MILES FROM THE PROJECT, INCLUDES EXCAVATION, HAULING, TO BE STOCKPILED, COMPLETE IN PLACE	CY	7050	\$4.50	\$31,725.00
8	WHEELCHAIR RAMPS AS PER COMC DETAIL, ALL SIZES, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	6	\$1,500.00	\$9,000.00
9	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, STREET SIGNS, STOP SIGNS, PAVEMENT STRIPING, MARKER, ETC., COMPLETE IN PLACE	LS	1	\$6,500.00	\$6,500.00
10	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	5	\$20.00	\$100.00
11	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00
12	CITY OF MISSOURI CITY (COMC) CONSTRUCTION PERMIT FOR CONSTRUCTION OF PAVING OF INTERNAL SECTION, (PERCENTAGE OF PAVING CONSTRUCTION COST AS REQUIRED BY COMC), COMPLETE IN PLACE	LS	1	\$10,000.00	\$10,000.00
13	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$119,325.50, COMPLETE IN PLACE	LS	1	\$4,850.00	\$4,850.00
14	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	4	\$100.00	\$400.00
15	CONNECT PROPOSED 6" PAVEMENT TO EXISTING 6" PAVEMENT AND DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	112	\$30.00	\$3,360.00
16	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$83,000.00	\$83,000.00
17	FINAL LOT GRADING OF 35 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$7,500.00	\$7,500.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF PAVING AND APPURTENANCES  
 TO SERVE SIENNA SECTION 33C  
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 6  
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS  
 MARCH 23, 2021  
 LJA ENGINEERING, INC.  
 D. FORREST  
 MARCH 24, 2021  
 1416-1533CP (9.2)

4) PRECISE SERVICES INC.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
18	COMMON ROADWAY AND LOT EXCAVATION TO BE USED FOR ONSITE FILL, AS PER GRADING PLAN, INCLUDES EXCAVATION, HAULING, PLACING AND COMPACTING TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	560	\$4.50	\$2,520.00
19	COMMON ROADWAY AND LOT EXCAVATION TO BE HAULED USING ON ROAD TRUCKS TO A DISPOSAL SITE 1.5 MILES FROM THE PROJECT, PLACED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	3677	\$4.50	\$16,546.50
20	HIGH PERFORMANCE TURF REINFORCEMENT MAT (PYROMAT, 972.439.2355), OR APPROVED EQUAL, AS PER PLANS, COMPLETE IN PLACE	SY	133	\$70.00	\$9,310.00
<b>PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 6) SUBTOTAL:</b>					<b>\$493,382.50</b>
<b>MISCELLANEOUS ITEMS</b>					
1	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00
2	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00
3	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00
4	STANDARD DEDUCT FOR DAMAGE TO TREE MARKED FOR PRESERVATION, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00
5	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$500.00</b>
<b>ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS</b>					
1	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	6356	\$2.25	\$14,301.00
2	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	140	\$195.00	\$27,300.00
<b>ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS SUBTOTAL:</b>					<b>\$41,601.00</b>
<b>BIDDING SUMMARY</b>					
SUBTOTAL PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA M.U.D. NO. 6)					\$493,382.50
SUBTOTAL MISCELLANEOUS ITEMS					\$500.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$493,882.50</b>
<b>ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS</b>					
TOTAL AMOUNT BASE BID					\$493,882.50
SUBTOTAL ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS					\$41,601.00
<b>TOTAL AMOUNT INCLUDING ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS</b>					<b>\$535,483.50</b>