


BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 50C
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
JUNE 6, 2024
LJA ENGINEERING, INC.
C CORTEZ
JUNE 6, 2024
1417-1550CP (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID	BID INCLUDING ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS
1) MH2 CONSTRUCTION SERVICES, LLC	\$444,230.00	\$472,000.00

CALENDAR DAYS 40/50



Richard Stanfield Jr
6/11/2024

Richard Stanfield Jr

I, RICHARD STANFIELD, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 50C
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JUNE 6, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JUNE 6, 2024
 1417-1550CP (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

1) MH2 CONSTRUCTION SERVICES, LLC

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA MUD. NO. 7)					
1	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER STEVE WIGGINGTON, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,331.00	\$2,331.00
2	6" REINFORCED CONCRETE PAVEMENT POURED FULL-WIDTH WHERE APPLICABLE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	3875	\$70.00	\$271,250.00
3	4" X 12" REINFORCED MOUNTABLE CURB WITH POLYETHYLENE FIBERS, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	1968	\$5.00	\$9,840.00
4	6" REINFORCED CONCRETE CURB, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	LF	335	\$5.00	\$1,675.00
5	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	4660	\$5.00	\$23,300.00
6	LIME FOR SUBGRADE PREPARATION, (8% BY DRY WEIGHT), (44 LBS/SY), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	TON	102.5	\$408.00	\$41,820.00
7	COMMON ROADWAY EXCAVATION TO BE USED FOR ONSITE FILL, INCLUDES EXCAVATION, HAULING, PLACING AND COMPACTION TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	CY	2698	\$4.10	\$11,061.80
8	STOCKPILE OF COMMON ROADWAY EXCAVATION TO ADJACENT CONSTRUCTION SITE NORTH OF SECTION USING ON-ROAD TRUCKS (0-0.50 MILES), COMPLETE IN PLACE	CY	3878	\$4.10	\$15,899.80
9	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, STREET SIGNS, STOP SIGNS, PAVEMENT STRIPING, MARKER, ETC., COMPLETE IN PLACE	LS	1	\$5,435.00	\$5,435.00
10	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	3	\$18.00	\$54.00
11	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$8,788.00	\$8,788.00
12	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00
13	CITY OF MISSOURI CITY (COMC) CONSTRUCTION PERMIT FOR CONSTRUCTION OF PAVING OF INTERNAL SECTION, (PERCENTAGE OF PAVING CONSTRUCTION COST AS REQUIRED BY COMC), COMPLETE IN PLACE	LS	1	\$7,100.00	\$7,100.00
14	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$78,661.10, COMPLETE IN PLACE	LS	1	\$9,269.34	\$9,269.34
15	FINAL LOT GRADING OF 38 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$14,388.00	\$14,388.00
16	IRRIGATION SLEEVE, 6" PVC SCHEDULE 40, INCLUDES RISERS AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	LF	61	\$41.00	\$2,501.00
17	CONNECT PROPOSED 6" PAVEMENT TO EXISTING 6" PAVEMENT AND DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER APPURTENANCES, COMPLETE IN PLACE	LF	56	\$58.00	\$3,248.00
18	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 50C
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JUNE 6, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JUNE 6, 2024
 1417-1550CP (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

1) MH2 CONSTRUCTION SERVICES, LLC

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
19	FORT BEND COUNTY DEVELOPMENT PERMIT, FOR PLACING AND COMPACTING SPOILS, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00
20	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$0.55	\$1.10
21	6" REINFORCED CONCRETE PAVEMENT FOR ACCESS DRIVE, POURED FULL-WIDTH WHERE APPLICABLE (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	18	\$68.00	\$1,224.00

PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA MUD. NO. 7) SUBTOTAL: \$431,686.04

CLEARING AND GRUBBING ITEMS (DEVELOPER ITEMS) - (SIENNA MUD NO. 7)

1	STRIPPING OF LOTS AND RESERVES, INCLUDES REMOVING ALL STUMPS AND ROOTS (ONLY AREAS AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	AC	6.01	\$1,892.00	\$11,370.92
2	STRIPPING OF PRIVATE UTILITY EASEMENTS, INCLUDES REMOVING ALL STUMPS AND ROOTS (ONLY AREAS AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	AC	0.62	\$1,892.00	\$1,173.04

CLEARING AND GRUBBING ITEMS (DEVELOPER ITEMS) - (SIENNA MUD NO. 7) SUBTOTAL: \$12,543.96

MISCELLANEOUS ITEMS

1	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00
2	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00
3	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00
4	STANDARD DEDUCT FOR DAMAGE TO TREE MARKED FOR PRESERVATION, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00
5	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	LS	0	-\$500.00	\$0.00

MISCELLANEOUS ITEMS SUBTOTAL: \$0.00

ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS

1	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	4660	\$2.00	\$9,320.00
2	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	102.5	\$180.00	\$18,450.00

ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS SUBTOTAL: \$27,770.00

BIDDING SUMMARY

SUBTOTAL PAVING IMPROVEMENT ITEMS (INTERNAL) – (SIENNA MUD. NO. 7)	\$431,686.04
SUBTOTAL CLEARING AND GRUBBING ITEMS (DEVELOPER ITEMS) - (SIENNA MUD NO. 7)	\$12,543.96
SUBTOTAL MISCELLANEOUS ITEMS	\$0.00
TOTAL AMOUNT BASE BID	\$444,230.00
ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS	
TOTAL AMOUNT BASE BID	\$444,230.00
SUBTOTAL ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS	\$27,770.00
TOTAL AMOUNT INCLUDING ALTERNATE BID NO. 1 – FIELD CONDITIONS ITEMS	\$472,000.00