

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 78
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7

BID OPENING DATE:

APRIL 09, 2026

BID OPENING LOCATION:

LJA ENGINEERING, INC.

TABULATION BY:

C CORTEZ

TABULATION DATE:


APRIL 10, 2026

LJA JOB NO.

1417-1578P (9.2)

BIDDER NAME	BASE BID	ALTERNATE BID NO. 1 PLUS BASE BID
1) HARRIS CONSTRUCTION COMPANY, LLC	\$849,473.80	\$927,787.80
2) CLEARPAVE, LLC	\$872,070.00	\$945,000.00
3) MH2 CONSTRUCTION SERVICES, LLC	\$886,000.00	\$958,930.00
4) GMR TOTAL SERVICES, LLC	\$1,059,747.90	\$1,132,677.90
5) DECROSTA CONSTRUCTION	\$1,072,916.06	\$1,222,814.06

50/10 Calendar Days



for Tyler Volk

I, Richard Stanfield, P.E., hereby certify these bid tabulations to be true and correct.

Tyler Volk

4/10/2026

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 78
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

APRIL 09, 2026
LJA ENGINEERING, INC.
C CORTEZ
APRIL 10, 2026
1417-1578P (9.2)

NO.	ITEM DESCRIPTION	UNIT	QTY	1) HARRIS CONSTRUCTION COMPANY, LLC		2) CLEARPAVE, LLC		3) MHZ CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)									
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$4,858.00	\$4,858.00	\$4,858.00	\$4,858.00	\$4,858.00	\$4,858.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00
3.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	10242	\$46.65	\$477,789.30	\$47.50	\$486,495.00	\$45.28	\$463,757.76
4.	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	4289	\$3.75	\$16,083.75	\$4.00	\$17,156.00	\$3.72	\$15,955.08
5.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1724	\$3.75	\$6,465.00	\$4.00	\$6,896.00	\$3.72	\$6,413.28
6.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	12237	\$2.75	\$33,651.75	\$3.00	\$36,711.00	\$3.78	\$46,255.86
7.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	269.2	\$350.00	\$94,220.00	\$375.00	\$100,950.00	\$349.48	\$94,080.02
8.	STOCKPILE AND UTILITY SPOILS EXCAVATION TO BE USED FOR FILL TO FINAL GRADE WITHIN THE PROJECT LIMITS, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	37840	\$2.50	\$94,600.00	\$2.75	\$104,060.00	\$3.70	\$140,008.00
9.	ROADWAY EXCAVATION TO BE USED FOR FILL TO FINAL GRADE WITHIN THE PROJECT LIMITS, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5063	\$3.00	\$15,189.00	\$2.75	\$13,923.25	\$3.70	\$18,733.10
10.	HAULING, PLACEMENT AND COMPACTION OF EXCAVATION SPOILS TO BE HAULED USING ON-ROAD TRUCKS, TO BE HAULED TO FILL SITE "A", WITHIN 1 MILE OF THE PROJECT, PLACED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, AS PER GEOTECHNICAL ENGINEER'S RECOMMENDATION, COMPLETE IN PLACE	CY	6717	\$5.50	\$36,943.50	\$6.00	\$40,302.00	\$5.28	\$35,465.76
11.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$8,725.00	\$8,725.00	\$7,500.00	\$7,500.00	\$5,338.00	\$5,338.00
12.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	8	\$21.00	\$168.00	\$25.00	\$200.00	\$8.00	\$64.00
13.	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$2,500.00	\$2,500.00	\$1,800.00	\$1,800.00
14.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT, AND REGRADE AREA TO MATCH FINISHED GRADE, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
15.	CITY OF MISSOURI CITY CONSTRUCTION PERMIT, COMPLETE IN PLACE	LS	1	\$15,350.00	\$15,350.00	\$12,500.00	\$12,500.00	\$13,000.00	\$13,000.00
16.	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$209,824.30, COMPLETE IN PLACE	LS	1	\$5,875.00	\$5,875.00	\$3,500.00	\$3,500.00	\$6,461.62	\$6,461.62
17.	FINAL LOT GRADING OF 50 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$10,495.00	\$10,495.00	\$14,495.98	\$14,495.98	\$11,558.00	\$11,558.00
18.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	129	\$40.00	\$5,160.00	\$35.00	\$4,515.00	\$28.28	\$3,648.12
19.	CONNECT PROPOSED 6" PAVEMENT TO EXISTING 6" PAVEMENT AND DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER APPURTENANCES. COMPLETE IN PLACE	LF	56	\$26.50	\$1,484.00	\$0.01	\$0.56	\$17.28	\$967.68

BID TABULATION FOR:

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 78
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

**APRIL 09, 2026
LJA ENGINEERING, INC.
C CORTEZ
APRIL 10, 2026
1417-1578P (9.2)**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) HARRIS CONSTRUCTION COMPANY, LLC		2) CLEARPAVE, LLC		3) MHZ CONSTRUCTION SERVICES, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
20.	ADA RAMPS, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	8	\$1,625.00	\$13,000.00	\$1,250.00	\$10,000.00	\$1,258.00	\$10,064.00
21.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$200.00	\$400.00	\$0.01	\$0.02	\$0.50	\$1.00
22.	DEMUCK AND FILL EXISTING DRAINAGE SWALE, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	SY	719	\$3.50	\$2,516.50	\$0.01	\$7.19	\$2.88	\$2,070.72
23.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00
24.	FORT BEND COUNTY DEVELOPMENT PERMIT FOR PLACING AND COMPACTING SPOILS, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00
25.	FORT BEND COUNTY DRIVEWAY PERMIT FOR HAULING SPOILS ON SIENNA PARKWAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$849,473.80		\$872,070.00		\$886,000.00
BASE BID MISCELLANEOUS ITEMS									
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	WETLANDS CROSSING FOR TEMPORARY ACCESS ROAD, INCLUDES MATTING, COMPLETE IN PLACE	EA	0	-\$10.00	\$0.00	-\$10.00	\$0.00	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO A TREE MARKED FOR PRESERVATION, COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00	-\$500.00	\$0.00	-\$500.00	\$0.00
SUBTOTAL BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00
ALTERNATE BID NO. 1 FIELD CONDITIONS ITEMS									
1.	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	12237	\$2.00	\$24,474.00	\$2.00	\$24,474.00	\$2.00	\$24,474.00
2.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	269.2	\$200.00	\$53,840.00	\$180.00	\$48,456.00	\$180.00	\$48,456.00
SUBTOTAL ALTERNATE BID NO. 1 FIELD CONDITIONS ITEMS					\$78,314.00		\$72,930.00		\$72,930.00
BID SUMMARY									
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$849,473.80		\$872,070.00		\$886,000.00
BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$849,473.80		\$872,070.00		\$886,000.00
ALTERNATE BID NO. 1									
TOTAL AMOUNT BASE BID					\$849,473.80		\$872,070.00		\$886,000.00
FIELD CONDITIONS ITEMS					\$78,314.00		\$72,930.00		\$72,930.00
TOTAL ALTERNATE BID NO. 1 PLUS BASE BID					\$927,787.80		\$945,000.00		\$958,930.00

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE SIENNA SECTION 7B SIENNA MUNICIPAL UTILITY DISTRICT NO. 7

0

APRIL 09, 2026
LJA ENGINEERING, INC.
C CORTEZ
APRIL 10, 2026
1417-1578P (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

NO.	ITEM DESCRIPTION	UNIT	QTY	4) GMR TOTAL SERVICES, LLC		5) DECROSTA CONSTRUCTION	
				UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)							
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$4,858.00	\$4,858.00	\$4,858.00	\$4,858.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$2,500.00	\$2,500.00
3.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	10242	\$51.00	\$522,342.00	\$48.43	\$496,020.06
4.	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	4289	\$4.50	\$19,300.50	\$4.00	\$17,156.00
5.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1724	\$4.50	\$7,758.00	\$4.00	\$6,896.00
6.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	12237	\$3.80	\$46,500.60	\$4.00	\$48,948.00
7.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	269.2	\$376.50	\$101,353.80	\$375.00	\$100,950.00
8.	STOCKPILE AND UTILITY SPOILS EXCAVATION TO BE USED FOR FILL TO FINAL GRADE WITHIN THE PROJECT LIMITS, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	37840	\$3.50	\$132,440.00	\$5.00	\$189,200.00
9.	ROADWAY EXCAVATION TO BE USED FOR FILL TO FINAL GRADE WITHIN THE PROJECT LIMITS, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5063	\$3.50	\$17,720.50	\$6.00	\$30,378.00
10.	HAULING, PLACEMENT AND COMPACTION OF EXCAVATION SPOILS TO BE HAULED USING ON-ROAD TRUCKS, TO BE HAULED TO FILL SITE "A", WITHIN 1 MILE OF THE PROJECT, PLACED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY WITH MAXIMUM 8" LIFTS, AS PER GEOTECHNICAL ENGINEER'S RECOMMENDATION, COMPLETE IN PLACE	CY	6717	\$9.50	\$63,811.50	\$8.00	\$53,736.00
11.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$2,851.00	\$2,851.00	\$15,000.00	\$15,000.00
12.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTON FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	8	\$9.10	\$72.80	\$25.00	\$200.00
13.	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$6,845.00	\$6,845.00	\$1,000.00	\$1,000.00
14.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT, AND REGRADE AREA TO MATCH FINISHED GRADE, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
15.	CITY OF MISSOURI CITY CONSTRUCTION PERMIT, COMPLETE IN PLACE	LS	1	\$3,000.00	\$3,000.00	\$25,000.00	\$25,000.00
16.	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$209,824.30, COMPLETE IN PLACE	LS	1	\$7,000.00	\$7,000.00	\$25,000.00	\$25,000.00
17.	FINAL LOT GRADING OF 50 LOTS AND ADJACENT RESERVES, COMPLETE IN PLACE	LS	1	\$8,776.00	\$8,776.00	\$30,000.00	\$30,000.00
18.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	129	\$38.90	\$5,018.10	\$40.00	\$5,160.00
19.	CONNECT PROPOSED 6" PAVEMENT TO EXISTING 6" PAVEMENT AND DOWEL INTO EXISTING CONCRETE PAVEMENT AND UNDERCUT, AND ANY OTHER APPURTENANCES. COMPLETE IN PLACE	LF	56	\$1,530.00	\$85,680.00	\$25.00	\$1,400.00

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURT
TO SERVE SIENNA SECTION 78
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

APRIL 09, 2026
LJA ENGINEERING, INC.
C CORTEZ
APRIL 10, 2026
1417-1578P (9.2)

NO.	ITEM DESCRIPTION	UNIT	QTY	4) GMR TOTAL SERVICES, LLC		5) DECROSTA CONSTRUCTION	
				UNIT COST	TOTAL	UNIT COST	TOTAL
20.	ADA RAMPS, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	8	\$1,530.00	\$12,240.00	\$1,500.00	\$12,000.00
21.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$500.00	\$1,000.00	\$100.00	\$200.00
22.	DEMUCK AND FILL EXISTING DRAINAGE SWALE, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	SY	719	\$7.90	\$5,680.10	\$6.00	\$4,314.00
23.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00
24.	FORT BEND COUNTY DEVELOPMENT PERMIT FOR PLACING AND COMPACTING SPOILS, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00
25.	FORT BEND COUNTY DRIVEWAY PERMIT FOR HAULING SPOILS ON SIENNA PARKWAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$1,059,747.90		\$1,072,916.06
BASE BID MISCELLANEOUS ITEMS							
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	WETLANDS CROSSING FOR TEMPORARY ACCESS ROAD, INCLUDES MATTING, COMPLETE IN PLACE	EA	0	-\$10.00	\$0.00	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO A TREE MARKED FOR PRESERVATION, COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00	-\$500.00	\$0.00
SUBTOTAL BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00
ALTERNATE BID NO. 1 FIELD CONDITIONS ITEMS							
1.	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	12237	\$2.00	\$24,474.00	\$4.00	\$48,948.00
2.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	269.2	\$180.00	\$48,456.00	\$375.00	\$100,950.00
SUBTOTAL ALTERNATE BID NO. 1 FIELD CONDITIONS ITEMS					\$72,930.00		\$149,898.00
BID SUMMARY							
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$1,059,747.90		\$1,072,916.06
BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$1,059,747.90		\$1,072,916.06
ALTERNATE BID NO. 1							
TOTAL AMOUNT BASE BID					\$1,059,747.90		\$1,072,916.06
FIELD CONDITIONS ITEMS					\$72,930.00		\$149,898.00
TOTAL ALTERNATE BID NO. 1 PLUS BASE BID					\$1,132,677.90		\$1,222,814.06