

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 85
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
MARCH 19, 2026
LJA ENGINEERING, INC.
C CORTEZ
MARCH 19, 2026
1417-1585P (9.2)

BIDDER NAME	ALTERNATE BID PLUS	
	BASE BID	BASE BID
1) MH2 CONSTRUCTION SERVICES, LLC	\$1,838,183.80	\$2,023,795.80
2) CLEARPAVE, LLC	\$1,845,550.00	\$2,031,162.00
3) HARRIS CONSTRUCTION COMPANY, LLC	\$1,851,200.55	\$2,036,812.55
4) PRINCIPAL PAVING CONTRACTORS, LTD	\$1,897,206.00	\$2,082,818.00
5) D&J CONSTRUCTION, INC	\$1,906,304.50	\$2,091,916.50
6) ICON GC LLC	\$2,030,690.00	\$2,216,302.00

60/10 Contract Days

for *Tyler Volk*

I, RICHARD STANFIELD, P.E., hereby certify these bid tabulations to be true and correct.



Tyler Volk

3/19/2026

BID TABULATION FOR:

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 85
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
MARCH 19, 2026
LJA ENGINEERING, INC.
C CORTEZ
MARCH 19, 2026
1417-1585P (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) MH2 CONSTRUCTION SERVICES, LLC		2) CLEARPAVE, LLC		3) HARRIS CONSTRUCTION COMPANY, LLC		4) PRINCIPAL PAVING CONTRACTORS, LTD	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)											
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI SURVEYING, COMPLETE IN PLACE	LS	1	\$12,039.00	\$12,039.00	\$12,039.00	\$12,039.00	\$12,039.00	\$12,039.00	\$12,039.00	\$12,039.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00
3.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	20762	\$45.38	\$942,179.56	\$46.75	\$970,623.50	\$48.00	\$996,576.00	\$47.00	\$975,814.00
4.	7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	3579	\$49.68	\$177,804.72	\$54.00	\$193,266.00	\$50.15	\$179,486.85	\$53.00	\$189,687.00
5.	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	6456	\$3.63	\$23,435.28	\$4.00	\$25,824.00	\$3.75	\$24,210.00	\$4.00	\$25,824.00
6.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	7478	\$3.63	\$27,145.14	\$4.00	\$29,912.00	\$3.75	\$28,042.50	\$4.00	\$29,912.00
7.	CONNECT PROPOSED 6" CURB TO EXISTING 6" CURB AND 7" PAVEMENT, INCLUDING DOWEL INTO EXISTING CONCRETE PAVEMENT AND ANY NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	215	\$5.18	\$1,113.70	\$10.00	\$2,150.00	\$5.00	\$1,075.00	\$2.00	\$430.00
8.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	29006	\$3.48	\$100,940.88	\$3.25	\$94,269.50	\$3.00	\$87,018.00	\$4.00	\$116,024.00
9.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	638	\$344.48	\$219,778.24	\$375.00	\$239,250.00	\$375.00	\$239,250.00	\$350.00	\$223,300.00
10.	ROADWAY AND LOT EXCAVATION TO BE USED FOR FILL TO FINAL GRADE WITHIN THE PROJECT LIMITS, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, EXCAVATION, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	41491	\$3.68	\$152,686.88	\$2.50	\$103,727.50	\$2.45	\$101,652.95	\$5.00	\$207,455.00
11.	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$1,688.00	\$1,688.00	\$2,500.00	\$2,500.00	\$1,500.00	\$1,500.00	\$500.00	\$500.00
12.	IMPORT FILL, INCLUDES EXCAVATION AND HAUL FROM DESIGNATED STOCKPILE, USING ON ROAD TRUCKS, (0 - 0.5 MILE), PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND FINAL SITE GRADING, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	4513	\$5.88	\$26,536.44	\$7.00	\$31,591.00	\$4.00	\$18,052.00	\$8.00	\$36,104.00
13.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$25,488.00	\$25,488.00	\$32,500.00	\$32,500.00	\$30,915.00	\$30,915.00	\$5,000.00	\$5,000.00
14.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTONS FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	20	\$15.80	\$316.00	\$25.00	\$500.00	\$19.00	\$380.00	\$10.00	\$200.00
15.	CITY OF MISSOURI CITY CONSTRUCTION PERMIT, COMPLETE IN PLACE	LS	1	\$13,298.00	\$13,298.00	\$13,500.00	\$13,500.00	\$10,000.00	\$10,000.00	\$500.00	\$500.00
16.	TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$1,228.00	\$1,228.00	\$1,500.00	\$1,500.00	\$1,425.00	\$1,425.00	\$1,050.00	\$1,050.00
17.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	3	\$0.25	\$0.75	\$0.01	\$0.03	\$200.00	\$600.00	\$50.00	\$150.00
18.	ADA RAMPS, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	24	\$1,258.00	\$30,192.00	\$1,250.00	\$30,000.00	\$1,575.00	\$37,800.00	\$1,408.00	\$33,792.00
19.	MAINTAIN AND REMOVE EXISTING CONSTRUCTION EXIT, AND REGRADE AREA TO MATCH FINISHED GRADE, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
20.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00
21.	REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	28	\$12.00	\$336.00	\$10.00	\$280.00	\$15.50	\$434.00	\$6.00	\$168.00
22.	FINAL LOT AND RESERVE GRADING, COMPLETE IN PLACE	LS	1	\$28,788.00	\$28,788.00	\$25,000.00	\$25,000.00	\$24,750.00	\$24,750.00	\$15,000.00	\$15,000.00
23.	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$514,076.50 , COMPLETE IN PLACE	LS	1	\$11,000.00	\$11,000.00	\$6,659.39	\$6,659.39	\$15,295.00	\$15,295.00	\$1,000.00	\$1,000.00
24.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	320	\$27.68	\$8,857.60	\$35.00	\$11,200.00	\$40.00	\$12,800.00	\$25.00	\$8,000.00
25.	4" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	400	\$25.88	\$10,352.00	\$25.00	\$10,000.00	\$30.00	\$12,000.00	\$20.00	\$8,000.00
26.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	37	\$18.00	\$666.00	\$0.01	\$0.37	\$5.00	\$185.00	\$2.00	\$74.00

BID TABULATION FOR:

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SECTION 85
SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
MARCH 19, 2026
LJA ENGINEERING, INC.
C CORTEZ
MARCH 19, 2026
1417-1585P (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) MH2 CONSTRUCTION SERVICES, LLC		2) CLEARPAVE, LLC		3) HARRIS CONSTRUCTION COMPANY, LLC		4) PRINCIPAL PAVING CONTRACTORS, LTD	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
27.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO PROPOSED 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	347	\$18.00	\$6,246.00	\$0.01	\$3.47	\$5.00	\$1,735.00	\$2.00	\$694.00
28.	CONNECT PROPOSED 7" REINFORCED CONCRETE PAVEMENT TO EXISTING 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	37	\$18.00	\$666.00	\$0.01	\$0.37	\$5.00	\$185.00	\$2.00	\$74.00
29.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	28	\$18.00	\$504.00	\$0.01	\$0.28	\$5.00	\$140.00	\$2.00	\$56.00
30.	REMOVE AND OFFSITE DISPOSAL OF EXISTING ASPHALT PAVING, INCLUDES BASE, COMPLETE IN PLACE	SY	359	\$11.88	\$4,264.92	\$0.01	\$3.59	\$15.75	\$5,654.25	\$1.00	\$359.00
31.	REMOVE EXISTING REINFORCED CONCRETE TYPE"C" GRADE INLET TOP AND REPLACE WITH PROPOSED "H-2" INLET, COMPLETE IN PLACE	EA	1	\$5,132.69	\$5,132.69	\$3,750.00	\$3,750.00	\$2,500.00	\$2,500.00	\$500.00	\$500.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$1,838,183.80		\$1,845,550.00		\$1,851,200.55		\$1,897,206.00
BASE BID BASE BID MISCELLANEOUS ITEMS											
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00	-\$10.00	\$0.00	-\$10.00	\$0.00	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO A TREE MARKED FOR PRESERVATION, COMPLETE IN PLACE	EA	0	\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00	\$0.00	\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00	-\$500.00	\$0.00	-\$500.00	\$0.00	-\$500.00	\$0.00
SUBTOTAL BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00		\$0.00
ALTERNATE BID FIELD CONDITIONS ITEMS											
1.	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER. COMPLETE IN PLACE	SY	29006	\$2.00	\$58,012.00	\$2.00	\$58,012.00	\$2.00	\$58,012.00	\$2.00	\$58,012.00
2.	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER. COMPLETE IN PLACE	TON	638	\$200.00	\$127,600.00	\$200.00	\$127,600.00	\$200.00	\$127,600.00	\$200.00	\$127,600.00
SUBTOTAL ALTERNATE BID FIELD CONDITIONS ITEMS					\$185,612.00		\$185,612.00		\$185,612.00		\$185,612.00
BID SUMMARY											
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$1,838,183.80		\$1,845,550.00		\$1,851,200.55		\$1,897,206.00
BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$1,838,183.80		\$1,845,550.00		\$1,851,200.55		\$1,897,206.00
ALTERNATE BID											
TOTAL AMOUNT BASE BID					\$1,838,183.80		\$1,845,550.00		\$1,851,200.55		\$1,897,206.00
FIELD CONDITIONS ITEMS					\$185,612.00		\$185,612.00		\$185,612.00		\$185,612.00
TOTAL ALTERNATE BID PLUS BASE BID					\$2,023,795.80		\$2,031,162.00		\$2,036,812.55		\$2,082,818.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LIA JOB NO.

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 85
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 MARCH 19, 2026
 LJA ENGINEERING, INC.
 C CORTEZ
 MARCH 19, 2026
 1417-1585P (9.2)**

NO.	ITEM DESCRIPTION	UNIT	QTY	5) D&J CONSTRUCTION, INC		6) ICON GC LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)							
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI SURVEYING, COMPLETE IN PLACE	LS	1	\$12,039.00	\$12,039.00	\$12,039.00	\$12,039.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP. 281.499.4539, COMPLETE IN PLACE	LS	1	\$3,500.00	\$3,500.00	\$35,000.00	\$35,000.00
3.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	20762	\$48.00	\$996,576.00	\$48.00	\$996,576.00
4.	7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	3579	\$54.00	\$193,266.00	\$52.00	\$186,108.00
5.	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	6456	\$3.75	\$24,210.00	\$3.50	\$22,596.00
6.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	7478	\$3.75	\$28,042.50	\$3.50	\$26,173.00
7.	CONNECT PROPOSED 6" CURB TO EXISTING 6" CURB AND 7" PAVEMENT, INCLUDING DOWEL INTO EXISTING CONCRETE PAVEMENT AND ANY NECESSARY APPURTENANCES. COMPLETE IN PLACE	LF	215	\$10.00	\$2,150.00	\$5.00	\$1,075.00
8.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	29006	\$3.50	\$101,521.00	\$3.75	\$108,772.50
9.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER. COMPLETE IN PLACE	TON	638	\$360.00	\$229,680.00	\$380.00	\$242,440.00
10.	ROADWAY AND LOT EXCAVATION TO BE USED FOR FILL TO FINAL GRADE WITHIN THE PROJECT LIMITS, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, EXCAVATION, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	41491	\$3.00	\$124,473.00	\$4.50	\$186,709.50
11.	HAULING AND PLACING OF ONSITE STRIPPING ON LOTS AND RESERVES, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$18,000.00	\$18,000.00
12.	IMPORT FILL, INCLUDES EXCAVATION AND HAUL FROM DESIGNATED STOCKPILE, USING ON ROAD TRUCKS, (0 - 0.5 MILE), PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND FINAL SITE GRADING, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	4513	\$8.00	\$36,104.00	\$12.00	\$54,156.00
13.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$32,000.00	\$32,000.00	\$25,000.00	\$25,000.00
14.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTONS FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	20	\$15.00	\$300.00	\$16.00	\$320.00
15.	CITY OF MISSOURI CITY CONSTRUCTION PERMIT, COMPLETE IN PLACE	LS	1	\$18,000.00	\$18,000.00	\$16,370.00	\$16,370.00
16.	TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$1,400.00	\$1,400.00	\$1,200.00	\$1,200.00
17.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	3	\$1.00	\$3.00	\$25.00	\$75.00
18.	ADA RAMPS, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	24	\$1,200.00	\$28,800.00	\$1,450.00	\$34,800.00
19.	MAINTAIN AND REMOVE EXISTING CONSTRUCTION EXIT, AND REGRADE AREA TO MATCH FINISHED GRADE, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
20.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00
21.	REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	28	\$15.00	\$420.00	\$6.00	\$168.00
22.	FINAL LOT AND RESERVE GRADING, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$27,000.00	\$27,000.00
23.	PROVIDE SUBDIVISION BOND IN THE AMOUNT OF \$514,076.50 , COMPLETE IN PLACE	LS	1	\$12,500.00	\$12,500.00	\$10,200.00	\$10,200.00
24.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	320	\$35.00	\$11,200.00	\$24.00	\$7,680.00
25.	4" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	400	\$30.00	\$12,000.00	\$16.00	\$6,400.00
26.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	37	\$15.00	\$555.00	\$8.00	\$296.00

BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SECTION 85
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 7
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 MARCH 19, 2026
 LJA ENGINEERING, INC.
 C CORTEZ
 MARCH 19, 2026
 1417-1585P (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

NO.	ITEM DESCRIPTION	UNIT	QTY	5) D&J CONSTRUCTION, INC		6) ICON GC LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL
27.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO PROPOSED 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	347	\$15.00	\$5,205.00	\$8.00	\$2,776.00
28.	CONNECT PROPOSED 7" REINFORCED CONCRETE PAVEMENT TO EXISTING 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	37	\$15.00	\$555.00	\$8.00	\$296.00
29.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	28	\$15.00	\$420.00	\$8.00	\$224.00
30.	REMOVE AND OFFSITE DISPOSAL OF EXISTING ASPHALT PAVING, INCLUDES BASE, COMPLETE IN PLACE	SY	359	\$15.00	\$5,385.00	\$10.00	\$3,590.00
31.	REMOVE EXISTING REINFORCED CONCRETE TYPE"C" GRADE INLET TOP AND REPLACE WITH PROPOSED "H-2" INLET, COMPLETE IN PLACE	EA	1	\$2,500.00	\$2,500.00	\$2,650.00	\$2,650.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$1,906,304.50		\$2,030,690.00
BASE BID BASE BID MISCELLANEOUS ITEMS							
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO A TREE MARKED FOR PRESERVATION, COMPLETE IN PLACE	EA	0	\$1,000.00	\$0.00	\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00	-\$500.00	\$0.00
SUBTOTAL BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00
ALTERNATE BID FIELD CONDITIONS ITEMS							
1.	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER. COMPLETE IN PLACE	SY	29006	\$2.00	\$58,012.00	\$2.00	\$58,012.00
2.	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER. COMPLETE IN PLACE	TON	638	\$200.00	\$127,600.00	\$200.00	\$127,600.00
SUBTOTAL ALTERNATE BID FIELD CONDITIONS ITEMS					\$185,612.00		\$185,612.00
BID SUMMARY							
BASE BID PAVING IMPROVEMENT ITEMS (INTERNAL) - (SIENNA MUD NO. 7)					\$1,906,304.50		\$2,030,690.00
BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$1,906,304.50		\$2,030,690.00
ALTERNATE BID							
TOTAL AMOUNT BASE BID					\$1,906,304.50		\$2,030,690.00
FIELD CONDITIONS ITEMS					\$185,612.00		\$185,612.00
TOTAL ALTERNATE BID PLUS BASE BID					\$2,091,916.50		\$2,216,302.00