


BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SPRINGS WAY PHASE 2
SIENNA MANAGEMENT DISTRICT
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
NOVEMBER 13, 2025
LJA ENGINEERING, INC.
C CORTEZ
NOVEMBER 17, 2025
1475-1505B (9.2)

BID OPENING DATE:**BID OPENING LOCATION:****TABULATION BY:****TABULATION DATE:****LJA JOB NO.**

BIDDER NAME	BASE BID	ALTERNATE BID NO. 1
		PLUS BASE BID
1) CONSTA BUILD LLC	\$370,607.00	\$399,317.00
2) GMR TOTAL SERVICES, LLC	\$375,157.00	\$436,808.00
3) MH2 CONSTRUCTION SERVICES, LLC	\$378,354.00	\$407,064.00
4) D&J CONSTRUCTION, INC	\$388,007.00	\$435,312.00
5) HARRIS CONSTRUCTION COMPANY, LLC	\$412,387.05	\$441,097.05

40/50 CONTRACT DAYS

11/20/2025

I, RICHARD STANFIELD, JR., E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SPRINGS WAY PHASE 2
 SIENNA MANAGEMENT DISTRICT
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 NOVEMBER 13, 2025
 LJA ENGINEERING, INC.
 C CORTEZ
 NOVEMBER 17, 2025
 1475-1505B (9.2)**

				1) CONSTA BUILD LLC		2) GMR TOTAL SERVICES, LLC		3) MH2 CONSTRUCTION SERVICES, LLC		4) D&J CONSTRUCTION, INC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS											
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI SURVEYING, COMPLETE IN PLACE	LS	1	\$2,200.00	\$2,200.00	\$2,200.00	\$2,200.00	\$2,200.00	\$2,200.00	\$2,750.00	\$2,750.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,200.00	\$2,200.00	\$2,200.00	\$2,200.00	\$2,200.00	\$2,200.00	\$2,750.00	\$2,750.00
3.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	3824	\$48.00	\$183,552.00	\$56.00	\$214,144.00	\$51.78	\$198,006.72	\$57.50	\$219,880.00
4.	7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	278	\$72.00	\$20,016.00	\$71.00	\$19,738.00	\$69.38	\$19,287.64	\$62.50	\$17,375.00
5.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2095	\$4.00	\$8,380.00	\$5.00	\$10,475.00	\$3.98	\$8,338.10	\$4.00	\$8,380.00
6.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	4815	\$4.00	\$19,260.00	\$3.80	\$18,297.00	\$4.51	\$21,715.65	\$4.00	\$19,260.00
7.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	106	\$350.00	\$37,100.00	\$409.00	\$43,354.00	\$361.58	\$38,327.48	\$388.00	\$41,128.00
8.	ROADWAY EXCAVATION OF MATERIAL, INCLUDES STRIPPING, STOCKPILING OF DIRT ADJACENT TO PROJECT SITE AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5932	\$4.00	\$23,728.00	\$4.00	\$23,728.00	\$3.98	\$23,609.36	\$4.00	\$23,728.00
9.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$4,500.00	\$4,500.00	\$5,345.00	\$5,345.00	\$11,088.00	\$11,088.00	\$5,300.00	\$5,300.00
10.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTONS FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	4	\$30.00	\$120.00	\$13.00	\$52.00	\$18.98	\$75.92	\$15.00	\$60.00
11.	TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, ETC.), PER TMUTCD, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$4,500.00	\$4,500.00	\$1,794.00	\$1,794.00	\$9,418.00	\$9,418.00	\$2,500.00	\$2,500.00
12.	CITY OF MISSOURI CITY CONSTRUCTION PERMIT, COMPLETE IN PLACE	LS	1	\$22,000.00	\$22,000.00	\$2,415.00	\$2,415.00	\$12,101.00	\$12,101.00	\$6,250.00	\$6,250.00
13.	2' SAWCUT, REMOVE AND OFFSITE DISPOSAL OF EXISTING 7" CONCRETE PAVEMENT, EXPOSE, CLEAN, AND TIE EXISTING REBAR INTO PROPOSED 7" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	137	\$45.00	\$6,165.00	\$19.00	\$2,603.00	\$12.98	\$1,778.26	\$20.00	\$2,740.00
14.	TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,300.00	\$2,600.00	\$1,547.00	\$3,094.00	\$1,288.00	\$2,576.00	\$2,000.00	\$4,000.00
15.	ADA RAMPS, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	4	\$1,800.00	\$7,200.00	\$1,791.00	\$7,164.00	\$1,668.00	\$6,672.00	\$1,500.00	\$6,000.00
16.	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
17.	REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	80	\$20.00	\$1,600.00	\$24.00	\$1,920.00	\$12.00	\$960.00	\$15.00	\$1,200.00
18.	FINAL GRADING OF RIGHT-OF-WAY, COMPLETE IN PLACE	LS	1	\$9,000.00	\$9,000.00	\$3,262.00	\$3,262.00	\$2,800.00	\$2,800.00	\$5,000.00	\$5,000.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SPRINGS WAY PHASE 2
SIENNA MANAGEMENT DISTRICT
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
NOVEMBER 13, 2025
LJA ENGINEERING, INC.
C CORTEZ
NOVEMBER 17, 2025
1475-1505B (9.2)

				1) CONSTA BUILD LLC		2) GMR TOTAL SERVICES, LLC		3) MH2 CONSTRUCTION SERVICES, LLC		4) D&J CONSTRUCTION, INC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
19.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	61	\$45.00	\$2,745.00	\$46.00	\$2,806.00	\$36.36	\$2,217.96	\$35.00	\$2,135.00
20.	4" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	61	\$30.00	\$1,830.00	\$36.00	\$2,196.00	\$33.08	\$2,017.88	\$30.00	\$1,830.00
21.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	37	\$30.00	\$1,110.00	\$28.00	\$1,036.00	\$58.00	\$2,146.00	\$20.00	\$740.00
22.	HAULING AND PLACING OF ONSITE STRIPPING ON RESERVES, COMPLETE IN PLACE	LS	1	\$6,800.00	\$6,800.00	\$3,523.00	\$3,523.00	\$7,029.53	\$7,029.53	\$500.00	\$500.00
23.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$1.00	\$1.00	\$169.00	\$169.00	\$0.50	\$0.50	\$1.00	\$1.00
24.	REMOVE AND OFFSITE DISPOSAL OF EXISTING REINFORCED CONCRETE INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$1,642.00	\$1,642.00	\$1,788.00	\$1,788.00	\$12,000.00	\$12,000.00
25.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$500.00	\$1,000.00	\$1,000.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS					\$370,607.00		\$375,157.00		\$378,354.00		\$388,007.00
BASE BID BASE BID MISCELLANEOUS ITEMS											
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00	-\$10.00	\$0.00	-\$10.00	\$0.00	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO A TREE MARKED FOR PRESERVATION, COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00	-\$500.00	\$0.00	-\$500.00	\$0.00	-\$500.00	\$0.00
SUBTOTAL BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00		\$0.00
ALTERNATE BID NO. 1 FIELD CONDITION ITEMS											
1.	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	4815	\$2.00	\$9,630.00	\$3.80	\$18,297.00	\$2.00	\$9,630.00	\$3.00	\$14,445.00
2.	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	106	\$180.00	\$19,080.00	\$409.00	\$43,354.00	\$180.00	\$19,080.00	\$310.00	\$32,860.00
SUBTOTAL ALTERNATE BID NO. 1 FIELD CONDITION ITEMS					\$28,710.00		\$61,651.00		\$28,710.00		\$47,305.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SPRINGS WAY PHASE 2
SIENNA MANAGEMENT DISTRICT
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
NOVEMBER 13, 2025
LJA ENGINEERING, INC.
C CORTEZ
NOVEMBER 17, 2025
1475-1505B (9.2)

				1) CONSTA BUILD LLC		2) GMR TOTAL SERVICES, LLC		3) MH2 CONSTRUCTION SERVICES, LLC		4) D&J CONSTRUCTION, INC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BID SUMMARY											
BASE BID PAVING IMPROVEMENT ITEMS					\$370,607.00		\$375,157.00		\$378,354.00		\$388,007.00
BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00		\$0.00		\$0.00		\$0.00
TOTAL AMOUNT BASE BID					\$370,607.00		\$375,157.00		\$378,354.00		\$388,007.00
ALTERNATE BID NO. 1											
TOTAL AMOUNT BASE BID					\$370,607.00		\$375,157.00		\$378,354.00		\$388,007.00
FIELD CONDITION ITEMS					\$28,710.00		\$61,651.00		\$28,710.00		\$47,305.00
TOTAL ALTERNATE BID NO. 1 PLUS BASE BID					\$399,317.00		\$436,808.00		\$407,064.00		\$435,312.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SPRINGS WAY PHASE 2
 SIENNA MANAGEMENT DISTRICT
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 NOVEMBER 13, 2025
 LJA ENGINEERING, INC.
 C CORTEZ
 NOVEMBER 17, 2025
 1475-1505B (9.2)**

5) HARRIS CONSTRUCTION COMPANY, LLC

NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
BASE BID PAVING IMPROVEMENT ITEMS					
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI SURVEYING, COMPLETE IN PLACE	LS	1	\$2,200.00	\$2,200.00
2.	AS BUILT CONSTRUCTION STAKING BY THE CONTRACTOR PER JON BORDOVSKY, GBI PARTNERS, LP, 281.499.4539, COMPLETE IN PLACE	LS	1	\$2,200.00	\$2,200.00
3.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	3824	\$55.45	\$212,040.80
4.	7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	278	\$63.75	\$17,722.50
5.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2095	\$4.15	\$8,694.25
6.	8" LIME STABILIZED SUBGRADE, (MISSOURI CITY SPECIFICATIONS), COMPLETE IN PLACE	SY	4815	\$4.05	\$19,500.75
7.	LIME FOR 8" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT (44 LBS/SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	106	\$415.00	\$43,990.00
8.	ROADWAY EXCAVATION OF MATERIAL, INCLUDES STRIPPING, STOCKPILING OF DIRT ADJACENT TO PROJECT SITE AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5932	\$5.00	\$29,660.00
9.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$10,575.00	\$10,575.00
10.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTONS FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE	EA	4	\$21.00	\$84.00
11.	TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, ETC.), PER TMUTCD, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$12,755.00	\$12,755.00
12.	CITY OF MISSOURI CITY CONSTRUCTION PERMIT, COMPLETE IN PLACE	LS	1	\$15,000.00	\$15,000.00
13.	2' SAWCUT, REMOVE AND OFFSITE DISPOSAL OF EXISTING 7" CONCRETE PAVEMENT, EXPOSE, CLEAN, AND TIE EXISTING REBAR INTO PROPOSED 7" CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	137	\$48.25	\$6,610.25
14.	TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,995.00	\$3,990.00
15.	ADA RAMPS, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	4	\$1,825.00	\$7,300.00
16.	INSTALLATION AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00
17.	REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	80	\$16.50	\$1,320.00
18.	FINAL GRADING OF RIGHT-OF-WAY, COMPLETE IN PLACE	LS	1	\$3,200.00	\$3,200.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

**CONSTRUCTION OF THE PAVING AND APPURTENANCES
 TO SERVE SIENNA SPRINGS WAY PHASE 2
 SIENNA MANAGEMENT DISTRICT
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 NOVEMBER 13, 2025
 LJA ENGINEERING, INC.
 C CORTEZ
 NOVEMBER 17, 2025
 1475-1505B (9.2)**

5) HARRIS CONSTRUCTION COMPANY, LLC

NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
19.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	61	\$40.00	\$2,440.00
20.	4" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	61	\$25.00	\$1,525.00
21.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	37	\$28.50	\$1,054.50
22.	HAULING AND PLACING OF ONSITE STRIPPING ON RESERVES, COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00
23.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$200.00	\$200.00
24.	REMOVE AND OFFSITE DISPOSAL OF EXISTING REINFORCED CONCRETE INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$3,325.00	\$3,325.00
25.	FORT BEND COUNTY RIGHT OF WAY PERMIT FOR TIE INTO EXISTING RIGHT OF WAY, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00
SUBTOTAL BASE BID PAVING IMPROVEMENT ITEMS					\$412,387.05
BASE BID BASE BID MISCELLANEOUS ITEMS					
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00
3.	STANDARD DEDUCT FOR DAMAGE TO WETLANDS FENCING BY THE CONTRACTOR, COMPLETE IN PLACE	LF	0	-\$10.00	\$0.00
4.	STANDARD DEDUCT FOR DAMAGE TO A TREE MARKED FOR PRESERVATION, COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00
5.	FORT BEND COUNTY CONSTRUCTION COMPLETION AND FINAL ACCEPTANCE INSPECTION FEES, COMPLETE IN PLACE	EA	0	-\$500.00	\$0.00
SUBTOTAL BASE BID BASE BID MISCELLANEOUS ITEMS					\$0.00
ALTERNATE BID NO. 1 FIELD CONDITION ITEMS					
1.	ADDITIONAL 8" LIME STABILIZED SUBGRADE (MISSOURI CITY SPECIFICATIONS) TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	SY	4815	\$2.00	\$9,630.00
2.	ADDITIONAL LIME FOR SUBGRADE PREPARATION (8% BY WEIGHT) (44 LBS/YD), TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	106	\$180.00	\$19,080.00
SUBTOTAL ALTERNATE BID NO. 1 FIELD CONDITION ITEMS					\$28,710.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES
TO SERVE SIENNA SPRINGS WAY PHASE 2
SIENNA MANAGEMENT DISTRICT
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
NOVEMBER 13, 2025
LJA ENGINEERING, INC.
C CORTEZ
NOVEMBER 17, 2025
1475-1505B (9.2)

5) HARRIS CONSTRUCTION COMPANY, LLC					
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL

BID SUMMARY

BASE BID PAVING IMPROVEMENT ITEMS	\$412,387.05
BASE BID BASE BID MISCELLANEOUS ITEMS	\$0.00
TOTAL AMOUNT BASE BID	\$412,387.05

ALTERNATE BID NO. 1

TOTAL AMOUNT BASE BID	\$412,387.05
FIELD CONDITION ITEMS	\$28,710.00
TOTAL ALTERNATE BID NO. 1 PLUS BASE BID	\$441,097.05