

BID TABULATION FOR:


CONSTRUCTION OF THE RIVER'S EDGE LIFT STATION NO. 2 - PHASE 1  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 144  
CITY OF CONROE E.T.J., MONTGOMERY COUNTY, TEXAS  
MARCH 11, 2021  
LJA ENGINEERING, INC.  
A.CAROTHERS  
MARCH 17, 2021  
1628-4409 (9.2)

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID	BID INCLUDING ALTERNATE BID ITEMS
1) WALSH CONSTRUCTION COMPANY, LLC	\$543,412.00	\$669,412.00
2) 5J SERVICES, LLC	\$584,650.00	\$728,650.00
3) PRINCIPAL PLANT SERVICES	\$588,719.00	\$678,719.00
4) T & C CONSTRUCTION,LTD	\$658,160.00	\$766,160.00
5) PELTIER BROTHERS CONSTRUCTION	\$827,363.00	\$877,763.00

CALENDAR DAYS 150/180

*E. Mariana Cuellar*  
03/25/2021



*E. Mariana Cuellar*

I, Mariana Cuellar, PE., hereby certify these bid tabulations to be true and correct.

LJA Engineering, Inc.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE RIVER'S EDGE LIFT STATION NO. 2 - PHASE 1  
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 144  
 CITY OF CONROE E.T.J., MONTGOMERY COUNTY, TEXAS  
 MARCH 11, 2021  
 LJA ENGINEERING, INC.  
 A.CAROTHERS  
 MARCH 17, 2021  
 1628-4409 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) WALSH CONSTRUCTION COMPANY, LLC		2) 5J SERVICES, LLC		3) PRINCIPAL PLANT SERVICES	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>SANITARY LIFT STATION ITEMS</b>									
1	SITE WORK, INCLUDING BUT NOT LIMITED TO SITE GRADING, HYDROMULCH SEEDING, SITE DRAINAGE, AND EQUIPMENT SLABS , COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$7,500.00	\$7,500.00	\$19,000.00	\$19,000.00
2	8' CONCRETE WET WELL AND VALVE PAD, INCLUDING ACCESS HATCHES, VENT, AND ALL APPURTENANCES WITH DRAWINGS, COMPLETE IN PLACE	LS	1	\$155,000.00	\$155,000.00	\$214,633.00	\$214,633.00	\$292,400.00	\$292,400.00
3	7.5 HP SUBMERSIBLE PUMP WITH MINIMUM EFFICIENCY OF 42% AT 152 GPM AND 48' T.D.H., INCLUDING DISCHARGE ELBOW, GUIDE RAILS, AND ALL APPURTENANCES FOR PROPOSED PUMPS, COMPLETE IN PLACE	EA	2	\$22,000.00	\$44,000.00	\$7,500.00	\$15,000.00	\$16,900.00	\$33,800.00
4	SANITARY LIFT STATION AND VALVE PAD PIPING, INCLUDING PIPE, VALVES, FITTINGS, SUPPORTS, AND ALL APPURTENANCES, COMPLETE IN PLACE	LS	1	\$72,000.00	\$72,000.00	\$49,000.00	\$49,000.00	\$22,500.00	\$22,500.00
5	CARBON ODOR SCRUBBER (PURE AIR DS-200 OR ECS TM-200 OR PRE-APPROVED EQUAL) WITH ALL REQUIRED PIPING AND APPURTENANCES, COMPLETE IN PLACE	EA	1	\$21,000.00	\$21,000.00	\$14,000.00	\$14,000.00	\$16,600.00	\$16,600.00
6	6" REINFORCED CONCRETE PAVEMENT WITH 8" LIME OR CEMENT STABILIZED SUBGRADE EXTENDING 1' OUTSIDE OF PAVEMENT (AS SHOWN ON PLANS), COMPLETE IN PLACE	SY	153	\$125.00	\$19,125.00	\$75.00	\$11,475.00	\$135.00	\$20,655.00
7	6" CRUSHED CONCRETE SITE COVER WITH GEOFABRIC(TENSAR TRIAX TX 140 OR APPROVED EQUAL), COMPLETE IN PLACE	SY	272	\$25.00	\$6,800.00	\$40.00	\$10,880.00	\$35.00	\$9,520.00
8	12" PVC ASTM D3034 SDR 26, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	46	\$72.00	\$3,312.00	\$450.00	\$20,700.00	\$600.00	\$27,600.00
9	6" AWWA C900, FORCE MAIN, DR 18, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	18	\$160.00	\$2,880.00	\$125.00	\$2,250.00	\$200.00	\$3,600.00
10	1" P.V.C. WATER LINE, COMPLETE IN PLACE	LF	21	\$200.00	\$4,200.00	\$100.00	\$2,100.00	\$10.00	\$210.00
11	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	64	\$10.00	\$640.00	\$10.00	\$640.00	\$1.00	\$64.00
12	8' TALL WOOD FENCE WITH STEEL POSTS, WITH 14 FOOT DOUBLE SWING GATE, AND ALL APPURTENANCES, (AS SHOWN ON PLANS), COMPLETE IN PLACE	LF	290	\$55.00	\$15,950.00	\$95.00	\$27,550.00	\$75.00	\$21,750.00
13	PROVIDE AND INSTALL REDUCED PRESSURE BACKFLOW PREVENTER, NON-FREEZE HOSE BIB, ALL NECESSARY APPURTENANCES, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00	\$4,500.00	\$4,500.00	\$500.00	\$500.00
14	4" PIPE BOLLARD, COMPLETE IN PLACE	EA	8	\$250.00	\$2,000.00	\$600.00	\$4,800.00	\$375.00	\$3,000.00
15	CONNECT PROPOSED SANITARY SEWER LINE TO PROPOSED SANITARY SEWER (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$2,000.00	\$2,000.00	\$500.00	\$500.00
16	CONNECT PROPOSED FORCE MAIN TO PROPOSED FORCE MAIN (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$1,000.00	\$1,000.00	\$100.00	\$100.00
17	CONNECT PROPOSED 1" WATER LINE TO PROPOSED 1" WATER LINE (BY OTHERS) INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$1,000.00	\$1,000.00	\$100.00	\$100.00
18	ALLOWANCE FOR ELECTRIC SERVICE PROVIDER EXACT AMOUNT WILL BE REIMBURSED TO CONTRACTOR UPON SUBMITTAL OF INVOICE FROM ELECTRIC SERVICE PROVIDER, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
19	NEW 200A 480V ELECTRICAL SERVICE ENTRANCE AND RACK WITH METERING PER UTILITY STANDARDS, WITH LIGHTING, DISCONNECTS AND ALL NECESSARY CONDUITS AND CABLES, COMPLETE IN PLACE	LS	1	\$6,500.00	\$6,500.00	\$6,000.00	\$6,000.00	\$39,000.00	\$39,000.00
20	NEW LIFT STATION CONTROL PANEL WITH ALL BREAKERS, MOTORS STARTERS, TRANSFORMER WITH PANEL BOARDS, SURGE PROTECTION AND ALL ASSOCIATED WIRE, CONDUITS, CABLES AND CONTROL, COMPLETE IN PLACE	LS	1	\$60,000.00	\$60,000.00	\$80,000.00	\$80,000.00	\$3,000.00	\$3,000.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE RIVER'S EDGE LIFT STATION NO. 2 - PHASE 1  
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 144  
 CITY OF CONROE E.T.J., MONTGOMERY COUNTY, TEXAS  
 MARCH 11, 2021  
 LJA ENGINEERING, INC.  
 A.CAROTHERS  
 MARCH 17, 2021  
 1628-4409 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) WALSH CONSTRUCTION COMPANY, LLC		2) 5J SERVICES, LLC		3) PRINCIPAL PLANT SERVICES	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
21	NEW PROPANE GENERATOR WITH NATURAL GAS CONVERTER AND 200A AUTOMATIC ASSOCIATED TRANSFER SWITCH, WITH POWER AND CONTROLS, CONDUIT AND CABLE, COMPLETE IN PLACE	LS	1	\$40,000.00	\$40,000.00	\$53,000.00	\$53,000.00	\$37,500.00	\$37,500.00
22	STANDARD SANITARY SEWER MANHOLE ALL DEPTHS, INCLUDES EXCAVATION, BEDDING, BACKFILL, COMPLETE IN PLACE	EA	1	\$4,900.00	\$4,900.00	\$6,000.00	\$6,000.00	\$4,600.00	\$4,600.00
<b>SANITARY LIFT STATION ITEMS SUBTOTAL:</b>					<b>\$501,507.00</b>	<b>\$554,028.00</b>			<b>\$575,999.00</b>
<b>MISCELLANEOUS ITEMS</b>									
1	STORM WATER POLLUTION PREVENTION PLAN, INCLUDING ADMINISTRATION, MAINTENANCE, AND REMOVAL AS REQUIRED BY THE PLANS AND AS DIRECTED BY THE ENGINEER, (TO BE MAINTAINED UNTIL CONTRACTOR'S NOTICE OF TERMINATION IS SUBMITTED), COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$1,000.00	\$1,000.00	\$100.00	\$100.00
2	DEWATERING FOR STRUCTURE, AS REQUIRED BY SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$1.00	\$1.00	\$100.00	\$100.00
3	CONTROL OF SURFACE WATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$1.00	\$1.00	\$100.00	\$100.00
4	DEWATERING OF LINE WORK (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	64	\$25.00	\$1,600.00	\$25.00	\$1,600.00	\$25.00	\$1,600.00
5	EXTRA CEMENT STABILIZED SAND, (1.5 SACKS OF CEMENT PER CUBIC YARD CEMENT STABILIZED SAND), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	20	\$25.00	\$500.00	\$25.00	\$500.00	\$12.00	\$240.00
6	EXTRA 6" REINFORCED CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	50	\$300.00	\$15,000.00	\$75.00	\$3,750.00	\$50.00	\$2,500.00
7	EXTRA 4,000 PSI CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	50	\$350.00	\$17,500.00	\$350.00	\$17,500.00	\$100.00	\$5,000.00
8	EXTRA COST OF UTILITY WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	64	\$10.00	\$640.00	\$15.00	\$960.00	\$10.00	\$640.00
9	EXTRA HYDROMULCH SEEDING OF PROJECT SITE, ( TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	AC	1.5	\$1,750.00	\$2,625.00	\$2,000.00	\$3,000.00	\$1,200.00	\$1,800.00
10	INSTALLATION, MAINTENANCE AND REMOVAL OF CONCRETE TRUCK WASHOUT, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$1,500.00	\$1,500.00	\$100.00	\$100.00
11	FILTER FABRIC FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	270	\$2.00	\$540.00	\$3.00	\$810.00	\$2.00	\$540.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$41,905.00</b>	<b>\$30,622.00</b>			<b>\$12,720.00</b>
<b>ALTERNATE BID ITEMS</b>									
1	12 FEET WIDE, 6" THICK CRUSHED GRAVEL ACCESS ROAD TO SITE, COMPLETE IN PLACE	SY	3600	\$35.00	\$126,000.00	\$40.00	\$144,000.00	\$25.00	\$90,000.00
<b>ALTERNATE BID ITEMS SUBTOTAL:</b>					<b>\$126,000.00</b>	<b>\$144,000.00</b>			<b>\$90,000.00</b>
<b>BIDDING SUMMARY</b>									
SUBTOTAL SANITARY LIFT STATION ITEMS					\$501,507.00	\$554,028.00			\$575,999.00
SUBTOTAL MISCELLANEOUS ITEMS					\$41,905.00	\$30,622.00			\$12,720.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$543,412.00</b>	<b>\$584,650.00</b>			<b>\$588,719.00</b>
<b>ALTERNATE BID ITEMS</b>									
TOTAL AMOUNT BASE BID					\$543,412.00	\$584,650.00			\$588,719.00
SUBTOTAL ALTERNATE BID ITEMS					\$126,000.00	\$144,000.00			\$90,000.00
<b>TOTAL AMOUNT INCLUDING ALTERNATE BID ITEMS</b>					<b>\$669,412.00</b>	<b>\$728,650.00</b>			<b>\$678,719.00</b>

**BID TABULATION FOR:**

CONSTRUCTION OF THE RIVER'S EDGE LIFT STATION NO. 2 - PHASE 1  
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 144  
 CITY OF CONROE E.T.J., MONTGOMERY COUNTY, TEXAS  
 MARCH 11, 2021  
 LJA ENGINEERING, INC.  
 A.CAROTHERS  
 MARCH 17, 2021  
 1628-4409 (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

ITEM	DESCRIPTION	UNIT	QTY	4) T & C CONSTRUCTION,LTD		5) PELTIER BROTHERS CONSTRUCTION	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>SANITARY LIFT STATION ITEMS</b>							
1	SITE WORK, INCLUDING BUT NOT LIMITED TO SITE GRADING, HYDROMULCH SEEDING, SITE DRAINAGE, AND EQUIPMENT SLABS , COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$2,400.00	\$2,400.00
2	8' CONCRETE WET WELL AND VALVE PAD, INCLUDING ACCESS HATCHES, VENT, AND ALL APPURTENANCES WITH DRAWINGS, COMPLETE IN PLACE	LS	1	\$247,000.00	\$247,000.00	\$552,000.00	\$552,000.00
3	7.5 HP SUBMERSIBLE PUMP WITH MINIMUM EFFICIENCY OF 42% AT 152 GPM AND 48' T.D.H., INCLUDING DISCHARGE ELBOW, GUIDE RAILS, AND ALL APPURTENANCES FOR PROPOSED PUMPS, COMPLETE IN PLACE	EA	2	\$15,000.00	\$30,000.00	\$10,000.00	\$20,000.00
4	SANITARY LIFT STATION AND VALVE PAD PIPING, INCLUDING PIPE, VALVES, FITTINGS, SUPPORTS, AND ALL APPURTENANCES, COMPLETE IN PLACE	LS	1	\$70,000.00	\$70,000.00	\$30,000.00	\$30,000.00
5	CARBON ODOR SCRUBBER (PURE AIR DS-200 OR ECS TM-200 OR PRE-APPROVED EQUAL) WITH ALL REQUIRED PIPING AND APPURTENANCES, COMPLETE IN PLACE	EA	1	\$20,000.00	\$20,000.00	\$15,000.00	\$15,000.00
6	6" REINFORCED CONCRETE PAVEMENT WITH 8" LIME OR CEMENT STABILIZED SUBGRADE EXTENDING 1' OUTSIDE OF PAVEMENT (AS SHOWN ON PLANS), COMPLETE IN PLACE	SY	153	\$100.00	\$15,300.00	\$98.00	\$14,994.00
7	6" CRUSHED CONCRETE SITE COVER WITH GEOFABRIC(TENSAR TRIAX TX 140 OR APPROVED EQUAL), COMPLETE IN PLACE	SY	272	\$50.00	\$13,600.00	\$39.00	\$10,608.00
8	12" PVC ASTM D3034 SDR 26, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	46	\$500.00	\$23,000.00	\$234.00	\$10,764.00
9	6" AWWA C900, FORCE MAIN, DR 18, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	18	\$100.00	\$1,800.00	\$53.00	\$954.00
10	1" P.V.C. WATER LINE, COMPLETE IN PLACE	LF	21	\$20.00	\$420.00	\$10.00	\$210.00
11	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	64	\$10.00	\$640.00	\$1.00	\$64.00
12	8' TALL WOOD FENCE WITH STEEL POSTS, WITH 14 FOOT DOUBLE SWING GATE, AND ALL APPURTENANCES, (AS SHOWN ON PLANS), COMPLETE IN PLACE	LF	290	\$80.00	\$23,200.00	\$40.00	\$11,600.00
13	PROVIDE AND INSTALL REDUCED PRESSURE BACKFLOW PREVENTER, NON-FREEZE HOSE BIB, ALL NECESSARY APPURTENANCES, COMPLETE IN PLACE	LS	1	\$2,000.00	\$2,000.00	\$2,000.00	\$2,000.00
14	4" PIPE BOLLARD, COMPLETE IN PLACE	EA	8	\$600.00	\$4,800.00	\$200.00	\$1,600.00
15	CONNECT PROPOSED SANITARY SEWER LINE TO PROPOSED SANITARY SEWER (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$60.00	\$60.00
16	CONNECT PROPOSED FORCE MAIN TO PROPOSED FORCE MAIN (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$200.00	\$200.00	\$60.00	\$60.00
17	CONNECT PROPOSED 1" WATER LINE TO PROPOSED 1" WATER LINE (BY OTHERS) INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$100.00	\$100.00	\$480.00	\$480.00
18	ALLOWANCE FOR ELECTRIC SERVICE PROVIDER EXACT AMOUNT WILL BE REIMBURSED TO CONTRACTOR UPON SUBMITTAL OF INVOICE FROM ELECTRIC SERVICE PROVIDER, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
19	NEW 200A 480V ELECTRICAL SERVICE ENTRANCE AND RACK WITH METERING PER UTILITY STANDARDS, WITH LIGHTING, DISCONNECTS AND ALL NECESSARY CONDUITS AND CABLES, COMPLETE IN PLACE	LS	1	\$22,000.00	\$22,000.00	\$6,000.00	\$6,000.00
20	NEW LIFT STATION CONTROL PANEL WITH ALL BREAKERS, MOTORS STARTERS, TRANSFORMER WITH PANEL BOARDS, SURGE PROTECTION AND ALL ASSOCIATED WIRE, CONDUITS, CABLES AND CONTROL, COMPLETE IN PLACE	LS	1	\$60,000.00	\$60,000.00	\$50,000.00	\$50,000.00

**BID TABULATION FOR:**

CONSTRUCTION OF THE RIVER'S EDGE LIFT STATION NO. 2 - PHASE 1  
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 144  
 CITY OF CONROE E.T.J., MONTGOMERY COUNTY, TEXAS  
 MARCH 11, 2021  
 LJA ENGINEERING, INC.  
 A.CAROTHERS  
 MARCH 17, 2021  
 1628-4409 (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

ITEM	DESCRIPTION	UNIT	QTY	4) T & C CONSTRUCTION,LTD		5) PELTIER BROTHERS CONSTRUCTION	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
21	NEW PROPANE GENERATOR WITH NATURAL GAS CONVERTER AND 200A AUTOMATIC ASSOCIATED TRANSFER SWITCH, WITH POWER AND CONTROLS, CONDUIT AND CABLE, COMPLETE IN PLACE	LS	1	\$50,000.00	\$50,000.00	\$40,000.00	\$40,000.00
22	STANDARD SANITARY SEWER MANHOLE ALL DEPTHS, INCLUDES EXCAVATION, BEDDING, BACKFILL, COMPLETE IN PLACE	EA	1	\$8,000.00	\$8,000.00	\$10,000.00	\$10,000.00
<b>SANITARY LIFT STATION ITEMS SUBTOTAL:</b>					<b>\$617,560.00</b>		<b>\$798,794.00</b>
<b>MISCELLANEOUS ITEMS</b>							
1	STORM WATER POLLUTION PREVENTION PLAN, INCLUDING ADMINISTRATION, MAINTENANCE, AND REMOVAL AS REQUIRED BY THE PLANS AND AS DIRECTED BY THE ENGINEER, (TO BE MAINTAINED UNTIL CONTRACTOR'S NOTICE OF TERMINATION IS SUBMITTED), COMPLETE IN PLACE	LS	1	\$3,000.00	\$3,000.00	\$4,800.00	\$4,800.00
2	DEWATERING FOR STRUCTURE, AS REQUIRED BY SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$1.00	\$1.00
3	CONTROL OF SURFACE WATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$1,200.00	\$1,200.00
4	DEWATERING OF LINE WORK (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	64	\$50.00	\$3,200.00	\$1.00	\$64.00
5	EXTRA CEMENT STABILIZED SAND, (1.5 SACKS OF CEMENT PER CUBIC YARD CEMENT STABILIZED SAND), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	20	\$30.00	\$600.00	\$30.00	\$600.00
6	EXTRA 6" REINFORCED CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	50	\$200.00	\$10,000.00	\$180.00	\$9,000.00
7	EXTRA 4,000 PSI CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	50	\$200.00	\$10,000.00	\$180.00	\$9,000.00
8	EXTRA COST OF UTILITY WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	64	\$50.00	\$3,200.00	\$1.00	\$64.00
9	EXTRA HYDROMULCH SEEDING OF PROJECT SITE, ( TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	AC	1.5	\$1,500.00	\$2,250.00	\$1,800.00	\$2,700.00
10	INSTALLATION, MAINTENANCE AND REMOVAL OF CONCRETE TRUCK WASHOUT, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$600.00	\$600.00
11	FILTER FABRIC FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	270	\$5.00	\$1,350.00	\$2.00	\$540.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$40,600.00</b>		<b>\$28,569.00</b>
<b>ALTERNATE BID ITEMS</b>							
1	12 FEET WIDE, 6" THICK CRUSHED GRAVEL ACCESS ROAD TO SITE, COMPLETE IN PLACE	SY	3600	\$30.00	\$108,000.00	\$14.00	\$50,400.00
<b>ALTERNATE BID ITEMS SUBTOTAL:</b>					<b>\$108,000.00</b>		<b>\$50,400.00</b>
<b>BIDDING SUMMARY</b>							
SUBTOTAL SANITARY LIFT STATION ITEMS					\$617,560.00		\$798,794.00
SUBTOTAL MISCELLANEOUS ITEMS					\$40,600.00		\$28,569.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$658,160.00</b>		<b>\$827,363.00</b>
<b>ALTERNATE BID ITEMS</b>							
TOTAL AMOUNT BASE BID					\$658,160.00		\$827,363.00
SUBTOTAL ALTERNATE BID ITEMS					\$108,000.00		\$50,400.00
<b>TOTAL AMOUNT INCLUDING ALTERNATE BID ITEMS</b>					<b>\$766,160.00</b>		<b>\$877,763.00</b>