BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

BIDDER NAME	BASE BID
1) ARS CONSTRUCTION LLC	$1,374,001.00
2) GMR TOTAL SERVICES, LLC	$1,405,502.40
3) HARRIS CONSTRUCTION COMPANY, LLC	$1,409,127.34
4) JSS CONSTRUCTION< LLC	$1,427,787.03
5) AR TURNKEE	$1,511,463.80
6) TEJAS UNDERGROUND UTILITIES LLC	$1,657,045.00
7) JTM CONSTRUCTION, LLC	$1,708,153.72
8) GM VERA'S CONSTRUCTION	$1,709,997.64
9) UCS: UNDERGROUND CONSTRUCTION SOLUTIONS	$1,796,781.00
10) REDDICO CONSTRUCTION COMPANY, INC.	$1,798,838.40
11) R CONSTRUCTION CIVIL, LLC	$1,842,637.00
12) ISJ UNDERGROUND UTILITIES	$1,857,234.00
13) NERIE CONSTRUCTION LLC	$2,299,776.20

40/50 CALENDAR DAYS

I, Everett Deao, P.E., hereby certify these bid tabulations to be true and correct.



11/24/2026

FRN F-1386
LJA, Inc.
O:\LAND\1882\2601\11192026_Offsite Water Line, Sewer, Force Main_BT

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				1) ARS CONSTRUCTION LLC		2) GMR TOTAL SERVICES, LLC		3) HARRIS CONSTRUCTION COMPANY, LLC		4) JSS CONSTRUCTION, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
WATER DISTRIBUTION SYSTEM ITEMS											
1.	8" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	446	$42.00	$18,732.00	$47.00	$20,962.00	$37.80	$16,858.80	$45.00	$20,070.00
2.	8" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	61	$55.00	$3,355.00	$60.90	$3,714.90	$112.20	$6,844.20	$60.00	$3,660.00
3.	12" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	4339	$65.00	$282,035.00	$61.50	$266,848.50	$60.85	$264,028.15	$65.00	$282,035.00
4.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINFS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	69	$110.00	$7,590.00	$100.00	$6,900.00	$120.75	$8,331.75	$110.00	$7,590.00
5.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	386	$85.00	$32,810.00	$100.00	$38,600.00	$105.65	$40,780.90	$110.00	$42,460.00
6.	LONG SIDE SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, INCLUDES TRENCHLESS CONSTRUCTION FOR CROSSING EXISTING PAVEMENT AND UTILITIES, COMPLETE IN PLACE	LF	97	$220.00	$21,340.00	$46.20	$4,481.40	$110.00	$10,670.00	$900.00	$87,300.00
7.	14" STEEL CASING FOR 8" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	32	$100.00	$3,200.00	$110.00	$3,520.00	$85.85	$2,747.20	$75.00	$2,400.00
8.	18" STEEL CASING FOR 12" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	448	$100.00	$44,800.00	$120.00	$53,760.00	$105.00	$47,040.00	$95.00	$42,560.00
9.	BORE AND JACK OR TUNNEL FOR 8" WATERLINE AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	32	$250.00	$8,000.00	$120.00	$3,840.00	$171.75	$5,496.00	$60.00	$1,920.00
10.	BORE AND JACK OR TUNNEL FOR 12" WATERLINE AND 18" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	448	$130.00	$58,240.00	$120.00	$53,760.00	$182.61	$81,809.28	$70.00	$31,360.00
11.	8" PLUG & CLAMP WITH 2" BLOW-OFF VALVE & BOX ASSEMBLY, COMPLETE IN PLACE	EA	2	$2,700.00	$5,400.00	$1,815.00	$3,630.00	$1,015.75	$2,031.50	$900.00	$1,800.00
12.	8" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	2	$2,450.00	$4,900.00	$1,957.00	$3,914.00	$1,981.50	$3,963.00	$2,500.00	$5,000.00
13.	12" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	4	$4,200.00	$16,800.00	$2,683.00	$10,732.00	$3,656.75	$14,627.00	$4,500.00	$18,000.00
14.	FIRE HYDRANTS, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	10	$7,250.00	$72,500.00	$6,178.00	$61,780.00	$6,028.75	$60,287.50	$7,000.00	$70,000.00
15.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$1.00	$5,402.00	$0.70	$3,781.40	$1.00	$5,402.00	$1.00	$5,402.00
16.	DEWATERING FOR WATER LINE, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$20.00	$108,040.00	$20.00	$108,040.00	$20.00	$108,040.00	$20.00	$108,040.00
17.	8" X 8" TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$7,500.00	$7,500.00	$11,820.00	$11,820.00	$6,362.75	$6,362.75	$6,500.00	$6,500.00
18.	12" X 12" BACK TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$9,500.00	$9,500.00	$22,870.00	$22,870.00	$15,854.00	$15,854.00	$9,500.00	$9,500.00
19.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00
20.	ADDITIONAL DUCTILE IRON FITTINGS, ALL DEPTHS, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	TON	1	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00
21.	REMOVE AND REPLACE EXISTING SIDEWALK TO MATCH EXISTING, INCLUDES OFFSITE DISPOSAL, COMPLETE IN PLACE	SY	11	$100.00	$1,100.00	$140.00	$1,540.00	$144.50	$1,589.50	$105.00	$1,155.00
22.	REMOVE AND REPLACE EXISTING ADA RAMP, AS NEEDED FOR CONSTRUCTION, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	1	$3,500.00	$3,500.00	$2,027.00	$2,027.00	$1,850.00	$1,850.00	$1,500.00	$1,500.00
SUBTOTAL WATER DISTRIBUTION SYSTEM ITEMS					**$720,744.00**		**$692,521.20**		**$710,613.53**		**$754,252.00**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				1) ARS CONSTRUCTION LLC		2) GMR TOTAL SERVICES, LLC		3) HARRIS CONSTRUCTION COMPANY, LLC		4) JSS CONSTRUCTION, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
SANITARY SEWER SYSTEM ITEMS											
1.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	10	$150.00	$1,500.00	$62.30	$623.00	$247.10	$2,471.00	$50.00	$500.00
2.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 8' - 12' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	414	$60.00	$24,840.00	$65.90	$27,282.60	$53.00	$21,942.00	$65.00	$26,910.00
3.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	664	$70.00	$46,480.00	$79.80	$52,987.20	$54.15	$35,955.60	$70.00	$46,480.00
4.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 16' - 20' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	977	$85.00	$83,045.00	$97.70	$95,452.90	$68.10	$66,533.70	$80.00	$78,160.00
5.	8" PVC FORCE MAIN, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, BENDS, ALL DEPTHS, COMPLETE IN PLACE	LF	2568	$46.00	$118,128.00	$76.80	$197,222.40	$60.25	$154,722.00	$65.00	$166,920.00
6.	14" STEEL CASING FOR 8" FORCEMAIN, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	346	$100.00	$34,600.00	$110.00	$38,060.00	$88.50	$30,621.00	$75.00	$25,950.00
7.	16" STEEL CASING FOR 10" PVC SEWER PIPE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	40	$100.00	$4,000.00	$120.00	$4,800.00	$117.10	$4,684.00	$85.00	$3,400.00
8.	BORE AND JACK OR TUNNEL FOR 8" FORCE MAIN AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	346	$100.00	$34,600.00	$100.00	$34,600.00	$175.00	$60,550.00	$60.00	$20,760.00
9.	BORE AND JACK OR TUNNEL FOR 10" PVC SEWER PIPE AND 16" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	40	$250.00	$10,000.00	$120.00	$4,800.00	$225.00	$9,000.00	$70.00	$2,800.00
10.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES ADJUSTMENTS, COMPLETE IN PLACE	EA	9	$3,800.00	$34,200.00	$2,987.00	$26,883.00	$5,081.50	$45,733.50	$6,500.00	$58,500.00
11.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, SEALED AND VENTED, (0' - 8' DEPTH), INCLUDES PROTECTIVE INTERIOR COATING AND ADJUSTMENTS, COMPLETE IN PLACE	EA	1	$5,500.00	$5,500.00	$7,485.00	$7,485.00	$4,483.75	$4,483.75	$7,500.00	$7,500.00
12.	CORROSION RESISTANT PRECAST MANHOLE FOR FORECE MAIN DISCHARGE, INCLUDES STAINLESS STEEL INFLOW PROTECTOR AND ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$13,000.00	$13,000.00	$6,703.00	$6,703.00	$6,820.65	$6,820.65	$8,500.00	$8,500.00
13.	EXTRA VERTICAL DEPTH FOR 4' DIAMETER SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	81.6	$130.00	$10,608.00	$160.00	$13,056.00	$282.60	$23,060.16	$300.00	$24,480.00
14.	TRENCH SAFETY SYSTEM FOR SANITARY SEWER, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$1.00	$4,633.00	$0.70	$3,243.10	$1.00	$4,633.00	$2.00	$9,266.00
15.	DEWATERING FOR SANITARY SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$20.00	$92,660.00	$20.00	$92,660.00	$20.00	$92,660.00	$20.00	$92,660.00
16.	VIDEO INSPECTION OF SANITARY SEWER, ALL SIZES, INCLUDES DIGITAL COPY, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LF	4633	$3.00	$13,899.00	$3.00	$13,899.00	$3.00	$13,899.00	$3.00	$13,899.00
17.	8" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$750.00	$750.00	$650.00	$650.00	$259.25	$259.25	$700.00	$700.00
18.	10" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$750.00	$750.00	$830.00	$830.00	$411.20	$411.20	$800.00	$800.00
19.	8" SANITARY SEWER PLUG AND CLAMP FOR FORCE MAIN, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$2,000.00	$2,000.00	$650.00	$650.00	$550.00	$550.00	$950.00	$950.00
20.	FORCE MAIN ISOLATION VALVE, INCLUDES BOX AND INFLOW PROTECTORS, COMPLETE IN PLACE	EA	1	$4,500.00	$4,500.00	$6,279.00	$6,279.00	$16,539.00	$16,539.00	$3,000.00	$3,000.00
21.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00
SUBTOTAL SANITARY SEWER SYSTEM ITEMS					**$544,693.00**		**$633,166.20**		**$600,528.81**		**$597,135.00**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				1) ARS CONSTRUCTION LLC		2) GMR TOTAL SERVICES, LLC		3) HARRIS CONSTRUCTION COMPANY, LLC		4) JSS CONSTRUCTION, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
MISCELLANEOUS ITEMS											
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI PARTNERS, LLC, COMPLETE IN PLACE	LS	1	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00
2.	MOBILIZATION, INCLUDES BONDS, INSURANCE, CONSTRUCTION PERMITS, ETC., COMPLETE IN PLACE.	LS	1	$60,000.00	$60,000.00	$34,560.00	$34,560.00	$31,048.00	$31,048.00	$41,586.03	$41,586.03
3.	FORT BEND COUNTY CONSTRUCTION PERMIT FOR CONSTRUCTION IMPROVEMENTS, INCLUDES BONDS, COMPLETE IN PLACE	LS	1	$10,000.00	$10,000.00	$4,915.00	$4,915.00	$4,456.50	$4,456.50	$2,500.00	$2,500.00
4.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	$1,500.00	$1,500.00	$1,599.00	$1,599.00	$2,130.50	$2,130.50	$2,000.00	$2,000.00
5.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION ENTRANCE, AND REGRADE AREA TO MATCH FINISHED GRADE, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$1,200.00	$1,200.00	$1,200.00	$1,200.00	$2,400.00	$2,400.00	$1,200.00	$1,200.00
6.	INSTALL REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	3689	$1.00	$3,689.00	$1.00	$3,689.00	$2.00	$7,378.00	$1.00	$3,689.00
7.	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$250.00	$250.00	$2,366.00	$2,366.00	$2,010.90	$2,010.90	$500.00	$500.00
8.	TEMPORARY TRAFFIC CONTROL ITEMS (FLAGGERS, CONES, BARRELS, ETC…) AS NEEDED FOR THE DURATION OF THE PROJECT PER THE DETAILS, COMPLETE IN PLACE	LS	1	$6,000.00	$6,000.00	$7,561.00	$7,561.00	$21,739.10	$21,739.10	$5,000.00	$5,000.00
9.	REMOVAL AND REPLACEMENT OF EXISTING BARBED WIRE FENCE FOR INSTALLATION OF PROPOSED WATERLINE AND FORCE MAIN, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	100	$80.00	$8,000.00	$35.00	$3,500.00	$12.50	$1,250.00	$25.00	$2,500.00
10.	REMOBILIZATION OF EQUIPMENT TO THE JOB SITE FOR COMPLETION OF PHASE 2 OF THE CONSTRUCTION, LIMITS OF CONSTRUCTION PHASING ARE DETAILED IN THE CONSTRUCTION PLANS, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LS	1	$5,000.00	$5,000.00	$7,500.00	$7,500.00	$12,647.00	$12,647.00	$4,500.00	$4,500.00
SUBTOTAL MISCELLANEOUS ITEMS					**$108,564.00**		**$79,815.00**		**$97,985.00**		**$76,400.03**
BID SUMMARY											
WATER DISTRIBUTION SYSTEM ITEMS					$720,744.00		$692,521.20		$710,613.53		$754,252.00
SANITARY SEWER SYSTEM ITEMS					$544,693.00		$633,166.20		$600,528.81		$597,135.00
MISCELLANEOUS ITEMS					$108,564.00		$79,815.00		$97,985.00		$76,400.03
TOTAL AMOUNT BASE BID					**$1,374,001.00**		**$1,405,502.40**		**$1,409,127.34**		**$1,427,787.03**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				5) AR TURNKEE		6) TEJAS UNDERGROUND UTILITIES LLC		7) JTM CONSTRUCTION, LLC		8) GM VERA'S CONSTRUCTION	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
WATER DISTRIBUTION SYSTEM ITEMS											
1.	8" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	446	$47.00	$20,962.00	$59.50	$26,537.00	$52.60	$23,459.60	$40.40	$18,018.40
2.	8" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	61	$93.00	$5,673.00	$116.00	$7,076.00	$80.80	$4,928.80	$63.90	$3,897.90
3.	12" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	4339	$81.70	$354,496.30	$72.00	$312,408.00	$101.60	$440,842.40	$75.30	$326,726.70
4.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINFS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	69	$177.00	$12,213.00	$164.00	$11,316.00	$169.80	$11,716.20	$115.40	$7,962.60
5.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	386	$137.00	$52,882.00	$103.50	$39,951.00	$143.80	$55,506.80	$105.90	$40,877.40
6.	LONG SIDE SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, INCLUDES TRENCHLESS CONSTRUCTION FOR CROSSING EXISTING PAVEMENT AND UTILITIES, COMPLETE IN PLACE	LF	97	$53.00	$5,141.00	$67.00	$6,499.00	$26.60	$2,580.20	$45.10	$4,374.70
7.	14" STEEL CASING FOR 8" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	32	$77.00	$2,464.00	$98.75	$3,160.00	$125.80	$4,025.60	$121.00	$3,872.00
8.	18" STEEL CASING FOR 12" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	448	$93.00	$41,664.00	$134.00	$60,032.00	$126.20	$56,537.60	$133.10	$59,628.80
9.	BORE AND JACK OR TUNNEL FOR 8" WATERLINE AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	32	$157.00	$5,024.00	$386.75	$12,376.00	$99.70	$3,190.40	$66.40	$2,124.80
10.	BORE AND JACK OR TUNNEL FOR 12" WATERLINE AND 18" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	448	$163.00	$73,024.00	$190.00	$85,120.00	$102.50	$45,920.00	$78.90	$35,347.20
11.	8" PLUG & CLAMP WITH 2" BLOW-OFF VALVE & BOX ASSEMBLY, COMPLETE IN PLACE	EA	2	$1,170.00	$2,340.00	$3,788.00	$7,576.00	$1,221.60	$2,443.20	$1,069.80	$2,139.60
12.	8" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	2	$2,370.00	$4,740.00	$4,590.50	$9,181.00	$2,869.40	$5,738.80	$2,315.90	$4,631.80
13.	12" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	4	$4,130.00	$16,520.00	$4,845.50	$19,382.00	$5,201.00	$20,804.00	$4,170.70	$16,682.80
14.	FIRE HYDRANTS, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	10	$7,230.00	$72,300.00	$6,675.00	$66,750.00	$8,965.60	$89,656.00	$6,794.70	$67,947.00
15.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$0.70	$3,781.40	$1.00	$5,402.00	$1.60	$8,643.20	$1.10	$5,942.20
16.	DEWATERING FOR WATER LINE, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$20.00	$108,040.00	$20.00	$108,040.00	$20.00	$108,040.00	$22.00	$118,844.00
17.	8" X 8" TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$9,700.00	$9,700.00	$7,179.00	$7,179.00	$10,964.10	$10,964.10	$8,926.90	$8,926.90
18.	12" X 12" BACK TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$23,700.00	$23,700.00	$18,410.00	$18,410.00	$25,698.90	$25,698.90	$20,702.70	$20,702.70
19.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$20.00	$5,000.00	$52.80	$13,200.00	$20.00	$5,000.00	$25.00	$6,250.00
20.	ADDITIONAL DUCTILE IRON FITTINGS, ALL DEPTHS, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	TON	1	$1,000.00	$1,000.00	$1,100.00	$1,100.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00
21.	REMOVE AND REPLACE EXISTING SIDEWALK TO MATCH EXISTING, INCLUDES OFFSITE DISPOSAL, COMPLETE IN PLACE	SY	11	$70.00	$770.00	$1,039.00	$11,429.00	$171.10	$1,882.10	$308.40	$3,392.40
22.	REMOVE AND REPLACE EXISTING ADA RAMP, AS NEEDED FOR CONSTRUCTION, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	1	$2,000.00	$2,000.00	$9,350.00	$9,350.00	$1,710.60	$1,710.60	$4,189.30	$4,189.30
SUBTOTAL WATER DISTRIBUTION SYSTEM ITEMS					**$823,434.70**		**$841,474.00**		**$930,288.50**		**$763,479.20**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				5) AR TURNKEE		6) TEJAS UNDERGROUND UTILITIES LLC		7) JTM CONSTRUCTION, LLC		8) GM VERA'S CONSTRUCTION	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
SANITARY SEWER SYSTEM ITEMS											
1.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	10	$137.00	$1,370.00	$454.50	$4,545.00	$72.60	$726.00	$67.70	$677.00
2.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 8' - 12' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	414	$67.00	$27,738.00	$79.00	$32,706.00	$74.20	$30,718.80	$62.20	$25,750.80
3.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	664	$73.00	$48,472.00	$75.50	$50,132.00	$83.20	$55,244.80	$68.20	$45,284.80
4.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 16' - 20' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	977	$87.00	$84,999.00	$98.00	$95,746.00	$98.20	$95,941.40	$83.00	$81,091.00
5.	8" PVC FORCE MAIN, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, BENDS, ALL DEPTHS, COMPLETE IN PLACE	LF	2568	$57.00	$146,376.00	$62.00	$159,216.00	$59.00	$151,512.00	$73.60	$189,004.80
6.	14" STEEL CASING FOR 8" FORCEMAIN, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	346	$77.00	$26,642.00	$82.50	$28,545.00	$100.30	$34,703.80	$116.80	$40,412.80
7.	16" STEEL CASING FOR 10" PVC SEWER PIPE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	40	$130.00	$5,200.00	$128.00	$5,120.00	$165.80	$6,632.00	$170.50	$6,820.00
8.	BORE AND JACK OR TUNNEL FOR 8" FORCE MAIN AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	346	$137.00	$47,402.00	$135.50	$46,883.00	$99.70	$34,496.20	$77.60	$26,849.60
9.	BORE AND JACK OR TUNNEL FOR 10" PVC SEWER PIPE AND 16" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	40	$373.00	$14,920.00	$320.90	$12,836.00	$106.10	$4,244.00	$83.10	$3,324.00
10.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES ADJUSTMENTS, COMPLETE IN PLACE	EA	9	$3,700.00	$33,300.00	$5,274.00	$47,466.00	$4,367.80	$39,310.20	$3,558.10	$32,022.90
11.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, SEALED AND VENTED, (0' - 8' DEPTH), INCLUDES PROTECTIVE INTERIOR COATING AND ADJUSTMENTS, COMPLETE IN PLACE	EA	1	$7,700.00	$7,700.00	$10,020.00	$10,020.00	$8,494.20	$8,494.20	$8,178.90	$8,178.90
12.	CORROSION RESISTANT PRECAST MANHOLE FOR FORECE MAIN DISCHARGE, INCLUDES STAINLESS STEEL INFLOW PROTECTOR AND ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$17,000.00	$17,000.00	$19,615.00	$19,615.00	$17,671.90	$17,671.90	$16,505.50	$16,505.50
13.	EXTRA VERTICAL DEPTH FOR 4' DIAMETER SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	81.6	$130.00	$10,608.00	$125.00	$10,200.00	$424.20	$34,614.72	$999.90	$81,591.84
14.	TRENCH SAFETY SYSTEM FOR SANITARY SEWER, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$2.70	$12,509.10	$2.00	$9,266.00	$2.10	$9,729.30	$1.10	$5,096.30
15.	DEWATERING FOR SANITARY SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$20.00	$92,660.00	$28.00	$129,724.00	$20.00	$92,660.00	$20.00	$92,660.00
16.	VIDEO INSPECTION OF SANITARY SEWER, ALL SIZES, INCLUDES DIGITAL COPY, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LF	4633	$3.00	$13,899.00	$3.00	$13,899.00	$3.00	$13,899.00	$3.30	$15,288.90
17.	8" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$200.00	$200.00	$1,066.00	$1,066.00	$141.00	$141.00	$129.80	$129.80
18.	10" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$350.00	$350.00	$1,176.00	$1,176.00	$322.50	$322.50	$275.70	$275.70
19.	8" SANITARY SEWER PLUG AND CLAMP FOR FORCE MAIN, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$870.00	$870.00	$1,685.00	$1,685.00	$1,192.50	$1,192.50	$920.00	$920.00
20.	FORCE MAIN ISOLATION VALVE, INCLUDES BOX AND INFLOW PROTECTORS, COMPLETE IN PLACE	EA	1	$3,300.00	$3,300.00	$4,733.00	$4,733.00	$2,839.60	$2,839.60	$5,288.70	$5,288.70
21.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$20.00	$5,000.00	$52.80	$13,200.00	$20.00	$5,000.00	$30.00	$7,500.00
SUBTOTAL SANITARY SEWER SYSTEM ITEMS					**$600,515.10**		**$697,779.00**		**$640,093.92**		**$684,673.34**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				5) AR TURNKEE		6) TEJAS UNDERGROUND UTILITIES LLC		7) JTM CONSTRUCTION, LLC		8) GM VERA'S CONSTRUCTION	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
MISCELLANEOUS ITEMS											
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI PARTNERS, LLC, COMPLETE IN PLACE	LS	1	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00
2.	MOBILIZATION, INCLUDES BONDS, INSURANCE, CONSTRUCTION PERMITS, ETC., COMPLETE IN PLACE.	LS	1	$37,000.00	$37,000.00	$48,104.00	$48,104.00	$53,039.80	$53,039.80	$177,245.30	$177,245.30
3.	FORT BEND COUNTY CONSTRUCTION PERMIT FOR CONSTRUCTION IMPROVEMENTS, INCLUDES BONDS, COMPLETE IN PLACE	LS	1	$5,300.00	$5,300.00	$11,937.00	$11,937.00	$5,474.00	$5,474.00	$7,150.00	$7,150.00
4.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	$2,100.00	$2,100.00	$4,279.00	$4,279.00	$10,263.80	$10,263.80	$3,850.00	$3,850.00
5.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION ENTRANCE, AND REGRADE AREA TO MATCH FINISHED GRADE, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$1,200.00	$1,200.00	$4,950.00	$4,950.00	$1,200.00	$1,200.00	$1,200.00	$1,200.00
6.	INSTALL REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	3689	$1.00	$3,689.00	$3.00	$11,067.00	$1.00	$3,689.00	$1.00	$3,689.00
7.	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$300.00	$300.00	$3,080.00	$3,080.00	$1,642.20	$1,642.20	$990.00	$990.00
8.	TEMPORARY TRAFFIC CONTROL ITEMS (FLAGGERS, CONES, BARRELS, ETC…) AS NEEDED FOR THE DURATION OF THE PROJECT PER THE DETAILS, COMPLETE IN PLACE	LS	1	$17,000.00	$17,000.00	$13,750.00	$13,750.00	$34,212.50	$34,212.50	$41,625.80	$41,625.80
9.	REMOVAL AND REPLACEMENT OF EXISTING BARBED WIRE FENCE FOR INSTALLATION OF PROPOSED WATERLINE AND FORCE MAIN, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	100	$10.00	$1,000.00	$22.00	$2,200.00	$16.40	$1,640.00	$21.70	$2,170.00
10.	REMOBILIZATION OF EQUIPMENT TO THE JOB SITE FOR COMPLETION OF PHASE 2 OF THE CONSTRUCTION, LIMITS OF CONSTRUCTION PHASING ARE DETAILED IN THE CONSTRUCTION PLANS, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LS	1	$7,000.00	$7,000.00	$5,500.00	$5,500.00	$13,685.00	$13,685.00	$11,000.00	$11,000.00
SUBTOTAL MISCELLANEOUS ITEMS					**$87,514.00**		**$117,792.00**		**$137,771.30**		**$261,845.10**
BID SUMMARY											
WATER DISTRIBUTION SYSTEM ITEMS					$823,434.70		$841,474.00		$930,288.50		$763,479.20
SANITARY SEWER SYSTEM ITEMS					$600,515.10		$697,779.00		$640,093.92		$684,673.34
MISCELLANEOUS ITEMS					$87,514.00		$117,792.00		$137,771.30		$261,845.10
TOTAL AMOUNT BASE BID					**$1,511,463.80**		**$1,657,045.00**		**$1,708,153.72**		**$1,709,997.64**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				9) UCS: UNDERGROUND CONSTRUCTION SOLUTIONS		10) REDDICO CONSTRUCTION COMPANY, INC.		11) R CONSTRUCTION CIVIL, LLC		12) ISJ UNDERGROUND UTILITIES	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
WATER DISTRIBUTION SYSTEM ITEMS											
1.	8" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	446	$55.00	$24,530.00	$60.00	$26,760.00	$40.00	$17,840.00	$41.00	$18,286.00
2.	8" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	61	$70.00	$4,270.00	$130.00	$7,930.00	$67.00	$4,087.00	$118.00	$7,198.00
3.	12" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	4339	$85.00	$368,815.00	$109.00	$472,951.00	$100.00	$433,900.00	$78.00	$338,442.00
4.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINFS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	69	$105.00	$7,245.00	$186.00	$12,834.00	$125.00	$8,625.00	$265.50	$18,319.50
5.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	386	$100.00	$38,600.00	$131.00	$50,566.00	$130.00	$50,180.00	$188.50	$72,761.00
6.	LONG SIDE SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, INCLUDES TRENCHLESS CONSTRUCTION FOR CROSSING EXISTING PAVEMENT AND UTILITIES, COMPLETE IN PLACE	LF	97	$30.00	$2,910.00	$38.00	$3,686.00	$30.00	$2,910.00	$3,106.50	$301,330.50
7.	14" STEEL CASING FOR 8" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	32	$100.00	$3,200.00	$81.00	$2,592.00	$50.00	$1,600.00	$130.50	$4,176.00
8.	18" STEEL CASING FOR 12" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	448	$100.00	$44,800.00	$91.00	$40,768.00	$75.00	$33,600.00	$129.00	$57,792.00
9.	BORE AND JACK OR TUNNEL FOR 8" WATERLINE AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	32	$200.00	$6,400.00	$77.00	$2,464.00	$210.00	$6,720.00	$83.00	$2,656.00
10.	BORE AND JACK OR TUNNEL FOR 12" WATERLINE AND 18" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	448	$200.00	$89,600.00	$109.00	$48,832.00	$220.00	$98,560.00	$82.50	$36,960.00
11.	8" PLUG & CLAMP WITH 2" BLOW-OFF VALVE & BOX ASSEMBLY, COMPLETE IN PLACE	EA	2	$2,000.00	$4,000.00	$1,215.00	$2,430.00	$1,000.00	$2,000.00	$1,133.50	$2,267.00
12.	8" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	2	$2,000.00	$4,000.00	$2,597.00	$5,194.00	$2,200.00	$4,400.00	$2,849.50	$5,699.00
13.	12" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	4	$3,600.00	$14,400.00	$4,562.00	$18,248.00	$4,000.00	$16,000.00	$5,259.00	$21,036.00
14.	FIRE HYDRANTS, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	10	$7,000.00	$70,000.00	$7,004.00	$70,040.00	$6,500.00	$65,000.00	$8,744.00	$87,440.00
15.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$1.00	$5,402.00	$1.00	$5,402.00	$1.00	$5,402.00	$0.10	$540.20
16.	DEWATERING FOR WATER LINE, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$20.00	$108,040.00	$20.00	$108,040.00	$20.00	$108,040.00	$20.00	$108,040.00
17.	8" X 8" TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$6,000.00	$6,000.00	$8,887.00	$8,887.00	$12,000.00	$12,000.00	$5,985.00	$5,985.00
18.	12" X 12" BACK TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$12,000.00	$12,000.00	$16,190.00	$16,190.00	$20,000.00	$20,000.00	$10,137.00	$10,137.00
19.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00
20.	ADDITIONAL DUCTILE IRON FITTINGS, ALL DEPTHS, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	TON	1	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00	$1,000.00
21.	REMOVE AND REPLACE EXISTING SIDEWALK TO MATCH EXISTING, INCLUDES OFFSITE DISPOSAL, COMPLETE IN PLACE	SY	11	$75.00	$825.00	$972.00	$10,692.00	$400.00	$4,400.00	$135.00	$1,485.00
22.	REMOVE AND REPLACE EXISTING ADA RAMP, AS NEEDED FOR CONSTRUCTION, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	1	$1,500.00	$1,500.00	$5,949.00	$5,949.00	$3,500.00	$3,500.00	$5,000.00	$5,000.00
SUBTOTAL WATER DISTRIBUTION SYSTEM ITEMS					**$822,537.00**		**$926,455.00**		**$904,764.00**		**$1,111,550.20**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				9) UCS: UNDERGROUND CONSTRUCTION SOLUTIONS		10) REDDICO CONSTRUCTION COMPANY, INC.		11) R CONSTRUCTION CIVIL, LLC		12) ISJ UNDERGROUND UTILITIES	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
SANITARY SEWER SYSTEM ITEMS											
1.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	10	$140.00	$1,400.00	$99.00	$990.00	$130.00	$1,300.00	$59.00	$590.00
2.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 8' - 12' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	414	$140.00	$57,960.00	$92.00	$38,088.00	$90.00	$37,260.00	$48.50	$20,079.00
3.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	664	$140.00	$92,960.00	$132.00	$87,648.00	$102.00	$67,728.00	$48.50	$32,204.00
4.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 16' - 20' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	977	$140.00	$136,780.00	$153.00	$149,481.00	$167.00	$163,159.00	$48.50	$47,384.50
5.	8" PVC FORCE MAIN, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, BENDS, ALL DEPTHS, COMPLETE IN PLACE	LF	2568	$70.00	$179,760.00	$76.00	$195,168.00	$89.00	$228,552.00	$39.50	$101,436.00
6.	14" STEEL CASING FOR 8" FORCEMAIN, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	346	$100.00	$34,600.00	$69.00	$23,874.00	$87.00	$30,102.00	$103.50	$35,811.00
7.	16" STEEL CASING FOR 10" PVC SEWER PIPE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	40	$100.00	$4,000.00	$102.00	$4,080.00	$130.00	$5,200.00	$213.50	$8,540.00
8.	BORE AND JACK OR TUNNEL FOR 8" FORCE MAIN AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	346	$200.00	$69,200.00	$55.00	$19,030.00	$125.00	$43,250.00	$47.50	$16,435.00
9.	BORE AND JACK OR TUNNEL FOR 10" PVC SEWER PIPE AND 16" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	40	$200.00	$8,000.00	$98.00	$3,920.00	$150.00	$6,000.00	$73.50	$2,940.00
10.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES ADJUSTMENTS, COMPLETE IN PLACE	EA	9	$8,000.00	$72,000.00	$3,320.00	$29,880.00	$2,650.00	$23,850.00	$25,936.00	$233,424.00
11.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, SEALED AND VENTED, (0' - 8' DEPTH), INCLUDES PROTECTIVE INTERIOR COATING AND ADJUSTMENTS, COMPLETE IN PLACE	EA	1	$10,000.00	$10,000.00	$7,903.00	$7,903.00	$9,000.00	$9,000.00	$18,197.00	$18,197.00
12.	CORROSION RESISTANT PRECAST MANHOLE FOR FORECE MAIN DISCHARGE, INCLUDES STAINLESS STEEL INFLOW PROTECTOR AND ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$10,000.00	$10,000.00	$16,446.00	$16,446.00	$34,899.00	$34,899.00	$12,701.50	$12,701.50
13.	EXTRA VERTICAL DEPTH FOR 4' DIAMETER SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	81.6	$300.00	$24,480.00	$144.00	$11,750.40	$205.00	$16,728.00	$30.00	$2,448.00
14.	TRENCH SAFETY SYSTEM FOR SANITARY SEWER, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$1.00	$4,633.00	$1.00	$4,633.00	$1.00	$4,633.00	$0.10	$463.30
15.	DEWATERING FOR SANITARY SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$25.00	$115,825.00	$20.00	$92,660.00	$20.00	$92,660.00	$20.00	$92,660.00
16.	VIDEO INSPECTION OF SANITARY SEWER, ALL SIZES, INCLUDES DIGITAL COPY, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LF	4633	$4.00	$18,532.00	$3.00	$13,899.00	$3.00	$13,899.00	$3.00	$13,899.00
17.	8" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$2,000.00	$2,000.00	$578.00	$578.00	$100.00	$100.00	$117.50	$117.50
18.	10" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$2,000.00	$2,000.00	$677.00	$677.00	$200.00	$200.00	$262.50	$262.50
19.	8" SANITARY SEWER PLUG AND CLAMP FOR FORCE MAIN, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$2,000.00	$2,000.00	$1,500.00	$1,500.00	$1,250.00	$1,250.00	$1,114.00	$1,114.00
20.	FORCE MAIN ISOLATION VALVE, INCLUDES BOX AND INFLOW PROTECTORS, COMPLETE IN PLACE	EA	1	$8,500.00	$8,500.00	$2,615.00	$2,615.00	$2,300.00	$2,300.00	$2,913.50	$2,913.50
21.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00	$20.00	$5,000.00
SUBTOTAL SANITARY SEWER SYSTEM ITEMS					**$859,630.00**		**$709,820.40**		**$787,070.00**		**$648,619.80**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LINE LOOP, SANITARY SEWER AND FORCE MAIN TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134A
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				9) UCS: UNDERGROUND CONSTRUCTION SOLUTIONS		10) REDDICO CONSTRUCTION COMPANY, INC.		11) R CONSTRUCTION CIVIL, LLC		12) ISJ UNDERGROUND UTILITIES	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
MISCELLANEOUS ITEMS											
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI PARTNERS, LLC, COMPLETE IN PLACE	LS	1	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00	$12,925.00
2.	MOBILIZATION, INCLUDES BONDS, INSURANCE, CONSTRUCTION PERMITS, ETC., COMPLETE IN PLACE.	LS	1	$75,000.00	$75,000.00	$106,088.00	$106,088.00	$37,000.00	$37,000.00	$60,000.00	$60,000.00
3.	FORT BEND COUNTY CONSTRUCTION PERMIT FOR CONSTRUCTION IMPROVEMENTS, INCLUDES BONDS, COMPLETE IN PLACE	LS	1	$15,000.00	$15,000.00	$1,770.00	$1,770.00	$30,000.00	$30,000.00	$2,500.00	$2,500.00
4.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	$2,000.00	$2,000.00	$1,067.00	$1,067.00	$1,500.00	$1,500.00	$50.00	$50.00
5.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION ENTRANCE, AND REGRADE AREA TO MATCH FINISHED GRADE, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$1,200.00	$1,200.00	$1,949.00	$1,949.00	$3,600.00	$3,600.00	$1,200.00	$1,200.00
6.	INSTALL REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	3689	$1.00	$3,689.00	$3.00	$11,067.00	$2.00	$7,378.00	$1.00	$3,689.00
7.	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$800.00	$800.00	$506.00	$506.00	$700.00	$700.00	$200.00	$200.00
8.	TEMPORARY TRAFFIC CONTROL ITEMS (FLAGGERS, CONES, BARRELS, ETC…) AS NEEDED FOR THE DURATION OF THE PROJECT PER THE DETAILS, COMPLETE IN PLACE	LS	1	$2,000.00	$2,000.00	$18,807.00	$18,807.00	$50,000.00	$50,000.00	$8,000.00	$8,000.00
9.	REMOVAL AND REPLACEMENT OF EXISTING BARBED WIRE FENCE FOR INSTALLATION OF PROPOSED WATERLINE AND FORCE MAIN, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	100	$5.00	$500.00	$24.00	$2,400.00	$25.00	$2,500.00	$35.00	$3,500.00
10.	REMOBILIZATION OF EQUIPMENT TO THE JOB SITE FOR COMPLETION OF PHASE 2 OF THE CONSTRUCTION, LIMITS OF CONSTRUCTION PHASING ARE DETAILED IN THE CONSTRUCTION PLANS, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LS	1	$1,500.00	$1,500.00	$5,984.00	$5,984.00	$5,200.00	$5,200.00	$5,000.00	$5,000.00
SUBTOTAL MISCELLANEOUS ITEMS					**$114,614.00**		**$162,563.00**		**$150,803.00**		**$97,064.00**
BID SUMMARY											
WATER DISTRIBUTION SYSTEM ITEMS					$822,537.00		$926,455.00		$904,764.00		$1,111,550.20
SANITARY SEWER SYSTEM ITEMS					$859,630.00		$709,820.40		$787,070.00		$648,619.80
MISCELLANEOUS ITEMS					$114,614.00		$162,563.00		$150,803.00		$97,064.00
TOTAL AMOUNT BASE BID					**$1,796,781.00**		**$1,798,838.40**		**$1,842,637.00**		**$1,857,234.00**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LI
TO SERVE FORT BEND COUNTY MUNICIPA
FORT BEND COUNTY MUNICIPAL UTILITY D
CITY OF HOUSTON E.T.J., FORT BEND COU

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				13) NERIE CONSTRUCTION LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
WATER DISTRIBUTION SYSTEM ITEMS					
1.	8" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	446	$79.00	$35,234.00
2.	8" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	61	$106.00	$6,466.00
3.	12" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	4339	$124.00	$538,036.00
4.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINFS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	69	$177.00	$12,213.00
5.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	386	$166.00	$64,076.00
6.	LONG SIDE SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, INCLUDES TRENCHLESS CONSTRUCTION FOR CROSSING EXISTING PAVEMENT AND UTILITIES, COMPLETE IN PLACE	LF	97	$75.00	$7,275.00
7.	14" STEEL CASING FOR 8" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	32	$193.00	$6,176.00
8.	18" STEEL CASING FOR 12" WATERLINE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	448	$195.00	$87,360.00
9.	BORE AND JACK OR TUNNEL FOR 8" WATERLINE AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	32	$195.00	$6,240.00
10.	BORE AND JACK OR TUNNEL FOR 12" WATERLINE AND 18" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	448	$193.00	$86,464.00
11.	8" PLUG & CLAMP WITH 2” BLOW-OFF VALVE & BOX ASSEMBLY, COMPLETE IN PLACE	EA	2	$1,680.00	$3,360.00
12.	8" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	2	$3,260.00	$6,520.00
13.	12" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	4	$5,410.00	$21,640.00
14.	FIRE HYDRANTS, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	10	$8,200.00	$82,000.00
15.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$7.00	$37,814.00
16.	DEWATERING FOR WATER LINE, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	5402	$20.00	$108,040.00
17.	8" X 8" TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$9,500.00	$9,500.00
18.	12" X 12" BACK TAPPING SLEEVE AND VALVE & BOX, COMPLETE IN PLACE	EA	1	$23,000.00	$23,000.00
19.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$35.00	$8,750.00
20.	ADDITIONAL DUCTILE IRON FITTINGS, ALL DEPTHS, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	TON	1	$17,000.00	$17,000.00
21.	REMOVE AND REPLACE EXISTING SIDEWALK TO MATCH EXISTING, INCLUDES OFFSITE DISPOSAL, COMPLETE IN PLACE	SY	11	$95.00	$1,045.00
22.	REMOVE AND REPLACE EXISTING ADA RAMP, AS NEEDED FOR CONSTRUCTION, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	1	$2,000.00	$2,000.00
SUBTOTAL WATER DISTRIBUTION SYSTEM ITEMS					**$1,170,209.00**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LI
TO SERVE FORT BEND COUNTY MUNICIPAL
FORT BEND COUNTY MUNICIPAL UTILITY D
CITY OF HOUSTON E.T.J., FORT BEND COUI

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				13) NERIE CONSTRUCTION LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
SANITARY SEWER SYSTEM ITEMS					
1.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	10	$218.00	$2,180.00
2.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 8' - 12' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	414	$96.00	$39,744.00
3.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	664	$143.00	$94,952.00
4.	10" PVC SEWER PIPE, ASTM D-3034, SDR 26, 16' - 20' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	977	$162.00	$158,274.00
5.	8" PVC FORCE MAIN, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, BENDS, ALL DEPTHS, COMPLETE IN PLACE	LF	2568	$86.00	$220,848.00
6.	14" STEEL CASING FOR 8" FORCEMAIN, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	346	$175.00	$60,550.00
7.	16" STEEL CASING FOR 10" PVC SEWER PIPE, DOES NOT INCLUDE CARRIER PIPE, INCLUDES SPACERS AND OTHER APPURTENANCES AS SHOWN IN THE DETAIL OF THE CONSTRUCTION PLANS, COMPLETE IN PLACE	LF	40	$253.00	$10,120.00
8.	BORE AND JACK OR TUNNEL FOR 8" FORCE MAIN AND 14" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	346	$201.00	$69,546.00
9.	BORE AND JACK OR TUNNEL FOR 10" PVC SEWER PIPE AND 16" STEEL CASING, DOES NOT INCLUDE CARRIER PIPE OR CASING, INCLUDES BORE PITS AND BACKFILL OF BORE PITS, COMPLETE IN PLACE	LF	40	$253.00	$10,120.00
10.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES ADJUSTMENTS, COMPLETE IN PLACE	EA	9	$5,400.00	$48,600.00
11.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, SEALED AND VENTED, (0' - 8' DEPTH), INCLUDES PROTECTIVE INTERIOR COATING AND ADJUSTMENTS, COMPLETE IN PLACE	EA	1	$7,820.00	$7,820.00
12.	CORROSION RESISTANT PRECAST MANHOLE FOR FORECE MAIN DISCHARGE, INCLUDES STAINLESS STEEL INFLOW PROTECTOR AND ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$17,275.00	$17,275.00
13.	EXTRA VERTICAL DEPTH FOR 4' DIAMETER SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	81.6	$422.00	$34,435.20
14.	TRENCH SAFETY SYSTEM FOR SANITARY SEWER, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$5.00	$23,165.00
15.	DEWATERING FOR SANITARY SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4633	$20.00	$92,660.00
16.	VIDEO INSPECTION OF SANITARY SEWER, ALL SIZES, INCLUDES DIGITAL COPY, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LF	4633	$4.00	$18,532.00
17.	8" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$800.00	$800.00
18.	10" SANITARY SEWER PLUG, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$950.00	$950.00
19.	8" SANITARY SEWER PLUG AND CLAMP FOR FORCE MAIN, ALL DEPTHS, COMPLETE IN PLACE	EA	1	$1,500.00	$1,500.00
20.	FORCE MAIN ISOLATION VALVE, INCLUDES BOX AND INFLOW PROTECTORS, COMPLETE IN PLACE	EA	1	$4,065.00	$4,065.00
21.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY, 200 PSI), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	250	$35.00	$8,750.00
SUBTOTAL SANITARY SEWER SYSTEM ITEMS					**$924,886.20**

BID TABULATION FOR: CONSTRUCTION OF THE OFFSITE WATER LI
TO SERVE FORT BEND COUNTY MUNICIPA
FORT BEND COUNTY MUNICIPAL UTILITY D
CITY OF HOUSTON E.T.J., FORT BEND COU

BID OPENING DATE: NOVEMBER 18, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: C CORTEZ
TABULATION DATE: NOVEMBER 18, 2026
LJA JOB NO. 1882-2601 (9.2)

				13) NERIE CONSTRUCTION LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
MISCELLANEOUS ITEMS					
1.	METHOD "A" CONSTRUCTION STAKING BY THE CONTRACTOR PER GBI PARTNERS, LLC, COMPLETE IN PLACE	LS	1	$12,925.00	$12,925.00
2.	MOBILIZATION, INCLUDES BONDS, INSURANCE, CONSTRUCTION PERMITS, ETC., COMPLETE IN PLACE.	LS	1	$62,000.00	$62,000.00
3.	FORT BEND COUNTY CONSTRUCTION PERMIT FOR CONSTRUCTION IMPROVEMENTS, INCLUDES BONDS, COMPLETE IN PLACE	LS	1	$22,000.00	$22,000.00
4.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	$15,000.00	$15,000.00
5.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION ENTRANCE, AND REGRADE AREA TO MATCH FINISHED GRADE, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$3,500.00	$3,500.00
6.	INSTALL REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	3689	$4.00	$14,756.00
7.	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	EA	1	$4,500.00	$4,500.00
8.	TEMPORARY TRAFFIC CONTROL ITEMS (FLAGGERS, CONES, BARRELS, ETC…) AS NEEDED FOR THE DURATION OF THE PROJECT PER THE DETAILS, COMPLETE IN PLACE	LS	1	$25,000.00	$25,000.00
9.	REMOVAL AND REPLACEMENT OF EXISTING BARBED WIRE FENCE FOR INSTALLATION OF PROPOSED WATERLINE AND FORCE MAIN, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LF	100	$200.00	$20,000.00
10.	REMOBILIZATION OF EQUIPMENT TO THE JOB SITE FOR COMPLETION OF PHASE 2 OF THE CONSTRUCTION, LIMITS OF CONSTRUCTION PHASING ARE DETAILED IN THE CONSTRUCTION PLANS, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LS	1	$25,000.00	$25,000.00
SUBTOTAL MISCELLANEOUS ITEMS					**$204,681.00**

BID SUMMARY

WATER DISTRIBUTION SYSTEM ITEMS	$1,170,209.00
SANITARY SEWER SYSTEM ITEMS	$924,886.20
MISCELLANEOUS ITEMS	$204,681.00
TOTAL AMOUNT BASE BID	**$2,299,776.20**