
BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS JUNE 19, 2024 LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024

BIDDER'S NAME TOTAL AMOUNT BID

1931-3212 (10.2)

1) D&J CONSTRUCTION, INC	\$1,168,062.75
2) PRINCIPAL PAVING CONTRACTORS, LTD.	\$1,180,798.00
3) R CONSTRUCTION CIVIL, LLC	\$1,197,339.80
4) DACO PAVING, INC.	\$1,238,000.00
5) EXCELL FOUNDATION	\$1,253,382.78
6) DIMAS BROS. CONSTRUCTION	\$1,254,000.00
7) ICON GC LLC	\$1,295,000.00
8) BEYER CONSTRUCTION, LLC	\$1,324,382.70
9) HCG	\$1,360,530.30
10) SCYTHE CONSTRUCTION, LLC	\$1,463,366.45
CALENDAR DAYS 65/75 OF NICHOLAS W. HOLLEK	



I, Nicholas Hollek PE, hereby certify these bid tabulations to be true and correct.

FRN F-1386 Page 1 of 9 LJA Engineering, Inc.

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO. CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS

2) PRINCIPAL PAVING CONTRACTORS, LTD.

3) R CONSTRUCTION CIVIL, LLC

JUNE 19, 2024 LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

1) D&J CONSTRUCTION, INC

				1) D&J CONSTR	UCTION, INC	2) PRINCIPAL PAVING C	ONTRACTORS, LTD.	3) R CONSTRUCTI	ON CIVIL, LLC
ITEM		UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
	NG AND APPURTENANCES ITEMS								
1	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	14084	\$50.00	\$704,200.00	\$51.00	\$718,284.00	\$53.00	\$746,452.00
2	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1970	\$3.75	\$7,387.50	\$3.50	\$6,895.00	\$4.00	\$7,880.00
3	4"X12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	6284	\$3.75	\$23,565.00	\$3.50	\$21,994.00	\$4.00	\$25,136.00
4	6° LIME STABILIZED SUBGRADE, MANIPULATION, INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	15924	\$3.50	\$55,734.00	\$4.00	\$63,696.00	\$4.00	\$63,696.00
5	LIME FOR 6" SUBGRADE PREPARATION (8% BY WEIGHT, 38 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	303	\$350.00	\$106,050.00	\$350.00	\$106,050.00	\$370.00	\$112,110.00
6	ROADWAY AND LOT EXCAVATION, IN ACCORDANCE WITH SUPPLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", COMPLETE IN PLACE	CY	19012	\$2.00	\$38,024.00	\$3.00	\$57,036.00	\$1.80	\$34,221.60
7	ROADWAY AND LOT EMBANKMENT, INCLUDES REMOVAL OF UNSUITABLE MATERIALS BEFORE PLACING FILL, STRIPPING, STOCKPILING OF STRIPPINGS, PROOF ROLLING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, REAPPLICATION OF STRIPPINGS, IN ACCORDANCE WITH SUPPLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", COMPLETE IN PLACE	CY	19012	\$2.00	\$38,024.00	\$2.00	\$38,024.00	\$1.80	\$34,221.60
8	EXTRA COST TO HAUL EXCAVATED MATERIAL OFFSITE IN LIEU OF ONSITE, USING OFF ROAD TRUCKS, (1 - 1.5 MILES), (AS DIRECTED BY ENGINEER), INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS TO FINAL GRADED AREA, COMPLETE IN PLACE	CY	6641	\$7.00	\$46,487.00	\$4.00	\$26,564.00	\$3.60	\$23,907.60
9	FINAL LOT GRADING, INCLUDING RESERVES, STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, INCLUDING MANIPULATION AND PLACEMENT OF STOCKPILE, COMPLETE IN PLACE	EA	90	\$150.00	\$13,500.00	\$199.00	\$17,910.00	\$205.00	\$18,450.00
10	TYPE 7 WHEELCHAIR RAMPS, INCLUDING TRUNCATED DOME SURFACE TO BE STAINED WITH CONTRASTING COLOR PER THE CONSTRUCTION PLAN SET, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	EA	10	\$1,400.00	\$14,000.00	\$1,400.00	\$14,000.00	\$2,000.00	\$20,000.00
11	TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, ETC.), PER TMUTCD, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00	\$1,000.00	\$1,000.00
12	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STOP SIGNS, STREET SIGNS, AND ALL OTHER TRAFFIC SIGNS SHOWN IN PLANS, ETC., COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$8,100.00	\$8,100.00
13	INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,400.00	\$2,800.00	\$1,000.00	\$2,000.00	\$1,250.00	\$2,500.00
14	BLUE DOUBLE REFLECTORIZED FIRE HYDRANT BUTTONS, COMPLETE IN PLACE	EA	11	\$15.00	\$165.00	\$10.00	\$110.00	\$16.00	\$176.00
15	CONNECT PROPOSED PAVEMENT TO EXISTING PAVEMENT, INCLUDES ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	87	\$20.00	\$1,740.00	\$15.00	\$1,305.00	\$44.00	\$3,828.00
16	REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	58	\$15.00	\$870.00	\$15.00	\$870.00	\$22.00	\$1,276.00
PAVII	NG AND APPURTENANCES ITEMS SUBTOTAL:				\$1,059,046.50		\$1,081,238.00		\$1,102,954.80

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS

2) PRINCIPAL PAVING CONTRACTORS, LTD.

3) R CONSTRUCTION CIVIL, LLC

JUNE 19, 2024 LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

1) D&J CONSTRUCTION, INC

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING GENERAL ITE	MS								
1 EXTRA CEMENT COMPLETE IN P	STABILIZED SAND BACKFILL, AS DIRECTED BY THE ENGINEER, ACE	CY	500	\$38.00	\$19,000.00	\$38.00	\$19,000.00	\$38.00	\$19,000.00
2 EXTRA LIME AS	DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	50	\$300.00	\$15,000.00	\$350.00	\$17,500.00	\$365.00	\$18,250.00
3 EXTRA BROADO PLACE	AST SEEDING, AS DIRECTED BY THE ENGINEER, COMPLETE IN	AC	1	\$900.00	\$900.00	\$1,000.00	\$1,000.00	\$675.00	\$675.00
4 EXTRA HYDROM PLACE	ULCH SEEDING, AS DIRECTED BY THE ENGINEER, COMPLETE IN	AC	1	\$2,500.00	\$2,500.00	\$1,500.00	\$1,500.00	\$1,600.00	\$1,600.00
5 6" PVC SLEEVES	S, SCHEDULE 40, COMPLETE IN PLACE	LF	76	\$35.00	\$2,660.00	\$35.00	\$2,660.00	\$35.00	\$2,660.00
	RETE TRUCK WASHOUT PIT AND REMOVAL ON POST , COMPLETE IN PLACE	EA	1	\$1,200.00	\$1,200.00	\$500.00	\$500.00	\$500.00	\$500.00
	LL, MAINTAIN, AND REMOVE SWPPP REINFORCED FILTER PAVING), COMPLETE IN PLACE	LF	8125	\$2.25	\$18,281.25	\$1.00	\$8,125.00	\$1.00	\$8,125.00
8 FURNISH, INSTA BARRIER, COMP	LL, MAINTAIN, AND REMOVE STAGE I AND II INLET PROTECTION LETE IN PLACE	EA	48	\$75.00	\$3,600.00	\$50.00	\$2,400.00	\$50.00	\$2,400.00
	ISTRUCTION EXIT, INCLUDING INSTALLATION, MAINTENANCE, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$2,500.00	\$2,500.00	\$1,500.00	\$1,500.00
	POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDING BOOKLET NOI AND NOT, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$1,000.00	\$1,000.00	\$1,200.00	\$1,200.00
11 CLEARING AND	GRUBBING, AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	AC	1	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00
PARTNERS, ALL	, CONTROL, AS BUILT AND LOT PINNING STAKING SET BY GBI STAKING TO BE PERFORMED AT ONE TIME. RE-STAKING IS OF CONTRACTOR (CONTACT JASON ASHWORTH AT 281-499- E IN PLACE	LS	1	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00
	S DRAINAGE SWALES, V-BOTTOM, GRADED TO DRAIN, INCLUDES EEDING AND WATERING, AS DIRECTED BY THE ENGINEER, ACE	LF	1000	\$7.00	\$7,000.00	\$5.00	\$5,000.00	\$3.50	\$3,500.00
	ON OF UNSUITABLE MATERIAL, FOR FILL PLACEMENT, AS HE ENGINEER, COMPLETE IN PLACE	CY	2000	\$4.00	\$8,000.00	\$5.00	\$10,000.00	\$3.30	\$6,600.00
PAVING GENERAL ITE	MS SUBTOTAL:				\$109,016.25		\$99,560.00		\$94,385.00
SUBTOTAL PAVING AN	D APPURTENANCES ITEMS				\$1,059,046.50		\$1,081,238.00		\$1,102,954.80
SUBTOTAL PAVING GE	NERAL ITEMS				\$109,016.25		\$99,560.00		\$94,385.00
TOTAL AMOUNT BASE	BID				\$1,168,062.75		\$1,180,798.00		\$1,197,339.80

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO. CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS JUNE 19, 2024

LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

<u> </u>	4) DACO PAVING, INC.		5) EXCELL FOUNDATION		6) DIMAS BROS. CONSTRUCTION			
ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING AND APPURTENANCES ITEMS	0	α	0.11.1 0001		0		0.111 0001	
1 6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	14084	\$52.00	\$732,368.00	\$51.55	\$726,030.20	\$58.00	\$816,872.00
2 6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1970	\$4.25	\$8,372.50	\$4.00	\$7,880.00	\$3.65	\$7,190.50
3 4"X12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	6284	\$4.25	\$26,707.00	\$4.00	\$25,136.00	\$3.65	\$22,936.60
4 6" LIME STABILIZED SUBGRADE, MANIPULATION, INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	15924	\$4.00	\$63,696.00	\$4.32	\$68,791.68	\$4.00	\$63,696.00
5 LIME FOR 6" SUBGRADE PREPARATION (8% BY WEIGHT, 38 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	303	\$325.00	\$98,475.00	\$354.00	\$107,262.00	\$355.00	\$107,565.00
6 ROADWAY AND LOT EXCAVATION, IN ACCORDANCE WITH SUPPLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", COMPLETE IN PLACE	CY	19012	\$5.00	\$95,060.00	\$4.40	\$83,652.80	\$2.25	\$42,777.00
7 ROADWAY AND LOT EMBANKMENT, INCLUDES REMOVAL OF UNSUITABLE MATERIALS BEFORE PLACING FILL, STRIPPING, STOCKPILING OF STRIPPINGS, PROOF ROLLING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, REAPPLICATION OF STRIPPINGS, IN ACCORDANCE WITH SUPPLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", COMPLETE IN PLACE	CY	19012	\$1.75	\$33,271.00	\$1.65	\$31,369.80	\$2.25	\$42,777.00
8 EXTRA COST TO HAUL EXCAVATED MATERIAL OFFSITE IN LIEU OF ONSITE, USING OFF ROAD TRUCKS, (1 - 1.5 MILES), (AS DIRECTED BY ENGINEER), INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS TO FINAL GRADED AREA, COMPLETE IN PLACE	CY	6641	\$3.60	\$23,907.60	\$3.30	\$21,915.30	\$3.00	\$19,923.00
9 FINAL LOT GRADING, INCLUDING RESERVES, STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, INCLUDING MANIPULATION AND PLACEMENT OF STOCKPILE, COMPLETE IN PLACE	EA	90	\$250.00	\$22,500.00	\$230.00	\$20,700.00	\$300.00	\$27,000.00
10 TYPE 7 WHEELCHAIR RAMPS, INCLUDING TRUNCATED DOME SURFACE TO BE STAINED WITH CONTRASTING COLOR PER THE CONSTRUCTION PLAN SET, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	EA	10	\$1,465.00	\$14,650.00	\$1,500.00	\$15,000.00	\$1,484.00	\$14,840.00
11 TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, ETC.), PER TMUTCD, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$3,000.00	\$3,000.00	\$1,500.00	\$1,500.00
12 PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STOP SIGNS, STREET SIGNS, AND ALL OTHER TRAFFIC SIGNS SHOWN IN PLANS, ETC., COMPLETE IN PLACE	LS	1	\$3,498.65	\$3,498.65	\$7,200.00	\$7,200.00	\$5,500.00	\$5,500.00
13 INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,350.00	\$2,700.00	\$1,500.00	\$3,000.00	\$1,250.00	\$2,500.00
14 BLUE DOUBLE REFLECTORIZED FIRE HYDRANT BUTTONS, COMPLETE IN PLACE	EA	11	\$22.00	\$242.00	\$15.00	\$165.00	\$20.00	\$220.00
15 CONNECT PROPOSED PAVEMENT TO EXISTING PAVEMENT, INCLUDES ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	87	\$5.00	\$435.00	\$20.00	\$1,740.00	\$25.00	\$2,175.00
16 REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	58	\$17.00	\$986.00	\$20.00	\$1,160.00	\$28.00	\$1,624.00
PAVING AND APPURTENANCES ITEMS SUBTOTAL:				\$1,127,368.75		\$1,124,002.78		\$1,179,096.10

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS JUNE 19, 2024

LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

20/1002 110			02.2 (.0)					
		4) DACO PAVING, INC.			5) EXCELL FOL	INDATION	6) DIMAS BROS. CONSTRUCTION	
ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING GENERAL ITEMS								
1 EXTRA CEMENT STABILIZED SAND BACKFILL, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	CY	500	\$38.00	\$19,000.00	\$38.00	\$19,000.00	\$38.00	\$19,000.00
2 EXTRA LIME AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	50	\$325.00	\$16,250.00	\$354.00	\$17,700.00	\$50.00	\$2,500.00
3 EXTRA BROADCAST SEEDING, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	AC	1	\$1,250.00	\$1,250.00	\$1,300.00	\$1,300.00	\$600.00	\$600.00
4 EXTRA HYDROMULCH SEEDING, AS DIRECTED BY THE ENGINEER, COMPLETE I PLACE	N AC	1	\$2,200.00	\$2,200.00	\$1,900.00	\$1,900.00	\$2,000.00	\$2,000.00
5 6" PVC SLEEVES, SCHEDULE 40, COMPLETE IN PLACE	LF	76	\$55.00	\$4,180.00	\$130.00	\$9,880.00	\$35.00	\$2,660.00
6 PROVIDE CONCRETE TRUCK WASHOUT PIT AND REMOVAL ON POST CONSTRUCTION, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$3,000.00	\$3,000.00	\$800.00	\$800.00
7 FURNISH, INSTALL, MAINTAIN, AND REMOVE SWPPP REINFORCED FILTER FABRIC FENCE (PAVING), COMPLETE IN PLACE	LF	8125	\$2.05	\$16,656.25	\$1.00	\$8,125.00	\$1.00	\$8,125.00
8 FURNISH, INSTALL, MAINTAIN, AND REMOVE STAGE I AND II INLET PROTECTION BARRIER, COMPLETE IN PLACE	I EA	48	\$165.00	\$7,920.00	\$400.00	\$19,200.00	\$25.00	\$1,200.00
9 STABILIZED CONSTRUCTION EXIT, INCLUDING INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$7,000.00	\$7,000.00	\$800.00	\$800.00
10 STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDING CONTRACTOR'S BOOKLET NOI AND NOT, COMPLETE IN PLACE	LS	1	\$2,100.00	\$2,100.00	\$4,000.00	\$4,000.00	\$843.90	\$843.90
11 CLEARING AND GRUBBING, AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	AC	1	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00
12 CONSTRUCTION, CONTROL, AS BUILT AND LOT PINNING STAKING SET BY GBI PARTNERS, ALL STAKING TO BE PERFORMED AT ONE TIME. RE-STAKING IS RESPONSIBILITY OF CONTRACTOR (CONTACT JASON ASHWORTH AT 281-499- 4539), COMPLETE IN PLACE	LS		\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00
13 MISCELLANEOUS DRAINAGE SWALES, V-BOTTOM, GRADED TO DRAIN, INCLUDE HYDROMULCH SEEDING AND WATERING, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	S LF	1000	\$4.10	\$4,100.00	\$4.40	\$4,400.00	\$3.00	\$3,000.00
14 OVER EXCAVATION OF UNSUITABLE MATERIAL, FOR FILL PLACEMENT, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	CY	2000	\$2.55	\$5,100.00	\$2.75	\$5,500.00	\$2.50	\$5,000.00
PAVING GENERAL ITEMS SUBTOTAL:				\$110,631.25		\$129,380.00		\$74,903.90
BIDDING SUMMARY								
SUBTOTAL PAVING AND APPURTENANCES ITEMS				\$1,127,368.75		\$1,124,002.78		\$1,179,096.10
SUBTOTAL PAVING GENERAL ITEMS				\$110,631.25		\$129,380.00		\$74,903.90
TOTAL AMOUNT BASE BID				\$1,238,000.00		\$1,253,382.78		\$1,254,000.00

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO. CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS JUNE 19, 2024 LJA ENGINEERING, INC.

LJA ENGINEERING, AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

ESA JOB NO.		133	1-3212 (10)					
		7) ICON		C LLC	8) BEYER CONSTR	RUCTION, LLC	9) HC	G
ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING AND APPURTENANCES ITEMS								
1 6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	14084	\$50.00	\$704,200.00	\$57.20	\$805,604.80	\$48.95	\$689,411.80
2 6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1970	\$4.00	\$7,880.00	\$4.95	\$9,751.50	\$4.00	\$7,880.00
3 4"X12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	6284	\$4.00	\$25,136.00	\$4.95	\$31,105.80	\$4.00	\$25,136.00
4 6" LIME STABILIZED SUBGRADE, MANIPULATION, INCLUDES COMPACTION TO 95% STANDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	15924	\$5.00	\$79,620.00	\$3.00	\$47,772.00	\$4.50	\$71,658.00
5 LIME FOR 6" SUBGRADE PREPARATION (8% BY WEIGHT, 38 LBS/SY), AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	303	\$375.00	\$113,625.00	\$369.00	\$111,807.00	\$310.00	\$93,930.00
6 ROADWAY AND LOT EXCAVATION, IN ACCORDANCE WITH SUPPLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", COMPLETE IN PLACE	CY	19012	\$4.00	\$76,048.00	\$5.25	\$99,813.00	\$4.00	\$76,048.00
7 ROADWAY AND LOT EMBANKMENT, INCLUDES REMOVAL OF UNSUITABLE MATERIALS BEFORE PLACING FILL, STRIPPING, STOCKPILING OF STRIPPINGS, PROOF ROLLING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, REAPPLICATION OF STRIPPINGS, IN ACCORDANCE WITH SUPPLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", COMPLETE IN PLACE	CY	19012	\$5.00	\$95,060.00	\$1.95	\$37,073.40	\$3.50	\$66,542.00
8 EXTRA COST TO HAUL EXCAVATED MATERIAL OFFSITE IN LIEU OF ONSITE, USING OFF ROAD TRUCKS, (1 - 1.5 MILES), (AS DIRECTED BY ENGINEER), INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS TO FINAL GRADED AREA, COMPLETE IN PLACE	CY	6641	\$5.50	\$36,525.50	\$3.70	\$24,571.70	\$14.50	\$96,294.50
9 FINAL LOT GRADING, INCLUDING RESERVES, STRIPPING AND PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS AND REPLACEMENT OF STRIPPINGS, INCLUDING MANIPULATION AND PLACEMENT OF STOCKPILE, COMPLETE IN PLACE	EA	90	\$280.00	\$25,200.00	\$240.00	\$21,600.00	\$310.00	\$27,900.00
10 TYPE 7 WHEELCHAIR RAMPS, INCLUDING TRUNCATED DOME SURFACE TO BE STAINED WITH CONTRASTING COLOR PER THE CONSTRUCTION PLAN SET, INCLUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER APPURTENANCES, COMPLETE IN PLACE	EA	10	\$1,450.00	\$14,500.00	\$1,400.00	\$14,000.00	\$2,000.00	\$20,000.00
11 TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, ETC.), PER TMUTCD, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$950.00	\$950.00	\$5,200.00	\$5,200.00
12 PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STOP SIGNS, STREET SIGNS, AND ALL OTHER TRAFFIC SIGNS SHOWN IN PLANS, ETC., COMPLETE IN PLACE	LS	1	\$8,590.50	\$8,590.50	\$3,600.00	\$3,600.00	\$8,800.00	\$8,800.00
13 INSTALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$100.00	\$200.00	\$1,450.00	\$2,900.00	\$1,200.00	\$2,400.00
14 BLUE DOUBLE REFLECTORIZED FIRE HYDRANT BUTTONS, COMPLETE IN PLACE	EA	11	\$16.00	\$176.00	\$8.00	\$88.00	\$15.00	\$165.00
15 CONNECT PROPOSED PAVEMENT TO EXISTING PAVEMENT, INCLUDES ANY OTHER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	87	\$7.00	\$609.00	\$47.00	\$4,089.00	\$30.00	\$2,610.00
16 REINFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	58	\$18.00	\$1,044.00	\$25.00	\$1,450.00	\$20.00	\$1,160.00
PAVING AND APPURTENANCES ITEMS SUBTOTAL:				\$1,189,414.00		\$1,216,176.20		\$1,195,135.30

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS

JUNE 19, 2024 LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

20/1002 1101			100	. 02.2 (.0)					
		7) ICON GC LLC			8) BEYER CONSTR	RUCTION, LLC	9) HCG		
ITEM DESCR	IPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
PAVING GENERAL ITEMS									
1 EXTRA CEMENT STABILIZED SAND BACKI COMPLETE IN PLACE	FILL, AS DIRECTED BY THE ENGINEER,	CY	500	\$38.00	\$19,000.00	\$38.00	\$19,000.00	\$38.00	\$19,000.00
2 EXTRA LIME AS DIRECTED BY THE ENGIN	IEER, COMPLETE IN PLACE	TON	50	\$375.00	\$18,750.00	\$369.00	\$18,450.00	\$325.00	\$16,250.00
3 EXTRA BROADCAST SEEDING, AS DIRECT PLACE	TED BY THE ENGINEER, COMPLETE IN	AC	1	\$1,500.00	\$1,500.00	\$600.00	\$600.00	\$1,200.00	\$1,200.00
4 EXTRA HYDROMULCH SEEDING, AS DIRE PLACE	CTED BY THE ENGINEER, COMPLETE IN	AC	1	\$2,500.00	\$2,500.00	\$1,500.00	\$1,500.00	\$2,500.00	\$2,500.00
5 6" PVC SLEEVES, SCHEDULE 40, COMPLE	TE IN PLACE	LF	76	\$36.00	\$2,736.00	\$49.00	\$3,724.00	\$55.00	\$4,180.00
6 PROVIDE CONCRETE TRUCK WASHOUT F CONSTRUCTION, COMPLETE IN PLACE	PIT AND REMOVAL ON POST	EA	1	\$100.00	\$100.00	\$2,100.00	\$2,100.00	\$1,500.00	\$1,500.00
7 FURNISH, INSTALL, MAINTAIN, AND REMO FABRIC FENCE (PAVING), COMPLETE IN F		LF	8125	\$1.00	\$8,125.00	\$1.50	\$12,187.50	\$4.40	\$35,750.00
8 FURNISH, INSTALL, MAINTAIN, AND REMO BARRIER, COMPLETE IN PLACE	VE STAGE I AND II INLET PROTECTION	EA	48	\$25.00	\$1,200.00	\$15,00	\$720.00	\$80.00	\$3,840.00
9 STABILIZED CONSTRUCTION EXIT, INCLU AND REMOVAL, COMPLETE IN PLACE	DING INSTALLATION, MAINTENANCE,	EA	1	\$100.00	\$100.00	\$2,000.00	\$2,000.00	\$1,800.00	\$1,800.00
10 STORM WATER POLLUTION PREVENTION CONTRACTOR'S BOOKLET NOI AND NOT,		LS	1	\$2,500.00	\$2,500.00	\$8,800.00	\$8,800.00	\$4,000.00	\$4,000.00
11 CLEARING AND GRUBBING, AS DIRECTED	BY ENGINEER, COMPLETE IN PLACE	AC	1	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00
12 CONSTRUCTION, CONTROL, AS BUILT AN PARTNERS, ALL STAKING TO BE PERFOR RESPONSIBILITY OF CONTRACTOR (CON 4539), COMPLETE IN PLACE	MED AT ONE TIME. RE-STAKING IS	LS		\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00	\$23,375.00
13 MISCELLANEOUS DRAINAGE SWALES, V- HYDROMULCH SEEDING AND WATERING COMPLETE IN PLACE		LF	1000	\$13.50	\$13,500.00	\$4.75	\$4,750.00	\$11.00	\$11,000.00
14 OVER EXCAVATION OF UNSUITABLE MAT DIRECTED BY THE ENGINEER, COMPLETE		CY	2000	\$3.60	\$7,200.00	\$3.00	\$6,000.00	\$18.00	\$36,000.00
PAVING GENERAL ITEMS SUBTOTAL:					\$105,586.00		\$108,206.50		\$165,395.00
BIDDING SUMMARY									
SUBTOTAL PAVING AND APPURTENANCES ITEM	MS				\$1,189,414.00		\$1,216,176.20		\$1,195,135.30
SUBTOTAL PAVING GENERAL ITEMS					\$105,586.00		\$108,206.50		\$165,395.00
TOTAL AMOUNT BASE BID					\$1,295,000.00		\$1,324,382.70		\$1,360,530.30

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO. CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2 CITY OF DAYTON, LIBERTY COUNTY, TEXAS

JUNE 19, 2024 LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

10) SCYTHE CONSTRUCTION, LLC

				10) SCYTHE CONST	RUCTION, LLC	
ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	
PAVING A	ND APPURTENANCES ITEMS					
1 6" RI	EINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	14084	\$57.90	\$815,463.60	
2 6" RI	EINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	1970	\$4.90	\$9,653.00	
3 4"X1	12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	6284	\$4.90	\$30,791.60	4.00
	IME STABILIZED SUBGRADE, MANIPULATION, INCLUDES COMPACTION TO 95% NDARD PROCTOR DENSITY, COMPLETE IN PLACE	SY	15924	\$5.70	\$90,766.80	
REQ	E FOR 6" SUBGRADE PREPARATION (8% BY WEIGHT, 38 LBS/SY), AS QUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, IPLETE IN PLACE	TON	303	\$395.00	\$119,685.00	
CON	ADWAY AND LOT EXCAVATION, IN ACCORDANCE WITH SUPPLEMENTAL NOTIONS ITEM "ESTIMATES OF EXCAVATION AND FILL QUANTITIES", IMPLETE IN PLACE	CY	19012	\$3.00	\$57,036.00	4-0019
MAT PRO DEN SUP	ADWAY AND LOT EMBANKMENT, INCLUDES REMOVAL OF UNSUITABLE TERIALS BEFORE PLACING FILL, STRIPPING, STOCKPILING OF STRIPPINGS, DOF ROLLING, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR ISITY, REAPPLICATION OF STRIPPINGS, IN ACCORDANCE WITH PLEMENTAL CONDITIONS ITEM "ESTIMATES OF EXCAVATION AND FILL WITHIES", COMPLETE IN PLACE	CY	19012	\$4.80	\$91,257.60	
USIN INCL COM	RA COST TO HAUL EXCAVATED MATERIAL OFFSITE IN LIEU OF ONSITE, NG OFF ROAD TRUCKS, (1 - 1.5 MILES), (AS DIRECTED BY ENGINEER), LUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND MIPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, IRE-APPLICATION OF STRIPPINGS TO FINAL GRADED AREA, COMPLETE IN CE	CY	6641	\$2.35	\$15,606.35	
HAU STR	AL LOT GRADING, INCLUDING RESERVES, STRIPPING AND PROOFROLLING, JUING, PLACEMENT AND COMPACTION OF MATERIALS AND REPLACEMENT OF RIPPINGS, INCLUDING MANIPULATION AND PLACEMENT OF STOCKPILE, MPLETE IN PLACE	EA	90	\$301.00	\$27,090.00	
STA INCL	E 7 WHEELCHAIR RAMPS, INCLUDING TRUNCATED DOME SURFACE TO BE INED WITH CONTRASTING COLOR PER THE CONSTRUCTION PLAN SET, LUDES REMOVAL OF EXISTING CURB IF REQUIRED AND ALL OTHER PURTENANCES, COMPLETE IN PLACE	EA	10	\$1,980.00	\$19,800.00	
THE	PORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF PROJECT, (FLAGGERS, CONES, ETC.), PER TMUTCD, INCLUDES TALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	\$2,560.00	\$2,560.00	
PAV SIGN	MANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, EMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STOP NS, STREET SIGNS, AND ALL OTHER TRAFFIC SIGNS SHOWN IN PLANS, ETC., MPLETE IN PLACE	LS	1	\$9,850.00	\$9,850.00	
13 INST	TALL TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,510.00	\$3,020.00	
14 BLU	E DOUBLE REFLECTORIZED FIRE HYDRANT BUTTONS, COMPLETE IN PLACE	EA	11	\$19.00	\$209.00	
	NNECT PROPOSED PAVEMENT TO EXISTING PAVEMENT, INCLUDES ANY HER NECESSARY APPURTENANCES, COMPLETE IN PLACE	LF	87	\$17.00	\$1,479.00	
16 REIN	NFORCED CONCRETE PAVING HEADER, COMPLETE IN PLACE	LF	58	\$19.00	\$1,102.00	
DAVING AN	ND APPURTENANCES ITEMS SUBTOTAL:				\$1,295,369.95	

Page 8 of 9 FRN F-1386 LJA Engineering, Inc.

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO. CONSTRUCTION OF PAVING AND APPURTENANCES TO SERVE MEDINA SECTION 2

CITY OF DAYTON, LIBERTY COUNTY, TEXAS

JUNE 19, 2024 LJA ENGINEERING, INC. AVIGAIL AMIGLEO JUNE 19, 2024 1931-3212 (10)

10) SCYTHE CONSTRUCTION, LLC

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
PAVI	NG GENERAL ITEMS				
1	EXTRA CEMENT STABILIZED SAND BACKFILL, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	CY	500	\$73.00	\$36,500.00
2	EXTRA LIME AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	TON	50	\$395.00	\$19,750.00
3	EXTRA BROADCAST SEEDING, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	AC	1	\$673.00	\$673.00
4	EXTRA HYDROMULCH SEEDING, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	AC	1	\$2,500.00	\$2,500.00
5	6" PVC SLEEVES, SCHEDULE 40, COMPLETE IN PLACE	LF	76	\$49.00	\$3,724.00
6	PROVIDE CONCRETE TRUCK WASHOUT PIT AND REMOVAL ON POST CONSTRUCTION, COMPLETE IN PLACE	EA	1	\$1,150.00	\$1,150.00
7	FURNISH, INSTALL, MAINTAIN, AND REMOVE SWPPP REINFORCED FILTER FABRIC FENCE (PAVING), COMPLETE IN PLACE	LF	8125	\$4.50	\$36,562.50
8	FURNISH, INSTALL, MAINTAIN, AND REMOVE STAGE I AND II INLET PROTECTION BARRIER, COMPLETE IN PLACE	EA	48	\$224.00	\$10,752.00
9	STABILIZED CONSTRUCTION EXIT, INCLUDING INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	EA	1	\$5,160.00	\$5,160.00
10	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDING CONTRACTOR'S BOOKLET NOI AND NOT, COMPLETE IN PLACE	LS	1	\$4,550.00	\$4,550.00
11	CLEARING AND GRUBBING, AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	AC	1	\$5,000.00	\$5,000.00
12	CONSTRUCTION, CONTROL, AS BUILT AND LOT PINNING STAKING SET BY GBI PARTNERS, ALL STAKING TO BE PERFORMED AT ONE TIME. RE-STAKING IS RESPONSIBILITY OF CONTRACTOR (CONTACT JASON ASHWORTH AT 281-499-4539), COMPLETE IN PLACE	LS		\$23,375.00	\$23,375.00
13	MISCELLANEOUS DRAINAGE SWALES, V-BOTTOM, GRADED TO DRAIN, INCLUDES HYDROMULCH SEEDING AND WATERING, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	1000	\$9.30	\$9,300.00
14	OVER EXCAVATION OF UNSUITABLE MATERIAL, FOR FILL PLACEMENT, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	CY	2000	\$4.50	\$9,000.00
PAVI	NG GENERAL ITEMS SUBTOTAL:				\$167,996.50
	ING SUMMARY				
	TOTAL PAVING AND APPURTENANCES ITEMS				\$1,295,369.95
SUBT	TOTAL PAVING GENERAL ITEMS				\$167,996.50
TOTA	AL AMOUNT BASE BID				\$1,463,366.45

 Page 9 of 9
 FRN F-1386

 LJA Engineering, Inc.