

Question No.	Date	Contractor	Firm	Question	Response
1	8/14/2026	Austin Baker	DDM Construction	Will pre-cast RCB be permitted for the cross culverts? Or is the intention for them to all be cast in place?	Contractor has the option to use precast or cast in place. Layout of culverts and headwalls assume common wall (cast in place). Note that culvert 4A has a specific detail on sheet S-4 and is intended to be cast in place.
2	8/14/2026	Austin Baker	DDM Construction	Regarding the grading associated with the Paving and Utility scopes. Between the two scopes the grading appears to require approximately 36,000 CY of excavation. Will the excess material all be required to be hauled off the site since the mass grading is complete? Or will it remain stockpiled onsite?	Excess material shall be placed at the stockpile location shown in the Stockpile Exhibit
3	8/14/2026	Austin Baker	DDM Construction	Will the paving contractor be permitted to use the stockpile and disposal area for our mobile batch plant? Or is there another location anticipated for this use onsite?	There is a separate location set aside for a batch plant adjacent to CR 202. We will issue an exhibit showing approximate location in an addendum.
4	8/14/2026	Austin Baker	DDM Construction	Regarding the storm and water work: Since the mass grading has been completed, is the contractor to assume the proposed grade line (PGL) on the profile for the utilities is the existing grade? Or is the existing grade line shown accurate?	In most cases, it is appropriate to assume that the PGL is existing. The heat map delineates areas where the PGL is not expected to be existing. Note that the CAD file named "20260728 LHP Project 1 Phase 2 0285LHPTPX1.dwg" gives mass grading contours.
5	8/14/2026	Austin Baker	DDM Construction	Will a site visit be permitted pre-bid? If so, please let me know who I can coordinate with.	A site visit is permitted. Please contact Shane Seabolt with Republic Property Group at 214.292.3410