

BID TABULATION FOR:


BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 4  
PROPOSED FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
OCTOBER 29, 2021  
LJA ENGINEERING, INC.  
A. OTTO  
OCTOBER 29, 2021  
2085-3040C (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) DURWOOD GREENE CONSTRUCTION CO.	\$705,637.00
2) TRIPLE B SERVICES, LLP	\$731,416.25

CALENDAR DAYS 50/60

I, Christopher J. LeBlanc, PE, hereby certify these bid tabulations to be true and correct.



**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 4  
 PROPOSED FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 OCTOBER 29, 2021  
 LJA ENGINEERING, INC.  
 A. OTTO  
 OCTOBER 29, 2021  
 2085-3040C (9.2)

1) DURWOOD GREENE CONSTRUCTION CO.                      2) TRIPLE B SERVICES, LLP

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>PAVING IMPROVEMENT ITEMS</b>							
1	6" REINFORCED CONCRETE PAVEMENT, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	11586	\$47.00	\$544,542.00	\$45.75	\$530,059.50
2	8" LIME STABILIZED SUB-GRADE (MANIPULATION), COMPLETE IN PLACE	SY	13060	\$3.00	\$39,180.00	\$4.25	\$55,505.00
3	HYDRATED LIME FOR 8" STABILIZED SUB-GRADE (35 LBS / SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	229	\$210.00	\$48,090.00	\$212.00	\$48,548.00
4	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$3,000.00	\$3,000.00	\$2,215.00	\$2,215.00
5	PERMANENT TRAFFIC CONTROL SIGNS INCLUDING STOP SIGNS, WITH STREET NAMES, DIRECTION SIGNS WITH SUPPLEMENTS, ETC., COMPLETE IN PLACE	EA	8	\$900.00	\$7,200.00	\$740.00	\$5,920.00
6	COMPLETE LOT GRADING (89 LOTS AND 4 RESERVES) AND FINAL DRESSING OF ALL AREAS, COMPLETE IN PLACE	LS	1	\$15,000.00	\$15,000.00	\$27,150.00	\$27,150.00
7	ROADWAY & LOT EXCAVATION, TO INCLUDE STRIPPING & PROOFROLLING, COMPLETE IN PLACE	CY	3325	\$2.50	\$8,312.50	\$3.20	\$10,640.00
8	ROADWAY, R.O.W. LOTS AND RESERVES FILL (IN PLACE) TO INCLUDE STRIPPING & PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS, COMPLETE IN PLACE	CY	3325	\$2.50	\$8,312.50	\$3.95	\$13,133.75
9	PROPOSED PAVING HEADER, COMPLETE IN PLACE	LF	56	\$20.00	\$1,120.00	\$16.50	\$924.00
10	TYPE 7 WHEELCHAIR RAMPS, PER DETAIL IN PLANS, COMPLETE IN PLACE	EA	12	\$1,400.00	\$16,800.00	\$1,885.00	\$22,620.00
11	TYPE III BARRICADE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	2	\$1,400.00	\$2,800.00	\$1,200.00	\$2,400.00
12	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$10.00	\$20.00	\$192.00	\$384.00
<b>PAVING IMPROVEMENT ITEMS SUBTOTAL:</b>					<b>\$694,377.00</b>		<b>\$719,499.25</b>
<b>MISCELLANEOUS ITEMS</b>							
1	STORMWATER POLLUTION PREVENTION PLAN COMPLIANCE, INSPECTIONS, MAINTENANCE OF ENTRANCE AND FENCE, NOI, NOT AND ALL OTHER ITEMS NOT SPECIFICALLY LISTED ABOVE, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$2,275.00	\$2,275.00
2	STABILIZED CONSTRUCTION EXIT, INSTALLATION, MAINTENANCE, AND REMOVAL (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), ENGINEER IN PLACE	EA	1	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00
3	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,138.00	\$1,138.00
4	CITY OF FULSHEAR INSPECTION FEE (1% OF CONSTRUCTION AMOUNT)	LS	1	\$7,060.00	\$7,060.00	\$7,304.00	\$7,304.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$11,260.00</b>		<b>\$11,917.00</b>
<b>BIDDING SUMMARY</b>							
SUBTOTAL PAVING IMPROVEMENT ITEMS					\$694,377.00		\$719,499.25
SUBTOTAL MISCELLANEOUS ITEMS					\$11,260.00		\$11,917.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$705,637.00</b>		<b>\$731,416.25</b>