

BID TABULATION FOR:


CONSTRUCTION OF WATER, SANITARY SEWER, DRAINAGE FACILITIES AND PAVING & APPURTENANCES TO SERVE PECAN RIDGE SECTION 5 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

APRIL 21, 2023  
LJA ENGINEERING, INC.  
A. OTTO  
APRIL 21, 2023  
2085-3050D (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID	BID INCLUDING ALTERNATE A - PAVING IMPROVEMENT ITEMS
1) R CONSTRUCTION CIVIL, LLC	\$999,340.65	\$1,369,606.85
2) HURTADO CONSTRUCTION COMPANY	\$1,019,875.45	\$1,388,937.41

CALENDAR DAYS 35/45



*Kap Mudd*

04/21/2023

I, Phillip Kane Mudd, PE, hereby certify these bid tabulations to be true and correct.

LJA Engineering, Inc.

**BID TABULATION FOR:**

CONSTRUCTION OF WATER, SANITARY SEWER, DRAINAGE FACILITIES AND PAVING & APPURTENANCES TO SERVE PECAN RIDGE SECTION 5 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 APRIL 21, 2023  
 LJA ENGINEERING, INC.  
 A. OTTO  
 APRIL 21, 2023  
 2085-3050D (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

ITEM	DESCRIPTION	UNIT	QTY	1) R CONSTRUCTION CIVIL, LLC		2) HURTADO CONSTRUCTION COMPANY	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>WATER ITEMS</b>							
1	4" PVC WATER PIPE, AWWA C-900, DR 18, CLASS 235, INCLUDES BEDDING, BACKFILL, AND FITTINGS, COMPLETE IN PLACE	LF	386	\$21.00	\$8,106.00	\$24.00	\$9,264.00
2	6" PVC WATER PIPE, AWWA C-900, DR 18, CLASS 235, INCLUDES BEDDING, BACKFILL, AND FITTINGS, COMPLETE IN PLACE	LF	497	\$29.00	\$14,413.00	\$30.58	\$15,198.26
3	8" PVC WATER PIPE, AWWA C-900, DR 18, CLASS 235, INCLUDES BEDDING, BACKFILL, AND FITTINGS, COMPLETE IN PLACE	LF	1324	\$36.00	\$47,664.00	\$38.88	\$51,477.12
4	4" AWWA GATE VALVE AND BOX, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	2	\$1,125.00	\$2,250.00	\$885.00	\$1,770.00
5	6" AWWA GATE VALVE AND BOX, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	2	\$1,330.00	\$2,660.00	\$1,093.00	\$2,186.00
6	8" AWWA GATE VALVE AND BOX, AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	2	\$1,875.00	\$3,750.00	\$1,628.00	\$3,256.00
7	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2848	\$0.10	\$284.80	\$0.02	\$56.96
8	FIRE HYDRANT UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE, 6" GATE VALVE & BOX, LEAD, AND FIRE HYDRANT, AND TRENCH SAFETY, COMPLETE IN PLACE	EA	5	\$5,750.00	\$28,750.00	\$5,800.00	\$29,000.00
9	REMOVE AND DISPOSE OF EXISTING PLUG AND CLAMP AND CONNECT PROPOSED WATERLINE TO EXISTING WATERLINE, COMPLETE IN PLACE	EA	1	\$330.00	\$330.00	\$8.00	\$8.00
10	SHORT SIDE SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE, INCLUDES METER BOX, CURB STOP, MARKER AND ALL NECESSARY CONNECTORS, PLUGS AND TAPS, COMPLETE IN PLACE	EA	18	\$580.00	\$10,440.00	\$628.00	\$11,304.00
11	LONG SIDE SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9), WATER SERVICE, INCLUDES METER BOX, CURB STOP, MARKER AND ALL NECESSARY CONNECTORS, PLUGS AND TAPS, TO BE INSTALLED DURING STAGE 1 OF THE CONSTRUCTION, COMPLETE IN PLACE	LF	641	\$20.00	\$12,820.00	\$25.00	\$16,025.00
12	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN PROJECT LIMITS), COMPLETE IN PLACE	CY	455	\$1.00	\$455.00	\$0.08	\$36.40
13	EXTRA CAST IRON FITTINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$1,000.00	\$1,000.00	\$1,000.00	\$1,000.00
<b>WATER ITEMS SUBTOTAL:</b>					<b>\$132,922.80</b>		<b>\$140,581.74</b>
<b>SANITARY SEWER SYSTEM ITEMS</b>							
1	8" PVC SEWER PIPE, 0' - 12' CUT, ASTM D-3034, SDR 26, TO INCLUDE BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	1507	\$33.00	\$49,731.00	\$45.00	\$67,815.00
2	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2160	\$0.10	\$216.00	\$0.02	\$43.20
3	STANDARD SANITARY SEWER MANHOLE FOR 6"-24" SANITARY SEWER PIPES, (0' - 8' DEPTH), TO INCLUDE INFLOW PREVENTER AND FINAL ADJUSTMENTS AS REQUIRED, COMPLETE IN PLACE	EA	13	\$2,300.00	\$29,900.00	\$2,638.00	\$34,294.00
4	EXTRA DEPTH OF SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	18	\$170.00	\$3,060.00	\$138.00	\$2,484.00
5	REMOVE AND DISPOSE OF EXISTING SANITARY PLUG AND CONNECT PROPOSED SANITARY SEWER TO EXISTING SANITARY SEWER, COMPLETE IN PLACE	EA	1	\$120.00	\$120.00	\$8.00	\$8.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF WATER, SANITARY SEWER, DRAINAGE FACILITIES  
 AND PAVING & APPURTENANCES TO SERVE PECAN RIDGE SECTION 5  
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 APRIL 21, 2023  
 LJA ENGINEERING, INC.  
 A. OTTO  
 APRIL 21, 2023  
 2085-3050D (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) R CONSTRUCTION CIVIL, LLC		2) HURTADO CONSTRUCTION COMPANY	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
6	DEWATERING, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	216	\$25.00	\$5,400.00	\$25.00	\$5,400.00
7	ADDITIONAL COST FOR SANITARY SEWER BEDDING AND BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00
8	EXTRA CEMENT STABILIZED SAND, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	50	\$20.00	\$1,000.00	\$20.00	\$1,000.00
9	"SHORT SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM D-3034, SDR 26, (ALL DEPTHS), INCLUDING CEMENT STABILIZED SAND BACKFILL, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	9	\$955.00	\$8,595.00	\$938.00	\$8,442.00
10	"FAR SIDE" DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEADS, ASTM D-3034, SDR 26, (ALL DEPTHS), ALL LENGTHS INCLUDING CEMENT STABILIZED SAND BACKFILL, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	LF	653	\$35.00	\$22,855.00	\$48.00	\$31,344.00
11	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN PROJECT LIMITS), COMPLETE IN PLACE	CY	323	\$1.00	\$323.00	\$0.02	\$6.46
12	TV INSPECTION FOR SANITARY SEWERS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	1507	\$2.00	\$3,014.00	\$0.02	\$30.14
13	STANDARD SANITARY SEWER DROP STRUCTURE, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$200.00	\$200.00	\$638.00	\$638.00
<b>SANITARY SEWER SYSTEM ITEMS SUBTOTAL:</b>					<b>\$125,914.00</b>	<b>\$153,004.80</b>	
<b>STORM SEWER SYSTEM ITEMS</b>							
1	24" RCP STORM SEWER, ASTM C-76, CLASS III, COMPLETE IN PLACE	LF	848	\$79.00	\$66,992.00	\$80.00	\$67,840.00
2	30" RCP STORM SEWER, ASTM C-76, CLASS III, COMPLETE IN PLACE	LF	262	\$102.00	\$26,724.00	\$104.00	\$27,248.00
3	36" RCP STORM SEWER, ASTM C-76, CLASS III, COMPLETE IN PLACE	LF	263	\$140.00	\$36,820.00	\$134.00	\$35,242.00
4	42" RCP STORM SEWER, ASTM C-76, CLASS III, COMPLETE IN PLACE	LF	227	\$187.00	\$42,449.00	\$178.00	\$40,406.00
5	48" RCP STORM SEWER, ASTM C-76, CLASS III, COMPLETE IN PLACE	LF	111	\$225.00	\$24,975.00	\$208.00	\$23,088.00
6	7' X 4' REINFORCED CONCRETE BOX (ASTM C-1433), ALL CUTS, TO INCLUDE BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	475	\$695.00	\$330,125.00	\$688.00	\$326,800.00
7	STAGE I – STANDARD (TYPE "H-2") INLET, ALL DEPTHS, INCLUDES TEMPORARY SILT BARRIER FENCE FOR STAGE I INLETS, COMPLETE IN PLACE	EA	14	\$1,050.00	\$14,700.00	\$998.00	\$13,972.00
8	STAGE II – STANDARD (TYPE "H-2") INLET, ALL DEPTHS, INCLUDES TEMPORARY SILT BARRIER FENCE FOR STAGE I INLETS, COMPLETE IN PLACE	EA	14	\$2,125.00	\$29,750.00	\$1,418.00	\$19,852.00
9	TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, ALL DEPTHS, INCLUDING FINAL ADJUSTMENTS AS REQUIRED, COMPLETE IN PLACE	EA	14	\$2,650.00	\$37,100.00	\$2,280.00	\$31,920.00
10	TYPE "C" MANHOLE FOR 48" STORM SEWER AND LARGER, ALL DEPTHS, INCLUDING FINAL ADJUSTMENTS AS REQUIRED, COMPLETE IN PLACE	EA	2	\$3,550.00	\$7,100.00	\$2,800.00	\$5,600.00
11	JUNCTION BOX, WITH TYPE "C" MANHOLE TOP, ALL DEPTHS & SIZES, INCLUDING FINAL ADJUSTMENTS AS REQUIRED, COMPLETE IN PLACE	EA	3	\$13,800.00	\$41,400.00	\$20,000.00	\$60,000.00
12	REMOVE AND DISPOSE OF EXISTING BRICK PLUG AND CONNECT PROPOSED MANHOLE TO EXISTING STORM SEWER, COMPLETE IN PLACE	EA	1	\$540.00	\$540.00	\$8.00	\$8.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF WATER, SANITARY SEWER, DRAINAGE FACILITIES  
 AND PAVING & APPURTENANCES TO SERVE PECAN RIDGE SECTION 5  
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 APRIL 21, 2023  
 LJA ENGINEERING, INC.  
 A. OTTO  
 APRIL 21, 2023  
 2085-3050D (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) R CONSTRUCTION CIVIL, LLC		2) HURTADO CONSTRUCTION COMPANY	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
13	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	2186	\$0.10	\$218.60	\$0.48	\$1,049.28
14	ADDITIONAL COST FOR STORM SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	100	\$15.00	\$1,500.00	\$15.00	\$1,500.00
15	DEWATERING, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	100	\$25.00	\$2,500.00	\$25.00	\$2,500.00
16	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN PROJECT LIMITS), COMPLETE IN PLACE	CY	1769	\$1.00	\$1,769.00	\$0.02	\$35.38
17	EXTRA CEMENT STABILIZED SAND, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$20.00	\$2,000.00	\$20.00	\$2,000.00
18	4" REINFORCED CONCRETE SLOPE PAVING, COMPLETE IN PLACE	SY	252	\$85.00	\$21,420.00	\$80.00	\$20,160.00
19	18" CONCRETE RIP RAP, COMPLETE IN PLACE	SY	134	\$98.00	\$13,132.00	\$78.00	\$10,452.00
<b>STORM SEWER SYSTEM ITEMS SUBTOTAL:</b>					<b>\$701,214.60</b>		<b>\$689,672.66</b>
<b>MISCELLANEOUS ITEMS</b>							
1	INSTALL AND MAINTAIN REINFORCED FILTER FABRIC FENCE ALONG BACK OF CURB (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	3433	\$1.25	\$4,291.25	\$1.25	\$4,291.25
2	INSTALL AND MAINTAIN FILTER FABRIC FENCE (TO BE USED AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	4163	\$1.00	\$4,163.00	\$1.00	\$4,163.00
3	STAGE II INLET PROTECTION BARRIER (TO BE USED AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	14	\$30.00	\$420.00	\$1.00	\$14.00
4	INSTALLATION, MAINTENANCE, AND REMOVAL OF ROCK FILTER DAM, TYPE 4, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$88.00	\$88.00
5	STABILIZED CONSTRUCTION EXIT, INCLUDES INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,750.00	\$1,750.00	\$800.00	\$800.00
6	CONCRETE TRUCK WASH OUT STATION, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$800.00	\$800.00
7	HYDRO-MULCH SEEDING, COMPLETE IN PLACE	AC	3	\$1,200.00	\$3,600.00	\$1,200.00	\$3,600.00
8	EXTRA BROADCAST SEEDING, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	AC	12	\$600.00	\$7,200.00	\$600.00	\$7,200.00
9	ADJUST EXISTING MANHOLE RIM ELEVATION AS REQUIRED (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	2	\$150.00	\$300.00	\$150.00	\$300.00
10	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDING INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00	\$800.00	\$800.00
11	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$800.00	\$800.00
12	CITY OF FULSHEAR INSPECTION FEE (1% OF CONSTRUCTION AMOUNT)	LS	1	\$13,365.00	\$13,365.00	\$13,760.00	\$13,760.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$39,289.25</b>		<b>\$36,616.25</b>

**BID TABULATION FOR:**

CONSTRUCTION OF WATER, SANITARY SEWER, DRAINAGE FACILITIES  
 AND PAVING & APPURTENANCES TO SERVE PECAN RIDGE SECTION 5  
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 APRIL 21, 2023  
 LJA ENGINEERING, INC.  
 A. OTTO  
 APRIL 21, 2023  
 2085-3050D (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

ITEM	DESCRIPTION	UNIT	QTY	1) R CONSTRUCTION CIVIL, LLC		2) HURTADO CONSTRUCTION COMPANY	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>ALTERNATE A - PAVING IMPROVEMENT ITEMS</b>							
1	6" REINFORCED CONCRETE PAVEMENT, INCLUDING REINFORCED CONCRETE CURB, COMPLETE IN PLACE	SY	5791	\$47.00	\$272,177.00	\$48.88	\$283,064.08
2	8" LIME STABILIZED SUB-GRADE (MANIPULATION), COMPLETE IN PLACE	SY	6732	\$3.40	\$22,888.80	\$3.18	\$21,407.76
3	HYDRATED LIME FOR 8" STABILIZED SUB-GRADE (35 LBS / SY) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	118	\$265.00	\$31,270.00	\$298.00	\$35,164.00
4	PERMANENT TRAFFIC CONTROL DEVICES, (INCLUDING TRAFFIC BUTTONS, PAVEMENT STRIPING), COMPLETE IN PLACE	LS	1	\$1,025.00	\$1,025.00	\$1,028.00	\$1,028.00
5	PERMANENT TRAFFIC CONTROL SIGNS INCLUDING STOP SIGNS, WITH STREET NAMES, DIRECTION SIGNS WITH SUPPLEMENTS, ETC., COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,008.00	\$1,008.00
6	COMPLETE LOT GRADING (32 LOTS AND 7 RESERVES) AND FINAL DRESSING OF ALL AREAS, COMPLETE IN PLACE	LS	1	\$9,100.00	\$9,100.00	\$5,280.00	\$5,280.00
7	ROADWAY & LOT EXCAVATION, TO INCLUDE STRIPPING & PROOFROLLING, COMPLETE IN PLACE	CY	5419	\$1.80	\$9,754.20	\$1.28	\$6,936.32
8	ROADWAY, R.O.W. LOTS AND RESERVES FILL (IN PLACE) TO INCLUDE STRIPPING & PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS, COMPLETE IN PLACE	CY	5419	\$1.80	\$9,754.20	\$1.28	\$6,936.32
9	EXCAVATION OF EXISTING STOCKPILE, TO INCLUDE STRIPPING, STOCKPILING OF STRIPPINGS, AND REAPPLYING STRIPPINGS AFTER EXCAVATION, COMPLETE IN PLACE	CY	1899	\$2.50	\$4,747.50	\$1.28	\$2,430.72
10	ROADWAY, R.O.W. LOTS AND RESERVES FILL (IN PLACE) OF EXCAVATION FROM EXISTING STOCKPILE, TO INCLUDE STRIPPING & PROOFROLLING, HAULING, PLACEMENT AND COMPACTION OF MATERIALS, COMPLETE IN PLACE	CY	1899	\$2.50	\$4,747.50	\$1.28	\$2,430.72
11	TYPE 7 WHEELCHAIR RAMPS, PER DETAIL IN PLANS, COMPLETE IN PLACE	EA	2	\$1,900.00	\$3,800.00	\$1,688.00	\$3,376.00
12	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1.00	\$2.00	\$0.02	\$0.04
<b>ALTERNATE A - PAVING IMPROVEMENT ITEMS SUBTOTAL:</b>					<b>\$370,266.20</b>		<b>\$369,061.96</b>
<b><u>BIDDING SUMMARY</u></b>							
SUBTOTAL WATER ITEMS					\$132,922.80		\$140,581.74
SUBTOTAL SANITARY SEWER SYSTEM ITEMS					\$125,914.00		\$153,004.80
SUBTOTAL STORM SEWER SYSTEM ITEMS					\$701,214.60		\$689,672.66
SUBTOTAL MISCELLANEOUS ITEMS					\$39,289.25		\$36,616.25
<b>TOTAL AMOUNT BASE BID</b>					<b>\$999,340.65</b>		<b>\$1,019,875.45</b>
<b><u>ALTERNATE A - PAVING IMPROVEMENT ITEMS</u></b>							
TOTAL AMOUNT BASE BID					\$999,340.65		\$1,019,875.45
SUBTOTAL ALTERNATE A - PAVING IMPROVEMENT ITEMS					\$370,266.20		\$369,061.96
<b>TOTAL AMOUNT INCLUDING ALTERNATE A - PAVING IMPROVEMENT ITEMS</b>					<b>\$1,369,606.85</b>		<b>\$1,388,937.41</b>