

BID TABULATION FOR:


CONSTRUCTION OF THE PAVING AND APPURTENANCES  
TO SERVE PECAN RIDGE SECTION 9  
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

APRIL 24, 2024  
LJA ENGINEERING, INC.  
A. OTTO  
APRIL 24, 2024  
2085-3090C (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) DURWOOD GREENE CONSTRUCTION CO.	\$645,878.75
2) HURTADO CONSTRUCTION COMPANY	\$653,047.08
3) DIMAS BROS. CONSTRUCTION	\$678,459.60

CALENDAR DAYS 40/50



*Kap Mudd*

04/25/2024

I, Phillip Kane Mudd, PE, hereby certify these bid tabulations to be true and correct.

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE PECAN RIDGE SECTION 9  
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 APRIL 24, 2024  
 LJA ENGINEERING, INC.  
 A. OTTO  
 APRIL 24, 2024  
 2085-3090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DURWOOD GREENE CONSTRUCTION CO.		2) HURTADO CONSTRUCTION COMPANY		3) DIMAS BROS. CONSTRUCTION	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<b>PAVING ITEMS</b>									
1	6-INCH REINFORCED CONCRETE PAVEMENT (3,000 PSI / 5 SACK CEMENT PER CUBIC YARD), COMPLETE IN PLACE	SY	6437	\$48.50	\$312,194.50	\$50.98	\$328,158.26	\$51.90	\$334,080.30
2	7-INCH REINFORCED CONCRETE PAVEMENT (3,000 PSI / 5 SACK CEMENT PER CUBIC YARD), COMPLETE IN PLACE	SY	2793	\$55.50	\$155,011.50	\$58.00	\$161,994.00	\$63.55	\$177,495.15
3	8" LIME STABILIZED SUBGRADE FOR 6-INCH PAVEMENT (MANIPULATION), COMPLETE IN PLACE	SY	10325	\$3.00	\$30,975.00	\$2.98	\$30,768.50	\$3.90	\$40,267.50
4	HYDRATED LIME FOR SUBGRADE, (2% BY DRY WEIGHT) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	69	\$385.00	\$26,565.00	\$335.00	\$23,115.00	\$325.00	\$22,425.00
5	FLY ASH FOR SUBGRADE, (8% BY DRY UNIT WEIGHT) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY A GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	273	\$135.00	\$36,855.00	\$148.00	\$40,404.00	\$128.00	\$34,944.00
6	4-INCH X 12-INCH REINFORCED CONCRETE CURB (3,000 PSI), COMPLETE IN PLACE	LF	1671	\$3.75	\$6,266.25	\$3.88	\$6,483.48	\$3.50	\$5,848.50
7	6-INCH REINFORCED CONCRETE CURB (3,000 PSI), COMPLETE IN PLACE	LF	3262	\$3.75	\$12,232.50	\$3.88	\$12,656.56	\$3.50	\$11,417.00
8	STANDARD PAVEMENT HEADER, COMPLETE IN PLACE	LF	38	\$15.00	\$570.00	\$28.00	\$1,064.00	\$30.00	\$1,140.00
9	ROADWAY, LOT AND RESERVE EXCAVATION AND EMBANKMENT, INCLUDES STRIPPINGS, STOCKPILING OF STRIPPINGS, COMPACTION TO 95% STANDARD PROCTOR DENSITY AND REAPPLICATION OF STRIPPINGS TO FINAL GRADED AREAS, COMPLETE IN PLACE	CY	3800	\$5.00	\$19,000.00	\$3.88	\$14,744.00	\$5.00	\$19,000.00
10	FINAL LOT AND RESERVE GRADING, COMPLETE IN PLACE	LS	1	\$9,000.00	\$9,000.00	\$8,000.00	\$8,000.00	\$5,000.00	\$5,000.00
11	REMOVE AND DISPOSE OF EXISTING BARRICADE, COMPLETE IN PLACE	EA	1	\$10.00	\$10.00	\$0.02	\$0.02	\$1.00	\$1.00
12	TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$3,000.00	\$3,000.00	\$50.00	\$50.00	\$1,200.00	\$1,200.00
13	CONNECTION TO EXISTING 7" CONCRETE PAVEMENT, COMPLETE IN PLACE	EA	1	\$700.00	\$700.00	\$1,500.00	\$1,500.00	\$500.00	\$500.00
14	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING ALL PAVEMENT STRIPPING, TRAFFIC BUTTONS, AND PERMANENT SIGNAGE, COMPLETE IN PLACE	LS	1	\$9,000.00	\$9,000.00	\$6,000.00	\$6,000.00	\$5,000.00	\$5,000.00
15	TEMPORARY TRAFFIC CONTROL DEVICES, INCLUDING ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	LS	1	\$10.00	\$10.00	\$8.00	\$8.00	\$500.00	\$500.00
16	CURB RAMPS, COMPLETE IN PLACE	EA	6	\$1,800.00	\$10,800.00	\$1,300.00	\$7,800.00	\$1,400.00	\$8,400.00
17	REGRAIDING OF V-BOTTOM SWALES, INCLUDES STRIPPINGS, STOCKPILING OF STRIPPINGS, COMPACTION TO 95% STANDARD PROCTOR DENSITY AND REAPPLICATION OF STRIPPINGS TO FINAL GRADED AREAS, COMPLETE IN PLACE	LF	510	\$3.00	\$1,530.00	\$1.48	\$754.80	\$2.50	\$1,275.00
<b>PAVING ITEMS SUBTOTAL:</b>					<b>\$633,719.75</b>		<b>\$643,500.62</b>		<b>\$668,493.45</b>
<b>MISCELLANEOUS ITEMS</b>									
1	REINFORCED FILTER FABRIC FENCE, COMPLETE IN PLACE	LF	100	\$1.50	\$150.00	\$1.50	\$150.00	\$1.50	\$150.00
2	STAGE II INLET PROTECTION BARRIERS (BURLAP BAG BARRIER), COMPLETE IN PLACE	EA	17	\$7.00	\$119.00	\$7.00	\$119.00	\$7.00	\$119.00
3	CONSTRUCT, MAINTAIN AND REMOVE STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$1,200.00	\$1,200.00	\$8.00	\$8.00	\$500.00	\$500.00

**BID TABULATION FOR:**

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

CONSTRUCTION OF THE PAVING AND APPURTENANCES  
 TO SERVE PECAN RIDGE SECTION 9  
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175  
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS  
 APRIL 24, 2024  
 LJA ENGINEERING, INC.  
 A. OTTO  
 APRIL 24, 2024  
 2085-3090C (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DURWOOD GREENE CONSTRUCTION CO.		2) HURTADO CONSTRUCTION COMPANY		3) DIMAS BROS. CONSTRUCTION	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
4	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$800.00	\$800.00	\$447.15	\$447.15
5	CEMENT STABILIZED SAND, 1.5 SACKS OF CEMENT PER CUBIC YARD OF MIX, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$20.00	\$20.00	\$20.00	\$20.00	\$40.00	\$40.00
6	CEMENT STABILIZED SAND, 2.0 SACKS PER TON, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$35.00	\$35.00	\$35.00	\$35.00	\$45.00	\$45.00
7	FLY ASH, COMPLETE IN PLACE	TON	10	\$100.00	\$1,000.00	\$100.00	\$1,000.00	\$128.00	\$1,280.00
8	TRAFFIC BUTTONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	1	\$15.00	\$15.00	\$5.00	\$5.00	\$5.00	\$5.00
9	THERMOPLASTIC PAVEMENT MARKINGS, ALL WIDTHS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	100	\$1.50	\$150.00	\$1.50	\$150.00	\$1.50	\$150.00
10	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE AND INSPECTIONS, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$800.00	\$800.00	\$500.00	\$500.00
11	CITY OF FULSHEAR INSPECTION FEE (1% OF CONSTRUCTION AMOUNT), COMPLETE IN PLACE	LS	1	\$6,470.00	\$6,470.00	\$6,459.46	\$6,459.46	\$6,730.00	\$6,730.00
<b>MISCELLANEOUS ITEMS SUBTOTAL:</b>					<b>\$12,159.00</b>		<b>\$9,546.46</b>		<b>\$9,966.15</b>
<b>BIDDING SUMMARY</b>									
SUBTOTAL PAVING ITEMS					\$633,719.75		\$643,500.62		\$668,493.45
SUBTOTAL MISCELLANEOUS ITEMS					\$12,159.00		\$9,546.46		\$9,966.15
<b>TOTAL AMOUNT BASE BID</b>					<b>\$645,878.75</b>		<b>\$653,047.08</b>		<b>\$678,459.60</b>