

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE LIFT STATION NO. 2
TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
FEBRUARY 15, 2024
LJA ENGINEERING, INC.
A. OTTO
FEBRUARY 16, 2024
2085-3102 (9.2)

BIDDER'S NAME	TOTAL AMOUNT BID
1) PELTIER BROTHERS CONSTRUCTION	\$834,090.00
2) 5J SERVICES, LLC	\$897,557.25
3) GAEL INC	\$1,029,961.64
4) REDDICO CONSTRUCTION COMPANY, INC.	\$1,100,797.50

CALENDAR DAYS 180/335/365



I, Ashley Broughton, PE, hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE LIFT STATION NO. 2
 TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
 FEBRUARY 15, 2024
 LJA ENGINEERING, INC.
 A. OTTO
 FEBRUARY 16, 2024
 2085-3102 (9.2)

				1) PELTIER BROTHERS CONSTRUCTION		2) 5J SERVICES, LLC		3) GAEL INC	
ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SANITARY LIFT STATION ITEMS									
1	SITE WORK, INCLUDING BUT NOT LIMITED TO SITE GRADING, HYDROMULCH SEEDING, SITE DRAINAGE, COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$10,000.00	\$10,000.00	\$46,210.00	\$46,210.00
2	8' DIAMETER CONCRETE WET WELL AND VALVE PAD, INCLUDING ACCESS HATCHES, VENT, AND ALL APPURTENANCES AS SHOWN ON DRAWINGS, COMPLETE IN PLACE	LS	1	\$515,000.00	\$515,000.00	\$326,825.00	\$326,825.00	\$366,682.00	\$366,682.00
3	20 HP SUBMERSIBLE NON-CLOG PUMP WITH MINIMUM EFFICIENCY OF 53% AT 379 GPM AND 80 T.D.H. WITH ONE PUMP RUNNING, INCLUDING DISCHARGE ELBOW, GUIDE RAILS, AND ALL APPURTENANCES FOR PROPOSED PUMPS, COMPLETE IN PLACE	EA	2	\$15,000.00	\$30,000.00	\$27,500.00	\$55,000.00	\$33,335.00	\$66,670.00
4	SANITARY LIFT STATION AND VALVE PAD PIPING, INCLUDING PIPE, VALVES, FITTINGS, SUPPORTS, AND ALL APPURTENANCES, COMPLETE IN PLACE	LS	1	\$50,000.00	\$50,000.00	\$100,000.00	\$100,000.00	\$76,194.00	\$76,194.00
5	6" REINFORCED CONCRETE PAVEMENT WITH 8" LIME OR CEMENT STABILIZED SUBGRADE EXTENDING 1 FOOT OUTSIDE PAVEMENT, COMPLETE IN PLACE	SY	178	\$100.00	\$17,800.00	\$75.00	\$13,350.00	\$223.00	\$39,694.00
6	6" CRUSHED CONCRETE SITE COVER WITH GEOFABRIC(TENSAR TRIAX TX 140 OR APPROVED EQUAL) WITH 8" LIME OR CEMENT STABILIZED SUBGRADE, COMPLETE IN PLACE	SY	464	\$36.00	\$16,704.00	\$55.00	\$25,520.00	\$40.00	\$18,560.00
7	8' TALL WOODEN FENCE INCLUDING 18' DOUBLE SWING GATE AS SHOWN ON PLANS, COMPLETE IN PLACE	LF	295	\$30.00	\$8,850.00	\$115.00	\$33,925.00	\$121.00	\$35,695.00
8	4" DIAMETER PIPE BOLLARD, COMPLETE IN PLACE	EA	3	\$500.00	\$1,500.00	\$800.00	\$2,400.00	\$1,183.00	\$3,549.00
9	8" PVC ASTM D2241 SDR 26, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	48	\$194.00	\$9,312.00	\$950.00	\$45,600.00	\$894.00	\$42,912.00
10	10" PVC ASTM D2241 SDR 26, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	9	\$220.00	\$1,980.00	\$1,150.00	\$10,350.00	\$1,222.00	\$10,998.00
11	6" AWWA C900, FORCE MAIN, DR 18, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	25	\$88.00	\$2,200.00	\$150.00	\$3,750.00	\$227.00	\$5,675.00
12	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	95	\$1.00	\$95.00	\$10.00	\$950.00	\$33.00	\$3,135.00
13	1" SCHEDULE 40 PVC WATER LINE, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING COMPLETE IN PLACE	LF	22	\$25.00	\$550.00	\$100.00	\$2,200.00	\$50.00	\$1,100.00
14	PROVIDE AND INSTALL REDUCED PRESSURE BACKFLOW PREVENTER, NON-FREEZE HOSE BIBB, ALL NECESSARY APPURTENANCES, COMPLETE IN PLACE	LS	1	\$600.00	\$600.00	\$6,500.00	\$6,500.00	\$6,230.00	\$6,230.00
15	GRASS SWALE, 3:1 SIDE SLOPE WITH V-BOTTOM, COMPLETE IN PLACE	LF	123	\$25.00	\$3,075.00	\$10.00	\$1,230.00	\$25.00	\$3,075.00
16	TYPE 'A' INLET, INCLUDING EXCAVATION, BACKFILL, AND BEDDING, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$2,750.00	\$2,750.00	\$3,500.00	\$3,500.00	\$3,750.00	\$3,750.00
17	12" RCP STORM SEWER, ALL DEPTHS, INCLUDING EXCAVATION BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	57	\$96.00	\$5,472.00	\$125.00	\$7,125.00	\$250.00	\$14,250.00
18	CONNECT PROPOSED 6" FORCE MAIN TO PROPOSED FORCE MAIN (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$50.00	\$50.00	\$2,000.00	\$2,000.00	\$4,500.00	\$4,500.00
19	CONNECT PROPOSED WATER LINE TO EXISTING WATER LINE (BY OTHERS) INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$50.00	\$50.00	\$2,000.00	\$2,000.00	\$500.00	\$500.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE LIFT STATION NO. 2
 TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
 FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
 CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
 FEBRUARY 15, 2024
 LJA ENGINEERING, INC.
 A. OTTO
 FEBRUARY 16, 2024
 2085-3102 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) PELTIER BROTHERS CONSTRUCTION		2) 5J SERVICES, LLC		3) GAEL INC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
20	CONNECT PROPOSED MANHOLE TO PROPOSED 8" SANITARY SEWER (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$100.00	\$100.00	\$4,000.00	\$4,000.00	\$1,000.00	\$1,000.00
21	STANDARD SANITARY MANHOLE ALL DEPTHS INCLUDES EXCAVATION, BEDDING, BACKFILL, COMPLETE IN PLACE	EA	1	\$14,000.00	\$14,000.00	\$9,000.00	\$9,000.00	\$17,178.00	\$17,178.00
22	ALLOWANCE FOR ELECTRIC SERVICE PROVIDER EXACT AMOUNT WILL BE REIMBURSED TO CONTRACTOR UPON SUBMITTAL OF INVOICE FROM ELECTRIC SERVICE PROVIDER, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
23	NEW 480V SERVICE WITH ALL DISCONNECTS, METERING, RACK AND DUCT BANK FROM TRANSFORMER POLE TO METER DISCONNECT, COMPLETE IN PLACE	LS	1	\$25,000.00	\$25,000.00	\$27,500.00	\$27,500.00	\$27,500.00	\$27,500.00
24	NEW 50 KW DIESEL GENERATOR, SUBBASE FUEL TANK, ATS, AND DUCT BANK FROM GENERATOR TO ATS, COMPLETE IN PLACE	LS	1	\$45,000.00	\$45,000.00	\$80,000.00	\$80,000.00	\$75,891.00	\$75,891.00
25	NEW DUPLEX LIFT STATION CONTROL PANEL WITH SOFT STARTS, ALL CONTROLS AND DUCT BANK FROM LIFT PUMPS TO NEW CONTROL PANEL, COMPLETE IN PLACE	LS	1	\$40,000.00	\$40,000.00	\$85,000.00	\$85,000.00	\$92,400.00	\$92,400.00
SANITARY LIFT STATION ITEMS SUBTOTAL:					\$815,088.00		\$877,725.00		\$983,348.00
MISCELLANEOUS ITEMS									
1	CITY OF FULSHEAR INSPECTION FEE, 1.0% OF THE TOTAL CONSTRUCTION COST, COMPLETE IN PLACE	LS	1	\$8,151.00	\$8,151.00	\$8,777.25	\$8,777.25	\$10,197.64	\$10,197.64
2	STORM WATER POLLUTION PREVENTION PLAN, INCLUDING ADMINISTRATION, MAINTENANCE, AND REMOVAL AS REQUIRED BY THE PLANS AND AS DIRECTED BY THE ENGINEER, (TO BE MAINTAINED UNTIL CONTRACTOR'S NOTICE OF TERMINATION IS SUBMITTED), COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$1,500.00	\$1,500.00	\$7,500.00	\$7,500.00
3	INSTALLATION, MAINTENANCE AND REMOVAL OF CONCRETE TRUCK WASHOUT, COMPLETE IN PLACE	LS	1	\$500.00	\$500.00	\$1,000.00	\$1,000.00	\$3,500.00	\$3,500.00
4	FILTER FABRIC FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	352	\$2.00	\$704.00	\$4.00	\$1,408.00	\$8.00	\$2,816.00
5	DEWATERING FOR STRUCTURE, AS REQUIRED BY SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1.00	\$1.00	\$1.00	\$1.00	\$5,000.00	\$5,000.00
6	DEWATERING OF LINE WORK (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	95	\$1.00	\$95.00	\$1.00	\$95.00	\$55.00	\$5,225.00
7	CONTROL OF SURFACE WATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1.00	\$1.00	\$1.00	\$1.00	\$2,500.00	\$2,500.00
8	EXTRA CEMENT STABILIZED SAND, (1.5 SACKS OF CEMENT PER CUBIC YARD CEMENT STABILIZED SAND), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	10	\$20.00	\$200.00	\$20.00	\$200.00	\$65.00	\$650.00
9	EXTRA 4,000 PSI CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	10	\$400.00	\$4,000.00	\$400.00	\$4,000.00	\$400.00	\$4,000.00
10	EXTRA COST OF UTILITY WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	95	\$30.00	\$2,850.00	\$30.00	\$2,850.00	\$55.00	\$5,225.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$19,002.00		\$19,832.25		\$46,613.64

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE LIFT STATION NO. 2
TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
FEBRUARY 15, 2024
LJA ENGINEERING, INC.
A. OTTO
FEBRUARY 16, 2024
2085-3102 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) PELTIER BROTHERS CONSTRUCTION		2) 5J SERVICES, LLC		3) GAEL INC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
<u>BIDDING SUMMARY</u>									
SUBTOTAL SANITARY LIFT STATION ITEMS					\$815,088.00		\$877,725.00		\$983,348.00
SUBTOTAL MISCELLANEOUS ITEMS					\$19,002.00		\$19,832.25		\$46,613.64
TOTAL AMOUNT BASE BID					\$834,090.00		\$897,557.25		\$1,029,961.64

LJA Engineering, Inc.

BID TABULATION FOR:**BID OPENING DATE:****BID OPENING LOCATION:****TABULATION BY:****TABULATION DATE:****LJA JOB NO.**

CONSTRUCTION OF THE LIFT STATION NO. 2
TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
FEBRUARY 15, 2024
LJA ENGINEERING, INC.
A. OTTO
FEBRUARY 16, 2024
2085-3102 (9.2)

4) REDDICO CONSTRUCTION COMPANY, INC.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
SANITARY LIFT STATION ITEMS					
1	SITE WORK, INCLUDING BUT NOT LIMITED TO SITE GRADING, HYDROMULCH SEEDING, SITE DRAINAGE, COMPLETE IN PLACE	LS	1	\$6,950.00	\$6,950.00
2	8' DIAMETER CONCRETE WET WELL AND VALVE PAD, INCLUDING ACCESS HATCHES, VENT, AND ALL APPURTENANCES AS SHOWN ON DRAWINGS, COMPLETE IN PLACE	LS	1	\$378,600.00	\$378,600.00
3	20 HP SUBMERSIBLE NON-CLOG PUMP WITH MINIMUM EFFICIENCY OF 53% AT 379 GPM AND 80 T.D.H. WITH ONE PUMP RUNNING, INCLUDING DISCHARGE ELBOW, GUIDE RAILS, AND ALL APPURTENANCES FOR PROPOSED PUMPS, COMPLETE IN PLACE	EA	2	\$86,610.00	\$173,220.00
4	SANITARY LIFT STATION AND VALVE PAD PIPING, INCLUDING PIPE, VALVES, FITTINGS, SUPPORTS, AND ALL APPURTENANCES, COMPLETE IN PLACE	LS	1	\$110,650.00	\$110,650.00
5	6" REINFORCED CONCRETE PAVEMENT WITH 8" LIME OR CEMENT STABILIZED SUBGRADE EXTENDING 1 FOOT OUTSIDE PAVEMENT, COMPLETE IN PLACE	SY	178	\$178.00	\$31,684.00
6	6" CRUSHED CONCRETE SITE COVER WITH GEOFABRIC(TENSAR TRIAX TX 140 OR APPROVED EQUAL) WITH 8" LIME OR CEMENT STABILIZED SUBGRADE, COMPLETE IN PLACE	SY	464	\$52.00	\$24,128.00
7	8' TALL WOODEN FENCE INCLUDING 18' DOUBLE SWING GATE AS SHOWN ON PLANS, COMPLETE IN PLACE	LF	295	\$105.00	\$30,975.00
8	4" DIAMETER PIPE BOLLARD, COMPLETE IN PLACE	EA	3	\$983.00	\$2,949.00
9	8" PVC ASTM D2241 SDR 26, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	48	\$446.00	\$21,408.00
10	10" PVC ASTM D2241 SDR 26, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	9	\$1,035.00	\$9,315.00
11	6" AWWA C900, FORCE MAIN, DR 18, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	25	\$89.00	\$2,225.00
12	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	95	\$1.00	\$95.00
13	1" SCHEDULE 40 PVC WATER LINE, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING COMPLETE IN PLACE	LF	22	\$30.00	\$660.00
14	PROVIDE AND INSTALL REDUCED PRESSURE BACKFLOW PREVENTER, NON-FREEZE HOSE BIBB, ALL NECESSARY APPURTENANCES, COMPLETE IN PLACE	LS	1	\$12,085.00	\$12,085.00
15	GRASS SWALE, 3:1 SIDE SLOPE WITH V-BOTTOM, COMPLETE IN PLACE	LF	123	\$10.50	\$1,291.50
16	TYPE 'A' INLET, INCLUDING EXCAVATION, BACKFILL, AND BEDDING, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$4,345.00	\$4,345.00
17	12" RCP STORM SEWER, ALL DEPTHS, INCLUDING EXCAVATION BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	57	\$123.00	\$7,011.00
18	CONNECT PROPOSED 6" FORCE MAIN TO PROPOSED FORCE MAIN (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$2,045.00	\$2,045.00
19	CONNECT PROPOSED WATER LINE TO EXISTING WATER LINE (BY OTHERS) INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$300.00	\$300.00

BID TABULATION FOR:

CONSTRUCTION OF THE LIFT STATION NO. 2
TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
FEBRUARY 15, 2024
LJA ENGINEERING, INC.
A. OTTO
FEBRUARY 16, 2024
2085-3102 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

4) REDDICO CONSTRUCTION COMPANY, INC.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
20	CONNECT PROPOSED MANHOLE TO PROPOSED 8" SANITARY SEWER (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$6,350.00	\$6,350.00
21	STANDARD SANITARY MANHOLE ALL DEPTHS INCLUDES EXCAVATION, BEDDING, BACKFILL, COMPLETE IN PLACE	EA	1	\$11,965.00	\$11,965.00
22	ALLOWANCE FOR ELECTRIC SERVICE PROVIDER EXACT AMOUNT WILL BE REIMBURSED TO CONTRACTOR UPON SUBMITTAL OF INVOICE FROM ELECTRIC SERVICE PROVIDER, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00
23	NEW 480V SERVICE WITH ALL DISCONNECTS, METERING, RACK AND DUCT BANK FROM TRANSFORMER POLE TO METER DISCONNECT, COMPLETE IN PLACE	LS	1	\$110,010.00	\$110,010.00
24	NEW 50 KW DIESEL GENERATOR, SUBBASE FUEL TANK, ATS, AND DUCT BANK FROM GENERATOR TO ATS, COMPLETE IN PLACE	LS	1	\$61,870.00	\$61,870.00
25	NEW DUPLEX LIFT STATION CONTROL PANEL WITH SOFT STARTS, ALL CONTROLS AND DUCT BANK FROM LIFT PUMPS TO NEW CONTROL PANEL, COMPLETE IN PLACE	LS	1	\$48,330.00	\$48,330.00

SANITARY LIFT STATION ITEMS SUBTOTAL:**\$1,078,461.50****MISCELLANEOUS ITEMS**

1	CITY OF FULSHEAR INSPECTION FEE, 1.0% OF THE TOTAL CONSTRUCTION COST, COMPLETE IN PLACE	LS	1	\$10,899.00	\$10,899.00
2	STORM WATER POLLUTION PREVENTION PLAN, INCLUDING ADMINISTRATION, MAINTENANCE, AND REMOVAL AS REQUIRED BY THE PLANS AND AS DIRECTED BY THE ENGINEER, (TO BE MAINTAINED UNTIL CONTRACTOR'S NOTICE OF TERMINATION IS SUBMITTED), COMPLETE IN PLACE	LS	1	\$2,585.00	\$2,585.00
3	INSTALLATION, MAINTENANCE AND REMOVAL OF CONCRETE TRUCK WASHOUT, COMPLETE IN PLACE	LS	1	\$825.00	\$825.00
4	FILTER FABRIC FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	352	\$2.50	\$880.00
5	DEWATERING FOR STRUCTURE, AS REQUIRED BY SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1.00	\$1.00
6	DEWATERING OF LINE WORK (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	95	\$1.00	\$95.00
7	CONTROL OF SURFACE WATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1.00	\$1.00
8	EXTRA CEMENT STABILIZED SAND, (1.5 SACKS OF CEMENT PER CUBIC YARD CEMENT STABILIZED SAND), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	10	\$20.00	\$200.00
9	EXTRA 4,000 PSI CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	10	\$400.00	\$4,000.00
10	EXTRA COST OF UTILITY WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	95	\$30.00	\$2,850.00

MISCELLANEOUS ITEMS SUBTOTAL:**\$22,336.00**

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE LIFT STATION NO. 2
TO SERVE FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
FEBRUARY 15, 2024
LJA ENGINEERING, INC.
A. OTTO
FEBRUARY 16, 2024
2085-3102 (9.2)
4) REDDICO CONSTRUCTION COMPANY, INC.

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<u>BIDDING SUMMARY</u>					
SUBTOTAL SANITARY LIFT STATION ITEMS					\$1,078,461.50
SUBTOTAL MISCELLANEOUS ITEMS					\$22,336.00
TOTAL AMOUNT BASE BID					\$1,100,797.50

LJA Engineering, Inc.