


BID TABULATION FOR:

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 13
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
MAY 06, 2025
LJA ENGINEERING, INC.
A. OTTO
MAY 06, 2025
2085-3130C (9.2)

BID OPENING DATE:**BID OPENING LOCATION:****TABULATION BY:****TABULATION DATE:****LJA JOB NO.**

BIDDER NAME	BASE BID	PROPOSED DURATION (DAYS)
1) D&J CONSTRUCTION, INC	\$1,265,933.75	65 \ 75
2) DIMAS BROS. CONSTRUCTION	\$1,281,500.00	45 \ 50
3) DURWOOD GREENE CONSTRUCTION CO.	\$1,282,463.75	50 \ 60
4) R CONSTRUCTION CIVIL, LLC	\$1,299,083.20	80 \ 90
5) MH2 CONSTRUCTION SERVICES, LLC	\$1,408,000.00	60 \ 60
6) PRECISE SERVICES INC.	\$1,578,000.00	45 \ 60



A handwritten signature in black ink, appearing to read "Karl Mudd", positioned over the bottom left of the professional seal.

05/09/2025

I, Phillip Kane Mudd, PE, hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 13
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
MAY 06, 2025
LJA ENGINEERING, INC.
A. OTTO
MAY 06, 2025
2085-3130C (9.2)

				1) D&J CONSTRUCTION, INC		2) DIMAS BROS. CONSTRUCTION		3) DURWOOD GREENE CONSTRUCTION CO.		4) R CONSTRUCTION CIVIL, LLC	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
PAVING ITEMS											
1.	6-INCH REINFORCED CONCRETE PAVEMENT (3,000 PSI / 5 SACK CEMENT PER CUBIC YARD), COMPLETE IN PLACE	SY	17614	\$49.00	\$863,086.00	\$48.60	\$856,040.40	\$49.00	\$863,086.00	\$49.00	\$863,086.00
2.	8" LIME STABILIZED SUBGRADE FOR 6-INCH PAVEMENT (MANIPULATION), COMPLETE IN PLACE	SY	18756	\$3.75	\$70,335.00	\$3.75	\$70,335.00	\$3.50	\$65,646.00	\$4.20	\$78,775.20
3.	HYDRATED LIME FOR SUBGRADE, (2% BY DRY WEIGHT) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	124	\$375.00	\$46,500.00	\$328.00	\$40,672.00	\$390.00	\$48,360.00	\$375.00	\$46,500.00
4.	FLY ASH FOR SUBGRADE, (8% BY DRY UNIT WEIGHT) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY A GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	495	\$136.00	\$67,320.00	\$125.00	\$61,875.00	\$135.00	\$66,825.00	\$155.00	\$76,725.00
5.	4-INCH X 12-INCH REINFORCED CONCRETE CURB (3,000 PSI), COMPLETE IN PLACE	LF	6669	\$3.75	\$25,008.75	\$3.65	\$24,341.85	\$3.75	\$25,008.75	\$4.00	\$26,676.00
6.	6-INCH REINFORCED CONCRETE CURB (3,000 PSI), COMPLETE IN PLACE	LF	3612	\$3.75	\$13,545.00	\$3.65	\$13,183.80	\$3.75	\$13,545.00	\$4.00	\$14,448.00
7.	ROADWAY, LOT AND RESERVE EXCAVATION AND EMBANKMENT, INCLUDES STRIPPINGS, STOCKPILING OF STRIPPINGS, COMPACTION TO 95% STANDARD PROCTOR DENSITY AND REAPPLICATION OF STRIPPINGS TO FINAL GRADED AREAS, COMPLETE IN PLACE	CY	25000	\$3.50	\$87,500.00	\$4.35	\$108,750.00	\$4.00	\$100,000.00	\$3.55	\$88,750.00
8.	FINAL LOT AND RESERVE GRADING, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$40,000.00	\$40,000.00	\$27,000.00	\$27,000.00	\$27,000.00	\$27,000.00
9.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING ALL PAVEMENT STRIPPING, TRAFFIC BUTTONS, AND PERMANENT SIGNAGE, COMPLETE IN PLACE	LS	1	\$16,000.00	\$16,000.00	\$11,000.00	\$11,000.00	\$13,800.00	\$13,800.00	\$14,000.00	\$14,000.00
10.	TEMPORARY TRAFFIC CONTROL DEVICES, INCLUDING ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$500.00	\$500.00	\$10.00	\$10.00	\$1.00	\$1.00
11.	PAVEMENT HEADER, COMPLETE IN PLACE	LF	56	\$15.00	\$840.00	\$28.00	\$1,568.00	\$10.00	\$560.00	\$23.00	\$1,288.00
12.	TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,400.00	\$2,800.00	\$1,200.00	\$2,400.00	\$1,500.00	\$3,000.00	\$1,200.00	\$2,400.00
13.	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$1.00	\$1.00	\$1.00	\$1.00	\$10.00	\$10.00	\$1.00	\$1.00
14.	CONNECTION TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	EA	1	\$750.00	\$750.00	\$884.00	\$884.00	\$700.00	\$700.00	\$2,700.00	\$2,700.00
15.	TYPE 7 ADA RAMPS, COMPLETE IN PLACE	EA	22	\$1,300.00	\$28,600.00	\$1,484.00	\$32,648.00	\$1,600.00	\$35,200.00	\$1,750.00	\$38,500.00
SUBTOTAL PAVING ITEMS					\$1,243,785.75		\$1,264,199.05		\$1,262,750.75		\$1,280,850.20
MISCELLANEOUS ITEMS											
1.	REINFORCED FILTER FABRIC FENCE, COMPLETE IN PLACE	LF	1000	\$2.50	\$2,500.00	\$1.50	\$1,500.00	\$1.50	\$1,500.00	\$1.50	\$1,500.00
2.	STAGE II INLET PROTECTION BARRIERS (BURLAP BAG BARRIER), COMPLETE IN PLACE	EA	39	\$7.00	\$273.00	\$7.00	\$273.00	\$7.00	\$273.00	\$7.00	\$273.00
3.	CONSTRUCT, MAINTAIN AND REMOVE STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$500.00	\$500.00	\$800.00	\$800.00	\$1,500.00	\$1,500.00
4.	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,200.00	\$1,200.00	\$400.00	\$400.00	\$1,500.00	\$1,500.00	\$500.00	\$500.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 13
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
MAY 06, 2025
LJA ENGINEERING, INC.
A. OTTO
MAY 06, 2025
2085-3130C (9.2)

NO.	ITEM DESCRIPTION	UNIT	QTY	1) D&J CONSTRUCTION, INC		2) DIMAS BROS. CONSTRUCTION		3) DURWOOD GREENE CONSTRUCTION CO.		4) R CONSTRUCTION CIVIL, LLC	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
5.	CEMENT STABILIZED SAND, 1.5 SACKS OF CEMENT PER CUBIC YARD OF MIX, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$55.00	\$55.00	\$25.00	\$25.00	\$20.00	\$20.00	\$20.00	\$20.00
6.	CEMENT STABILIZED SAND, 2.0 SACKS PER TON, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$60.00	\$60.00	\$45.00	\$45.00	\$35.00	\$35.00	\$35.00	\$35.00
7.	FLY ASH, COMPLETE IN PLACE	TON	10	\$125.00	\$1,250.00	\$125.00	\$1,250.00	\$100.00	\$1,000.00	\$100.00	\$1,000.00
8.	TRAFFIC BUTTONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	11	\$10.00	\$110.00	\$5.00	\$55.00	\$10.00	\$110.00	\$5.00	\$55.00
9.	THERMOPLASTIC PAVEMENT MARKINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL WIDTHS, COMPLETE IN PLACE	LF	100	\$10.00	\$1,000.00	\$1.50	\$150.00	\$1.50	\$150.00	\$1.50	\$150.00
10.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE AND INSPECTIONS, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$622.95	\$622.95	\$1,500.00	\$1,500.00	\$1,200.00	\$1,200.00
11.	CITY OF FULSHEAR INSPECTION FEE (1% OF CONSTRUCTION AMOUNT), COMPLETE IN PLACE	LS	1	\$12,700.00	\$12,700.00	\$12,480.00	\$12,480.00	\$12,825.00	\$12,825.00	\$12,000.00	\$12,000.00
SUBTOTAL MISCELLANEOUS ITEMS					\$22,148.00		\$17,300.95		\$19,713.00		\$18,233.00
BID SUMMARY											
PAVING ITEMS					\$1,243,785.75		\$1,264,199.05		\$1,262,750.75		\$1,280,850.20
MISCELLANEOUS ITEMS					\$22,148.00		\$17,300.95		\$19,713.00		\$18,233.00
TOTAL AMOUNT BASE BID					\$1,265,933.75		\$1,281,500.00		\$1,282,463.75		\$1,299,083.20

BID TABULATION FOR:

BID OPENING DATE:

BID OPENING LOCATION:

TABULATION BY:

TABULATION DATE:

LJA JOB NO.

**CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 13
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
MAY 06, 2025
LJA ENGINEERING, INC.
A. OTTO
MAY 06, 2025
2085-3130C (9.2)**

				5) MH2 CONSTRUCTION SERVICES, LLC		6) PRECISE SERVICES INC.	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL
PAVING ITEMS							
1.	6-INCH REINFORCED CONCRETE PAVEMENT (3,000 PSI / 5 SACK CEMENT PER CUBIC YARD), COMPLETE IN PLACE	SY	17614	\$51.98	\$915,575.72	\$60.00	\$1,056,840.00
2.	8" LIME STABILIZED SUBGRADE FOR 6-INCH PAVEMENT (MANIPULATION), COMPLETE IN PLACE	SY	18756	\$4.51	\$84,589.56	\$5.85	\$109,722.60
3.	HYDRATED LIME FOR SUBGRADE, (2% BY DRY WEIGHT) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	124	\$362.00	\$44,888.00	\$345.00	\$42,780.00
4.	FLY ASH FOR SUBGRADE, (8% BY DRY UNIT WEIGHT) AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY A GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	495	\$180.00	\$89,100.00	\$135.00	\$66,825.00
5.	4-INCH X 12-INCH REINFORCED CONCRETE CURB (3,000 PSI), COMPLETE IN PLACE	LF	6669	\$4.05	\$27,009.45	\$4.25	\$28,343.25
6.	6-INCH REINFORCED CONCRETE CURB (3,000 PSI), COMPLETE IN PLACE	LF	3612	\$4.05	\$14,628.60	\$4.25	\$15,351.00
7.	ROADWAY, LOT AND RESERVE EXCAVATION AND EMBANKMENT, INCLUDES STRIPPINGS, STOCKPILING OF STRIPPINGS, COMPACTION TO 95% STANDARD PROCTOR DENSITY AND REAPPLICATION OF STRIPPINGS TO FINAL GRADED AREAS, COMPLETE IN PLACE	CY	25000	\$4.01	\$100,250.00	\$6.15	\$153,750.00
8.	FINAL LOT AND RESERVE GRADING, COMPLETE IN PLACE	LS	1	\$40,128.00	\$40,128.00	\$24,610.15	\$24,610.15
9.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING ALL PAVEMENT STRIPPING, TRAFFIC BUTTONS, AND PERMANENT SIGNAGE, COMPLETE IN PLACE	LS	1	\$17,190.00	\$17,190.00	\$16,000.00	\$16,000.00
10.	TEMPORARY TRAFFIC CONTROL DEVICES, INCLUDING ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, STREET SIGNS AND TRAFFIC SIGNS, COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$1,500.00	\$1,500.00
11.	PAVEMENT HEADER, COMPLETE IN PLACE	LF	56	\$18.00	\$1,008.00	\$22.50	\$1,260.00
12.	TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$1,500.00	\$3,000.00	\$1,450.00	\$2,900.00
13.	REMOVE AND DISPOSE OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	1	\$0.25	\$0.25	\$100.00	\$100.00
14.	CONNECTION TO EXISTING 6" CONCRETE PAVEMENT, COMPLETE IN PLACE	EA	1	\$3,248.00	\$3,248.00	\$1,050.00	\$1,050.00
15.	TYPE 7 ADA RAMPS, COMPLETE IN PLACE	EA	22	\$1,668.00	\$36,696.00	\$1,450.00	\$31,900.00
SUBTOTAL PAVING ITEMS					\$1,385,311.58		\$1,552,932.00
MISCELLANEOUS ITEMS							
1.	REINFORCED FILTER FABRIC FENCE, COMPLETE IN PLACE	LF	1000	\$1.50	\$1,500.00	\$1.50	\$1,500.00
2.	STAGE II INLET PROTECTION BARRIERS (BURLAP BAG BARRIER), COMPLETE IN PLACE	EA	39	\$7.00	\$273.00	\$7.00	\$273.00
3.	CONSTRUCT, MAINTAIN AND REMOVE STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00
4.	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$1,500.00	\$1,500.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE PAVING AND APPURTENANCES TO SERVE PECAN RIDGE SECTION 13
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 175
CITY OF FULSHEAR, FORT BEND COUNTY, TEXAS
MAY 06, 2025
LJA ENGINEERING, INC.
A. OTTO
MAY 06, 2025
2085-3130C (9.2)

				5) MH2 CONSTRUCTION SERVICES, LLC		6) PRECISE SERVICES INC.	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL
5.	CEMENT STABILIZED SAND, 1.5 SACKS OF CEMENT PER CUBIC YARD OF MIX, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$20.00	\$20.00	\$20.00	\$20.00
6.	CEMENT STABILIZED SAND, 2.0 SACKS PER TON, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$35.00	\$35.00	\$35.00	\$35.00
7.	FLY ASH, COMPLETE IN PLACE	TON	10	\$100.00	\$1,000.00	\$135.00	\$1,350.00
8.	TRAFFIC BUTTONS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	EA	11	\$5.00	\$55.00	\$10.00	\$110.00
9.	THERMOPLASTIC PAVEMENT MARKINGS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL WIDTHS, COMPLETE IN PLACE	LF	100	\$10.00	\$1,000.00	\$10.00	\$1,000.00
10.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE AND INSPECTIONS, COMPLETE IN PLACE	LS	1	\$800.00	\$800.00	\$2,000.00	\$2,000.00
11.	CITY OF FULSHEAR INSPECTION FEE (1% OF CONSTRUCTION AMOUNT), COMPLETE IN PLACE	LS	1	\$15,005.42	\$15,005.42	\$15,780.00	\$15,780.00
SUBTOTAL MISCELLANEOUS ITEMS					\$22,688.42		\$25,068.00
BID SUMMARY							
PAVING ITEMS					\$1,385,311.58		\$1,552,932.00
MISCELLANEOUS ITEMS					\$22,688.42		\$25,068.00
TOTAL AMOUNT BASE BID					\$1,408,000.00		\$1,578,000.00