


BID TABULATION FOR:

CONSTRUCTION OF THE ESCONDIDO LIFT STATION NO. 1
TO SERVE MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS
NOVEMBER 12, 2020
LJA ENGINEERING, INC.
D. FORREST
NOVEMBER 12, 2020
2139-3009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID
1) 5J SERVICES, LLC	\$563,897.50
2) REDDICO CONSTRUCTION COMPANY, INC.	\$572,505.98
3) LINDSEY CONSTRUCTION	\$634,350.00
4) PRINCIPAL PLANT SERVICES	\$793,537.00
5) AR TURNKEE	\$903,768.00

CALENDAR DAYS - 150/180



Armando R. Rueda
11/12/2020

Armando R. Rueda
I, Armando R. Rueda, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

CONSTRUCTION OF THE ESCONDIDO LIFT STATION NO. 1
 TO SERVE MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS
 NOVEMBER 12, 2020
 LJA ENGINEERING, INC.
 D. FORREST
 NOVEMBER 12, 2020
 2139-3009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	1) 5J SERVICES, LLC		2) REDDICO CONSTRUCTION COMPANY, INC.		3) LINDSEY CONSTRUCTION	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SANITARY LIFT STATION ITEMS									
1	SITE WORK, INCLUDING BUT NOT LIMITED TO SITE GRADING, BROADCAST SEEDING, SITE DRAINAGE, COMPLETE IN PLACE	LS	1	\$7,500.00	\$7,500.00	\$21,560.00	\$21,560.00	\$12,000.00	\$12,000.00
2	8' CONCRETE WET WELL AND VALVE PAD, INCLUDING ACCESS HATCHES, VENT, AND ALL APPURTENANCES AS SHOWN ON PLANS, COMPLETE IN PLACE	LS	1	\$195,393.00	\$195,393.00	\$180,645.00	\$180,645.00	\$248,451.00	\$248,451.00
3	15 HP SUBMERSIBLE PUMP WITH MINIMUM EFFICIENCY OF 58 AT 306 GPM AND 65' T.D.H., INCLUDING DISCHARGE ELBOW, GUIDE RAILS, AND ALL APPURTENANCES FOR PROPOSED PUMPS, COMPLETE IN PLACE	EA	2	\$10,000.00	\$20,000.00	\$34,655.00	\$69,310.00	\$35,000.00	\$70,000.00
4	SANITARY LIFT STATION AND VALVE PAD PIPING, INCLUDING PIPE, VALVES, FITTINGS, SUPPORTS, AND ALL APPURTENANCES, COMPLETE IN PLACE	LS	1	\$55,000.00	\$55,000.00	\$48,882.00	\$48,882.00	\$52,000.00	\$52,000.00
5	18" AWWA C-905 DR 18, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	28	\$450.00	\$12,600.00	\$480.00	\$13,440.00	\$500.00	\$14,000.00
6	8" AWWA C900, FORCE MAIN, DR 18, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	68	\$125.00	\$8,500.00	\$84.00	\$5,712.00	\$95.00	\$6,460.00
7	STANDARD SANITARY MANHOLE ALL DEPTHS, INCLUDES EXCAVATION, BEDDING, BACKFILL, COMPLETE IN PLACE	EA	1	\$6,000.00	\$6,000.00	\$4,750.00	\$4,750.00	\$5,000.00	\$5,000.00
8	6" REINFORCED CONCRETE PAVEMENT WITH 8" LIME OR CEMENT STABILIZED SUBGRADE EXTENDING 1' OUTSIDE PAVEMENT, COMPLETE IN PLACE	SY	283	\$70.00	\$19,810.00	\$86.50	\$24,479.50	\$60.00	\$16,980.00
9	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	96	\$10.00	\$960.00	\$1.15	\$110.40	\$1.00	\$96.00
10	8' WOOD FENCE, WITH 16 FOOT DOUBLE SWING WOOD GATE, AND ALL APPURTENANCES, (AS SHOWN ON PLANS), COMPLETE IN PLACE	LF	250	\$100.00	\$25,000.00	\$87.00	\$21,750.00	\$80.00	\$20,000.00
11	1" SCH. 40 P.V.C. WATER LINE, COMPLETE IN PLACE	LF	33	\$10.00	\$330.00	\$67.50	\$2,227.50	\$20.00	\$660.00
12	PROVIDE AND INSTALL REDUCED PRESSURE BACKFLOW PREVENTER, NON-FREEZE HOSE BIB, ALL NECESSARY APPURTENANCES, COMPLETE IN PLACE	LS	1	\$4,500.00	\$4,500.00	\$4,987.00	\$4,987.00	\$3,000.00	\$3,000.00
13	4" PIPE BOLLARD, COMPLETE IN PLACE	EA	8	\$650.00	\$5,200.00	\$854.00	\$6,832.00	\$425.00	\$3,400.00
14	6" CRUSHED CONCRETE WITH GEOFABRIC (TENSAR TRIAX TX140 OR APPROVED EQUAL), COMPLETE IN PLACE	SY	242	\$40.00	\$9,680.00	\$25.90	\$6,267.80	\$20.00	\$4,840.00
15	ALLOWANCE FOR ESTABLISHED ELECTRICAL SERVICE AS DIRECTED BY ENTERGY, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER). CHARGES FROM ENTERGY SHALL BE PAID BY THE CONTRACTOR. THE AMOUNTS PAID, SUPPORTED BY INVOICES, SHALL BE INCLUDED IN PAY REQUESTS FOR REIMBURSEMENT WITHOUT A GENERAL CONTRACTOR MARKUP, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
16	CORE INTO EXISTING MANHOLE AND CONNECT PROPOSED 18" SANITARY SEWER LINE TO SANITARY SEWER (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$2,000.00	\$2,000.00	\$1,860.00	\$1,860.00	\$5,000.00	\$5,000.00
17	CONNECT PROPOSED 8" FORCE MAIN TO PROPOSED FORCE MAIN (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$885.00	\$885.00	\$2,500.00	\$2,500.00
18	STORM WATER POLLUTION PREVENTION PLAN, INCLUDING ADMINISTRATION, MAINTENANCE, AND REMOVAL AS REQUIRED BY THE PLANS AND AS DIRECTED BY THE ENGINEER, (TO BE MAINTAINED UNTIL CONTRACTOR'S NOTICE OF TERMINATION IS SUBMITTED), COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$557.00	\$557.00	\$4,000.00	\$4,000.00

BID TABULATION FOR:

CONSTRUCTION OF THE ESCONDIDO LIFT STATION NO. 1
 TO SERVE MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS
 NOVEMBER 12, 2020
 LJA ENGINEERING, INC.
 D. FORREST
 NOVEMBER 12, 2020
 2139-3009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	1) 5J SERVICES, LLC		2) REDDICO CONSTRUCTION COMPANY, INC.		3) LINDSEY CONSTRUCTION	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
19	FILTER FABRIC FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	255	\$3.00	\$765.00	\$3.00	\$765.00	\$3.00	\$765.00
20	INSTALLATION, MAINTENANCE AND REMOVAL OF CONCRETE TRUCK WASHOUT, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$500.00	\$500.00	\$1,200.00	\$1,200.00
21	200A 480V SERVICE WITH METERING PER UTILITY STANDARDS, SERVICE RACK AND ALL ASSOCIATED WIRE AND CONDUIT, COMPLETE IN PLACE	LS	1	\$53,000.00	\$53,000.00	\$50,375.00	\$50,375.00	\$46,000.00	\$46,000.00
22	80 KW DIESEL GENERATOR WITH SOUND ATTENUATED HOUSING, 72-HOUR SUBBASE FUEL TANK, 200A ATS, ALL ASSOCIATED WIRE, CONDUIT AND CONTROLS, CONCRETE PAD, COMPLETE IN PLACE	LS	1	\$50,000.00	\$50,000.00	\$46,135.00	\$46,135.00	\$50,000.00	\$50,000.00
23	LIFT STATION, SURGE PROTECTION, CONTROL PANEL WITH COMBINATION MOTOR STARTERS, PUMP CONTROLLER, AUTO DIALER, LIGHTING TRANSFORMER AND LIGHTING PANEL WITH ALL ASSOCIATED POWER / CONTROL CONDUIT AND WIRE, COMPLETE IN PLACE	LS	1	\$40,000.00	\$40,000.00	\$16,921.00	\$16,921.00	\$20,000.00	\$20,000.00
24	CITY OF MAGNOLIA INSPECTION FEE (2.5% OF TOTAL CONSTRUCTION COST), COMPLETE IN PLACE	LS	1	\$13,997.50	\$13,997.50	\$13,813.78	\$13,813.78	\$15,858.00	\$15,858.00
25	FULL CONSTRUCTION STAKING FOR ESCONDIDO LIFT STATION, COORDINATE WITH GBI SURVEY, KYLE B. DUCKETT, 281.499.4539, COMPLETE IN PLACE	LS	1	\$3,600.00	\$3,600.00	\$3,600.00	\$3,600.00	\$3,600.00	\$3,600.00
SANITARY LIFT STATION ITEMS SUBTOTAL:					\$557,835.50		\$566,364.98		\$625,810.00
MISCELLANEOUS ITEMS									
1	DEWATERING FOR STRUCTURE, AS REQUIRED BY SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1.00	\$1.00	\$1,690.00	\$1,690.00	\$1,000.00	\$1,000.00
2	DEWATERING OF LINE WORK (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	96	\$25.00	\$2,400.00	\$25.00	\$2,400.00	\$25.00	\$2,400.00
3	EXTRA CEMENT STABILIZED SAND, (1.5 SACKS OF CEMENT PER CUBIC YARD CEMENT STABILIZED SAND), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	20	\$12.00	\$240.00	\$12.00	\$240.00	\$12.00	\$240.00
4	EXTRA 4,000 PSI CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	5	\$300.00	\$1,500.00	\$300.00	\$1,500.00	\$300.00	\$1,500.00
5	CONTROL OF SURFACE WATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1.00	\$1.00	\$215.00	\$215.00	\$1,000.00	\$1,000.00
6	EXTRA COST OF UTILITY WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	96	\$20.00	\$1,920.00	\$1.00	\$96.00	\$25.00	\$2,400.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$6,062.00		\$6,141.00		\$8,540.00
BIDDING SUMMARY									
SUBTOTAL SANITARY LIFT STATION ITEMS					\$557,835.50		\$566,364.98		\$625,810.00
SUBTOTAL MISCELLANEOUS ITEMS					\$6,062.00		\$6,141.00		\$8,540.00
TOTAL AMOUNT BASE BID					\$563,897.50		\$572,505.98		\$634,350.00

BID TABULATION FOR:

CONSTRUCTION OF THE ESCONDIDO LIFT STATION NO. 1
 TO SERVE MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS
 NOVEMBER 12, 2020
 LJA ENGINEERING, INC.
 D. FORREST
 NOVEMBER 12, 2020
 2139-3009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	4) PRINCIPAL PLANT SERVICES		5) AR TURNKEE	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SANITARY LIFT STATION ITEMS							
1	SITE WORK, INCLUDING BUT NOT LIMITED TO SITE GRADING, BROADCAST SEEDING, SITE DRAINAGE, COMPLETE IN PLACE	LS	1	\$90,986.00	\$90,986.00	\$65,000.00	\$65,000.00
2	8" CONCRETE WET WELL AND VALVE PAD, INCLUDING ACCESS HATCHES, VENT, AND ALL APPURTENANCES AS SHOWN ON PLANS, COMPLETE IN PLACE	LS	1	\$321,260.00	\$321,260.00	\$164,000.00	\$164,000.00
3	15 HP SUBMERSIBLE PUMP WITH MINIMUM EFFICIENCY OF 58 AT 306 GPM AND 65' T.D.H., INCLUDING DISCHARGE ELBOW, GUIDE RAILS, AND ALL APPURTENANCES FOR PROPOSED PUMPS, COMPLETE IN PLACE	EA	2	\$33,820.00	\$67,640.00	\$138,000.00	\$276,000.00
4	SANITARY LIFT STATION AND VALVE PAD PIPING, INCLUDING PIPE, VALVES, FITTINGS, SUPPORTS, AND ALL APPURTENANCES, COMPLETE IN PLACE	LS	1	\$38,024.00	\$38,024.00	\$105,000.00	\$105,000.00
5	18" AWWA C-905 DR 18, SEWER PIPE, ALL DEPTHS, INCLUDING EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	28	\$1,250.00	\$35,000.00	\$211.00	\$5,908.00
6	8" AWWA C900, FORCE MAIN, DR 18, ALL DEPTHS, INCLUDING FITTINGS, EXCAVATION, BACKFILL AND BEDDING, COMPLETE IN PLACE	LF	68	\$117.00	\$7,956.00	\$85.00	\$5,780.00
7	STANDARD SANITARY MANHOLE ALL DEPTHS, INCLUDES EXCAVATION, BEDDING, BACKFILL, COMPLETE IN PLACE	EA	1	\$7,900.00	\$7,900.00	\$9,000.00	\$9,000.00
8	6" REINFORCED CONCRETE PAVEMENT WITH 8" LIME OR CEMENT STABILIZED SUBGRADE EXTENDING 1' OUTSIDE PAVEMENT, COMPLETE IN PLACE	SY	283	\$115.00	\$32,545.00	\$125.00	\$35,375.00
9	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	96	\$1.00	\$96.00	\$10.00	\$960.00
10	8" WOOD FENCE, WITH 16 FOOT DOUBLE SWING WOOD GATE, AND ALL APPURTENANCES, (AS SHOWN ON PLANS), COMPLETE IN PLACE	LF	250	\$93.50	\$23,375.00	\$88.00	\$22,000.00
11	1" SCH. 40 P.V.C. WATER LINE, COMPLETE IN PLACE	LF	33	\$5.00	\$165.00	\$50.00	\$1,650.00
12	PROVIDE AND INSTALL REDUCED PRESSURE BACKFLOW PREVENTER, NON-FREEZE HOSE BIB, ALL NECESSARY APPURTENANCES, COMPLETE IN PLACE	LS	1	\$2,930.00	\$2,930.00	\$5,300.00	\$5,300.00
13	4" PIPE BOLLARD, COMPLETE IN PLACE	EA	8	\$650.00	\$5,200.00	\$800.00	\$6,400.00
14	6" CRUSHED CONCRETE WITH GEOFABRIC (TENSAR TRIAX TX140 OR APPROVED EQUAL), COMPLETE IN PLACE	SY	242	\$45.00	\$10,890.00	\$50.00	\$12,100.00
15	ALLOWANCE FOR ESTABLISHED ELECTRICAL SERVICE AS DIRECTED BY ENTERGY, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER). CHARGES FROM ENTERGY SHALL BE PAID BY THE CONTRACTOR. THE AMOUNTS PAID, SUPPORTED BY INVOICES, SHALL BE INCLUDED IN PAY REQUESTS FOR REIMBURSEMENT WITHOUT A GENERAL CONTRACTOR MARKUP, COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
16	CORE INTO EXISTING MANHOLE AND CONNECT PROPOSED 18" SANITARY SEWER LINE TO SANITARY SEWER (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$1,500.00	\$1,500.00	\$2,050.00	\$2,050.00
17	CONNECT PROPOSED 8" FORCE MAIN TO PROPOSED FORCE MAIN (BY OTHERS), INCLUDE ALL NECESSARY ADAPTORS AND CONNECTORS OR STUB OUT AND PLUG, COMPLETE IN PLACE	EA	1	\$650.00	\$650.00	\$1,400.00	\$1,400.00
18	STORM WATER POLLUTION PREVENTION PLAN, INCLUDING ADMINISTRATION, MAINTENANCE, AND REMOVAL AS REQUIRED BY THE PLANS AND AS DIRECTED BY THE ENGINEER, (TO BE MAINTAINED UNTIL CONTRACTOR'S NOTICE OF TERMINATION IS SUBMITTED), COMPLETE IN PLACE	LS	1	\$2,500.00	\$2,500.00	\$3,000.00	\$3,000.00

BID TABULATION FOR:

CONSTRUCTION OF THE ESCONDIDO LIFT STATION NO. 1
 TO SERVE MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174
 CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS
 NOVEMBER 12, 2020
 LJA ENGINEERING, INC.
 D. FORREST
 NOVEMBER 12, 2020
 2139-3009 (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

ITEM	DESCRIPTION	UNIT	QTY	4) PRINCIPAL PLANT SERVICES		5) AR TURNKEE	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
19	FILTER FABRIC FENCE, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	255	\$3.00	\$765.00	\$3.00	\$765.00
20	INSTALLATION, MAINTENANCE AND REMOVAL OF CONCRETE TRUCK WASHOUT, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00	\$500.00	\$500.00
21	200A 480V SERVICE WITH METERING PER UTILITY STANDARDS, SERVICE RACK AND ALL ASSOCIATED WIRE AND CONDUIT, COMPLETE IN PLACE	LS	1	\$32,250.00	\$32,250.00	\$39,000.00	\$39,000.00
22	80 KW DIESEL GENERATOR WITH SOUND ATTENUATED HOUSING, 72-HOUR SUBBASE FUEL TANK, 200A ATS, ALL ASSOCIATED WIRE, CONDUIT AND CONTROLS, CONCRETE PAD, COMPLETE IN PLACE	LS	1	\$41,285.00	\$41,285.00	\$47,000.00	\$47,000.00
23	LIFT STATION, SURGE PROTECTION, CONTROL PANEL WITH COMBINATION MOTOR STARTERS, PUMP CONTROLLER, AUTO DIALER, LIGHTING TRANSFORMER AND LIGHTING PANEL WITH ALL ASSOCIATED POWER / CONTROL CONDUIT AND WIRE, COMPLETE IN PLACE	LS	1	\$15,000.00	\$15,000.00	\$35,400.00	\$35,400.00
24	CITY OF MAGNOLIA INSPECTION FEE (2.5% OF TOTAL CONSTRUCTION COST), COMPLETE IN PLACE	LS	1	\$19,500.00	\$19,500.00	\$23,000.00	\$23,000.00
25	FULL CONSTRUCTION STAKING FOR ESCONDIDO LIFT STATION, COORDINATE WITH GBI SURVEY, KYLE B. DUCKETT, 281.499.4539, COMPLETE IN PLACE	LS	1	\$3,600.00	\$3,600.00	\$3,600.00	\$3,600.00
SANITARY LIFT STATION ITEMS SUBTOTAL:					\$782,517.00		\$890,188.00
MISCELLANEOUS ITEMS							
1	DEWATERING FOR STRUCTURE, AS REQUIRED BY SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$5,000.00	\$5,000.00
2	DEWATERING OF LINE WORK (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	96	\$30.00	\$2,880.00	\$25.00	\$2,400.00
3	EXTRA CEMENT STABILIZED SAND, (1.5 SACKS OF CEMENT PER CUBIC YARD CEMENT STABILIZED SAND), (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	20	\$40.00	\$800.00	\$12.00	\$240.00
4	EXTRA 4,000 PSI CONCRETE WITH REINFORCING STEEL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	5	\$300.00	\$1,500.00	\$300.00	\$1,500.00
5	CONTROL OF SURFACE WATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$3,000.00	\$3,000.00
6	EXTRA COST OF UTILITY WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	96	\$40.00	\$3,840.00	\$15.00	\$1,440.00
MISCELLANEOUS ITEMS SUBTOTAL:					\$11,020.00		\$13,580.00
BIDDING SUMMARY							
SUBTOTAL SANITARY LIFT STATION ITEMS					\$782,517.00		\$890,188.00
SUBTOTAL MISCELLANEOUS ITEMS					\$11,020.00		\$13,580.00
TOTAL AMOUNT BASE BID					\$793,537.00		\$903,768.00