

**BID TABULATION FOR:**

CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)

**BID OPENING DATE:**


**BID OPENING LOCATION:**

**TABULATION BY:**

**TABULATION DATE:**

**LJA JOB NO.**

BIDDER NAME	BASE BID	PROPOSED DURATION (DAYS)
1) SUBTERRA SERVICES ENTERPRISES, LLC	\$895,000.00	25 \ 30
2) TEXASITE, LLC	\$913,965.00	30 \ 40
3) CROSTEX CONSTRUCTION INC.	\$940,000.00	45 \ 55
4) KENNETH LAMB CONSTRUCTION CO.,LTD.	\$969,433.00	30 \ 40
5) R CONSTRUCTION CIVIL, LLC	\$983,191.00	35 \ 40
6) BLAZEY CONSTRUCTION SERVICES LLC	\$1,026,491.18	45 \ 55
7) CE BARKER LTD.	\$1,275,777.34	60 \ 75



2/18/2025

I, Louis A. Mui, PE, hereby certify these bid tabulations to be true and correct.

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) SUBTERRA SERVICES ENTERPRISES, LLC		2) TEXASITE, LLC		3) CROSTEX CONSTRUCTION INC.		4) KENNETH LAMB CONSTRUCTION CO.,LTD.		
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	
<b>WATER ITEMS - SECTION 8</b>												
1.	8" PVC WATER LINE PIPE, C-900, DR 18, CL 235, ALL DEPTHS, TO INCLUDE FITTINGS, BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	3145	\$37.00	\$116,365.00	\$34.00	\$106,930.00	\$35.00	\$110,075.00	\$39.00	\$122,655.00	
2.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	3145	\$0.01	\$31.45	\$1.00	\$3,145.00	\$0.05	\$157.25	\$2.00	\$6,290.00	
3.	FIRE HYDRANT UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE, 6" GATE VALVE & BOX, 6" LEAD AND FIRE HYDRANT, TRENCH SAFETY, COMPLETE IN PLACE	EA	5	\$6,000.00	\$30,000.00	\$6,293.00	\$31,465.00	\$7,300.00	\$36,500.00	\$6,953.00	\$34,765.00	
4.	8" AWWA GATE VALVE AND BOX AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	6	\$1,800.00	\$10,800.00	\$1,960.00	\$11,760.00	\$1,875.00	\$11,250.00	\$2,212.00	\$13,272.00	
5.	REMOVE AND DISPOSE OF 8" PLUG AND CLAMP & BLOW-OFF VALVE AND CONNECT PROPOSED 8" WATER LINE, COMPLETE IN PLACE	EA	5	\$500.00	\$2,500.00	\$1,464.00	\$7,320.00	\$1,000.00	\$5,000.00	\$756.00	\$3,780.00	
6.	SHORT SIDE SINGLE OR DOUBLE SERVICE, 1"(CTS POLYETHYLENE, SDR-9) WATER SERVICE, INCLUDES TRENCH SAFETY, CURB STOP, MARKER AND ALL NECESSARY CONNECTORS, PLUGS AND TAPS, COMPLETE IN PLACE	EA	22	\$1,000.00	\$22,000.00	\$803.00	\$17,666.00	\$970.00	\$21,340.00	\$1,096.00	\$24,112.00	
7.	LONG SIDE SINGLE OR DOUBLE SERVICE, 1"(CTS POLYETHYLENE, SDR-9) WATER SERVICE, INCLUDES TRENCH SAFETY, CURB STOP, MARKER AND ALL NECESSARY CONNECTORS, PLUGS AND TAPS, COMPLETE IN PLACE	EA	32	\$1,700.00	\$54,400.00	\$1,623.00	\$51,936.00	\$1,610.00	\$51,520.00	\$2,195.00	\$70,240.00	
8.	ADDITIONAL CAST IRON FITTINGS, COMPLETE IN PLACE	TON	1	\$250.00	\$250.00	\$1.00	\$1.00	\$1.00	\$1.00	\$1.00	\$1.00	
9.	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN 1 MILE OF ESCONDIDO OVERALL DEVELOPMENT LIMITS), COMPLETE IN PLACE	CY	865	\$1.00	\$865.00	\$4.00	\$3,460.00	\$6.00	\$5,190.00	\$2.00	\$1,730.00	
10.	METER BOX (DFW PLASTICS, INC., MODEL NO. DFW 1300.12.IT), OR APPROVED EQUAL, COMPLETE IN PLACE	EA	100	\$50.00	\$5,000.00	\$58.00	\$5,800.00	\$40.00	\$4,000.00	\$76.00	\$7,600.00	
<b>SUBTOTAL WATER ITEMS - SECTION 8</b>					<b>\$242,211.45</b>		<b>\$239,483.00</b>		<b>\$245,033.25</b>		<b>\$284,445.00</b>	
<b>SANITARY SEWER SYSTEM ITEMS - SECTION 8</b>												
1.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 0'-12' CUT, TO INCLUDE BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	3185	\$45.00	\$143,325.00	\$42.00	\$133,770.00	\$38.00	\$121,030.00	\$39.00	\$124,215.00	
2.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	3185	\$0.01	\$31.85	\$1.00	\$3,185.00	\$0.10	\$318.50	\$2.00	\$6,370.00	
3.	STANDARD 4' DIAMETER SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES PLASTIC INFLOW PROTECTORS, PROTECTIVE INTERIOR COATING (XYPEX ADMIX C-1000R, OR APPROVED EQUAL) AND ADJUSTMENTS, COMPLETE IN PLACE	EA	25	\$3,200.00	\$80,000.00	\$4,047.00	\$101,175.00	\$4,100.00	\$102,500.00	\$3,875.00	\$96,875.00	
4.	EXTRA DEPTH OF 4' DIAMETER STANDARD SANITARY SEWER MANHOLE, (OVER 8' DEPTH), COMPLETE IN PLACE	VF	16	\$250.00	\$4,000.00	\$330.00	\$5,280.00	\$390.00	\$6,240.00	\$375.00	\$6,000.00	
5.	STANDARD SANITARY SEWER MANHOLE EXTERNAL DROP STRUCTURE, ALL DEPTHS, COMPLETE IN PLACE	EA	4	\$800.00	\$3,200.00	\$817.00	\$3,268.00	\$1,350.00	\$5,400.00	\$1,097.00	\$4,388.00	
6.	EXTRA DEPTH STANDARD SANITARY SEWER MANHOLE DROP STRUCTURE (OVER 2.0'), COMPLETE IN PLACE	VF	5	\$40.00	\$200.00	\$35.00	\$175.00	\$40.00	\$200.00	\$113.00	\$565.00	

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) SUBTERRA SERVICES ENTERPRISES, LLC		2) TEXASITE, LLC		3) CROSTEX CONSTRUCTION INC.		4) KENNETH LAMB CONSTRUCTION CO.,LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
7.	STANDARD SANITARY SEWER STACKS, ALL DEPTHS, COMPLETE IN PLACE	EA	23	\$700.00	\$16,100.00	\$634.00	\$14,582.00	\$400.00	\$9,200.00	\$764.00	\$17,572.00
8.	SHORT SIDE SINGLE OR DOUBLE 6" GREEN PVC PIPE SERVICE LEADS, ASTM D-2241, SDR 26, ALL DEPTHS, INCLUDING CEMENT STABILIZED SAND BACKFILL, RISER/STACK, WYE, PLUG, MARKER, MANHOLE DROPS, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	32	\$1,800.00	\$57,600.00	\$1,517.00	\$48,544.00	\$2,345.00	\$75,040.00	\$1,713.00	\$54,816.00
9.	LONG SIDE SINGLE OR DOUBLE 6" GREEN PVC PIPE SERVICE LEADS, ASTM D-2241, SDR 26, ALL DEPTHS, INCLUDING CEMENT STABILIZED SAND BACKFILL, RISER/STACK, WYE, PLUG, MARKER, MANHOLE DROPS, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	LF	1265	\$57.00	\$72,105.00	\$54.00	\$68,310.00	\$59.00	\$74,635.00	\$58.00	\$73,370.00
10.	REMOVE EXISTING 8" SANITARY SEWER PLUG AND CONNECT PROPOSED 8" SANITARY SEWER, COMPLETE IN PLACE	EA	4	\$100.00	\$400.00	\$666.00	\$2,664.00	\$1,000.00	\$4,000.00	\$300.00	\$1,200.00
11.	DEWATERING (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	110	\$20.00	\$2,200.00	\$20.00	\$2,200.00	\$20.00	\$2,200.00	\$20.00	\$2,200.00
12.	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN 1 MILE OF ESCONDIDO OVERALL DEVELOPMENT LIMITS), COMPLETE IN PLACE	CY	1180	\$1.00	\$1,180.00	\$4.00	\$4,720.00	\$6.00	\$7,080.00	\$2.00	\$2,360.00
13.	ADDITIONAL COST FOR WATER AND SANITARY SEWER CROSSINGS, ALL DEPTHS, INCLUDES UPGRADE TO 20' SECTION FOR RESTRAINED JOINT AWWA C900 DR 18 PIPE FOR BOTH WATER AND SANITARY SEWER LINES WHERE APPLICABLE AND RESTRAINED JOINT FITTINGS, COMPLETE IN PLACE	EA	2	\$500.00	\$1,000.00	\$1,012.00	\$2,024.00	\$1,000.00	\$2,000.00	\$100.00	\$200.00
14.	ADDITIONAL COST FOR SANITARY SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	550	\$15.00	\$8,250.00	\$15.00	\$8,250.00	\$15.00	\$8,250.00	\$15.00	\$8,250.00
15.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00
<b>SUBTOTAL SANITARY SEWER SYSTEM ITEMS - SECTION 8</b>					<b>\$394,591.85</b>		<b>\$403,147.00</b>		<b>\$423,093.50</b>		<b>\$403,381.00</b>
<b>DRAINAGE FACILITIES ITEMS - SECTION 8</b>											
1.	18" RCP STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, TO INCLUDE BEDDING AND BACKFILL AND CEMENT STABILIZED SAND BACKFILL UNDER AND WITHIN 1' OF PAVING, COMPLETE IN PLACE	LF	224	\$79.00	\$17,696.00	\$74.00	\$16,576.00	\$75.00	\$16,800.00	\$67.00	\$15,008.00
2.	24" RCP STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, TO INCLUDE BEDDING AND BACKFILL AND CEMENT STABILIZED SAND BACKFILL UNDER AND WITHIN 1' OF PAVING, COMPLETE IN PLACE	LF	775	\$93.00	\$72,075.00	\$87.00	\$67,425.00	\$89.00	\$68,975.00	\$89.00	\$68,975.00
3.	30" RCP STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, TO INCLUDE BEDDING AND BACKFILL AND CEMENT STABILIZED SAND BACKFILL UNDER AND WITHIN 1' OF PAVING, COMPLETE IN PLACE	LF	105	\$118.00	\$12,390.00	\$114.00	\$11,970.00	\$112.00	\$11,760.00	\$151.00	\$15,855.00
4.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	1104	\$0.01	\$11.04	\$1.00	\$1,104.00	\$0.05	\$55.20	\$2.00	\$2,208.00
5.	TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, INCLUDES FINAL GRADE ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	6	\$2,700.00	\$16,200.00	\$3,876.00	\$23,256.00	\$3,950.00	\$23,700.00	\$4,312.00	\$25,872.00

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) SUBTERRA SERVICES ENTERPRISES, LLC		2) TEXASITE, LLC		3) CROSTEX CONSTRUCTION INC.		4) KENNETH LAMB CONSTRUCTION CO.,LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
6.	STAGE I – REINFORCED CONCRETE TYPE “C” INLET, 5’ OPENING, ALL DEPTHS, INCLUDES TEMPORARY INLET PROTECTION BARRIER FOR STAGE I INLETS, COMPLETE IN PLACE	EA	9	\$2,100.00	\$18,900.00	\$1,824.00	\$16,416.00	\$2,500.00	\$22,500.00	\$1,850.00	\$16,650.00
7.	STAGE II – REINFORCED CONCRETE TYPE “C” INLET, 5’ OPENING, COMPLETE IN PLACE	EA	9	\$2,600.00	\$23,400.00	\$2,052.00	\$18,468.00	\$1,625.00	\$14,625.00	\$2,510.00	\$22,590.00
8.	DEWATERING (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	500	\$20.00	\$10,000.00	\$20.00	\$10,000.00	\$20.00	\$10,000.00	\$20.00	\$10,000.00
9.	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN 1 MILE OF ESCONDIDO OVERALL DEVELOPMENT LIMITS), COMPLETE IN PLACE	CY	920	\$1.00	\$920.00	\$4.00	\$3,680.00	\$6.00	\$5,520.00	\$2.00	\$1,840.00
10.	ADDITIONAL COST FOR STORM SEWER BEDDING AND BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS, ALL SIZES & DEPTHS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	300	\$15.00	\$4,500.00	\$15.00	\$4,500.00	\$15.00	\$4,500.00	\$15.00	\$4,500.00
11.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00
12.	REMOVE AND DISPOSE OF EXISTING 8” BRICK PLUG AND CONNECT PROPOSED STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$250.00	\$250.00	\$666.00	\$666.00	\$1,000.00	\$1,000.00	\$300.00	\$300.00
13.	DRAINAGE SWALE, “V” BOTTOM, INCLUDES EXCAVATION, HAULING AND GRADING, COMPLETE IN PLACE	LF	153	\$10.00	\$1,530.00	\$8.00	\$1,224.00	\$3.50	\$535.50	\$10.00	\$1,530.00
14.	RE-ESTABLISH DRAINAGE SWALE, “V” BOTTOM, INCLUDES EXCAVATION, HAULING AND GRADING, COMPLETE IN PLACE	LF	567	\$5.00	\$2,835.00	\$11.00	\$6,237.00	\$3.50	\$1,984.50	\$7.00	\$3,969.00
15.	REMOVE EXISTING REINFORCED CONCRETE TYPE “E” INLET TOP AND REPLACE WITH TYPE “C” STORM MH TOP, FOR 42” STORM SEWER AND SMALLER, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$3,990.00	\$3,990.00	\$2,000.00	\$2,000.00	\$1,500.00	\$1,500.00
16.	BREAK INTO EXISTING 10” TYPE C-1” INLET AND CONNECT PROPOSED STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$912.00	\$912.00	\$2,750.00	\$2,750.00	\$800.00	\$800.00
17.	4” CONCRETE LINED DRAINAGE SWALE WITH 2’ TOE WALLS ALL AROUND, “V” BOTTOM, INCLUDES EXCAVATION, HAULING AND GRADING, COMPLETE IN PLACE	SY	174	\$120.00	\$20,880.00	\$142.00	\$24,708.00	\$125.00	\$21,750.00	\$175.00	\$30,450.00
18.	4” REINFORCED CONCRETE SLOPE PAVEMENT WITH 2’ TOE WALLS ALL AROUND, COMPLETE IN PLACE	SY	51	\$120.00	\$6,120.00	\$136.00	\$6,936.00	\$125.00	\$6,375.00	\$175.00	\$8,925.00
19.	STAGE II-REINFORCED CONCRETE TYPE “C-1” INLET, 10’ OPENING, COMPLETE IN PLACE	EA	1	\$2,574.66	\$2,574.66	\$2,850.00	\$2,850.00	\$4,000.00	\$4,000.00	\$3,785.00	\$3,785.00
<b>SUBTOTAL DRAINAGE FACILITIES ITEMS - SECTION 8</b>					<b>\$216,781.70</b>		<b>\$225,918.00</b>		<b>\$223,830.20</b>		<b>\$239,757.00</b>
<b>MISCELLANEOUS ITEMS</b>											
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) SUBTERRA SERVICES ENTERPRISES, LLC		2) TEXASITE, LLC		3) CROSTEX CONSTRUCTION INC.		4) KENNETH LAMB CONSTRUCTION CO.,LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	FULL CONSTRUCTION STAKING FOR SECTION 8 WS&D ITEMS, COORDINATE WITH GBI PARTNERS, LLC., KYLE DUCKETT, 281.499.4539, COMPLETE IN PLACE	LS	1	\$18,010.00	\$18,010.00	\$18,010.00	\$18,010.00	\$29,250.00	\$29,250.00	\$18,010.00	\$18,010.00
4.	AS-BUILT SURVEY FOR ALL LOT CORNERS, BUILDING LINE, BACK OF PAD AND BACK OF LOT, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH GBI PARTNERS, LLC, KYLE DUCKETT, 281.499.4539, COMPLETE IN PLACE	LS	1	\$7,500.00	\$7,500.00	\$7,500.00	\$7,500.00	\$8,500.00	\$8,500.00	\$7,500.00	\$7,500.00
5.	ADDITIONAL DUCTILE IRON FITTINGS (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$250.00	\$250.00	\$1.00	\$1.00	\$1.00	\$1.00	\$1.00	\$1.00
6.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	100	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00
7.	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$1,368.00	\$1,368.00	\$1,750.00	\$1,750.00	\$150.00	\$150.00
8.	STORMWATER POLLUTION PREVENTION PLAN COMPLIANCE, INSPECTIONS, MAINTENANCE OF ENTRANCE AND FENCE, NOI, NOT, ALL ITEMS NOT SPECIFICALLY LISTED ABOVE, COMPLETE IN PLACE	LS	1	\$1,000.00	\$1,000.00	\$1,710.00	\$1,710.00	\$3,075.05	\$3,075.05	\$2,000.00	\$2,000.00
9.	STABILIZED CONSTRUCTION EXIT, INSTALLATION, MAINTENANCE AND REMOVAL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$2,508.00	\$2,508.00	\$1.00	\$1.00	\$1,500.00	\$1,500.00
10.	REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), SWMHCA SPECIFICATION NO. 4311, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	4660	\$1.75	\$8,155.00	\$2.00	\$9,320.00	\$0.10	\$466.00	\$1.65	\$7,689.00
<b>SUBTOTAL MISCELLANEOUS ITEMS</b>					<b>\$41,415.00</b>		<b>\$45,417.00</b>		<b>\$48,043.05</b>		<b>\$41,850.00</b>
<b>BID SUMMARY</b>											
WATER ITEMS - SECTION 8					\$242,211.45		\$239,483.00		\$245,033.25		\$284,445.00
SANITARY SEWER SYSTEM ITEMS - SECTION 8					\$394,591.85		\$403,147.00		\$423,093.50		\$403,381.00
DRAINAGE FACILITIES ITEMS - SECTION 8					\$216,781.70		\$225,918.00		\$223,830.20		\$239,757.00
MISCELLANEOUS ITEMS					\$41,415.00		\$45,417.00		\$48,043.05		\$41,850.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$895,000.00</b>		<b>\$913,965.00</b>		<b>\$940,000.00</b>		<b>\$969,433.00</b>

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	5) R CONSTRUCTION CIVIL, LLC		6) BLAZEY CONSTRUCTION SERVICES LLC		7) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
<b>WATER ITEMS - SECTION 8</b>									
1.	8" PVC WATER LINE PIPE, C-900, DR 18, CL 235, ALL DEPTHS, TO INCLUDE FITTINGS, BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	3145	\$37.00	\$116,365.00	\$36.00	\$113,220.00	\$35.00	\$110,075.00
2.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	3145	\$1.00	\$3,145.00	\$0.12	\$377.40	\$0.01	\$31.45
3.	FIRE HYDRANT UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE, 6" GATE VALVE & BOX, 6" LEAD AND FIRE HYDRANT, TRENCH SAFETY, COMPLETE IN PLACE	EA	5	\$7,050.00	\$35,250.00	\$9,100.00	\$45,500.00	\$6,700.00	\$33,500.00
4.	8" AWWA GATE VALVE AND BOX AND ADJUSTMENTS AS NECESSARY, COMPLETE IN PLACE	EA	6	\$2,250.00	\$13,500.00	\$2,020.00	\$12,120.00	\$2,000.00	\$12,000.00
5.	REMOVE AND DISPOSE OF 8" PLUG AND CLAMP & BLOW-OFF VALVE AND CONNECT PROPOSED 8" WATER LINE, COMPLETE IN PLACE	EA	5	\$400.00	\$2,000.00	\$560.00	\$2,800.00	\$1,600.00	\$8,000.00
6.	SHORT SIDE SINGLE OR DOUBLE SERVICE, 1"(CTS POLYETHYLENE, SDR-9) WATER SERVICE, INCLUDES TRENCH SAFETY, CURB STOP, MARKER AND ALL NECESSARY CONNECTORS, PLUGS AND TAPS, COMPLETE IN PLACE	EA	22	\$900.00	\$19,800.00	\$1,100.00	\$24,200.00	\$800.00	\$17,600.00
7.	LONG SIDE SINGLE OR DOUBLE SERVICE, 1"(CTS POLYETHYLENE, SDR-9) WATER SERVICE, INCLUDES TRENCH SAFETY, CURB STOP, MARKER AND ALL NECESSARY CONNECTORS, PLUGS AND TAPS, COMPLETE IN PLACE	EA	32	\$1,700.00	\$54,400.00	\$1,750.00	\$56,000.00	\$925.00	\$29,600.00
8.	ADDITIONAL CAST IRON FITTINGS, COMPLETE IN PLACE	TON	1	\$1,200.00	\$1,200.00	\$2,000.00	\$2,000.00	\$500.00	\$500.00
9.	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN 1 MILE OF ESCONDIDO OVERALL DEVELOPMENT LIMITS), COMPLETE IN PLACE	CY	865	\$6.00	\$5,190.00	\$6.00	\$5,190.00	\$1.00	\$865.00
10.	METER BOX (DFW PLASTICS, INC., MODEL NO. DFW 1300.12.IT), OR APPROVED EQUAL, COMPLETE IN PLACE	EA	100	\$30.00	\$3,000.00	\$160.00	\$16,000.00	\$50.00	\$5,000.00
<b>SUBTOTAL WATER ITEMS - SECTION 8</b>					<b>\$253,850.00</b>		<b>\$277,407.40</b>		<b>\$217,171.45</b>
<b>SANITARY SEWER SYSTEM ITEMS - SECTION 8</b>									
1.	8" PVC SEWER PIPE, ASTM D-2241, SDR 26, 0'-12' CUT, TO INCLUDE BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	3185	\$47.00	\$149,695.00	\$49.00	\$156,065.00	\$80.00	\$254,800.00
2.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	3185	\$1.00	\$3,185.00	\$0.12	\$382.20	\$0.01	\$31.85
3.	STANDARD 4' DIAMETER SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES PLASTIC INFLOW PROTECTORS, PROTECTIVE INTERIOR COATING (XYPEX ADMIX C-1000R, OR APPROVED EQUAL) AND ADJUSTMENTS, COMPLETE IN PLACE	EA	25	\$4,400.00	\$110,000.00	\$4,200.00	\$105,000.00	\$4,000.00	\$100,000.00
4.	EXTRA DEPTH OF 4' DIAMETER STANDARD SANITARY SEWER MANHOLE, (OVER 8' DEPTH), COMPLETE IN PLACE	VF	16	\$400.00	\$6,400.00	\$270.00	\$4,320.00	\$400.00	\$6,400.00
5.	STANDARD SANITARY SEWER MANHOLE EXTERNAL DROP STRUCTURE, ALL DEPTHS, COMPLETE IN PLACE	EA	4	\$700.00	\$2,800.00	\$1,100.00	\$4,400.00	\$1,600.00	\$6,400.00
6.	EXTRA DEPTH STANDARD SANITARY SEWER MANHOLE DROP STRUCTURE (OVER 2.0'), COMPLETE IN PLACE	VF	5	\$40.00	\$200.00	\$62.00	\$310.00	\$75.00	\$375.00

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:**

**BID OPENING LOCATION:**

**TABULATION BY:**

**TABULATION DATE:**

**LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	5) R CONSTRUCTION CIVIL, LLC		6) BLAZEY CONSTRUCTION SERVICES LLC		7) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
7.	STANDARD SANITARY SEWER STACKS, ALL DEPTHS, COMPLETE IN PLACE	EA	23	\$1,000.00	\$23,000.00	\$750.00	\$17,250.00	\$1,600.00	\$36,800.00
8.	SHORT SIDE SINGLE OR DOUBLE 6" GREEN PVC PIPE SERVICE LEADS, ASTM D-2241, SDR 26, ALL DEPTHS, INCLUDING CEMENT STABILIZED SAND BACKFILL, RISER/STACK, WYE, PLUG, MARKER, MANHOLE DROPS, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	EA	32	\$1,900.00	\$60,800.00	\$2,320.00	\$74,240.00	\$3,000.00	\$96,000.00
9.	LONG SIDE SINGLE OR DOUBLE 6" GREEN PVC PIPE SERVICE LEADS, ASTM D-2241, SDR 26, ALL DEPTHS, INCLUDING CEMENT STABILIZED SAND BACKFILL, RISER/STACK, WYE, PLUG, MARKER, MANHOLE DROPS, AND ANY NECESSARY FITTINGS, ETC., COMPLETE IN PLACE	LF	1265	\$53.00	\$67,045.00	\$70.00	\$88,550.00	\$140.00	\$177,100.00
10.	REMOVE EXISTING 8" SANITARY SEWER PLUG AND CONNECT PROPOSED 8" SANITARY SEWER, COMPLETE IN PLACE	EA	4	\$200.00	\$800.00	\$320.00	\$1,280.00	\$1,800.00	\$7,200.00
11.	DEWATERING (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	110	\$21.00	\$2,310.00	\$30.00	\$3,300.00	\$20.00	\$2,200.00
12.	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN 1 MILE OF ESCONDIDO OVERALL DEVELOPMENT LIMITS), COMPLETE IN PLACE	CY	1180	\$6.00	\$7,080.00	\$6.00	\$7,080.00	\$1.00	\$1,180.00
13.	ADDITIONAL COST FOR WATER AND SANITARY SEWER CROSSINGS, ALL DEPTHS, INCLUDES UPGRADE TO 20' SECTION FOR RESTRAINED JOINT AWWA C900 DR 18 PIPE FOR BOTH WATER AND SANITARY SEWER LINES WHERE APPLICABLE AND RESTRAINED JOINT FITTINGS, COMPLETE IN PLACE	EA	2	\$900.00	\$1,800.00	\$2,860.00	\$5,720.00	\$1,750.00	\$3,500.00
14.	ADDITIONAL COST FOR SANITARY SEWER BEDDING & BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	550	\$15.00	\$8,250.00	\$15.00	\$8,250.00	\$15.00	\$8,250.00
15.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00
<b>SUBTOTAL SANITARY SEWER SYSTEM ITEMS - SECTION 8</b>					<b>\$448,365.00</b>		<b>\$481,147.20</b>		<b>\$705,236.85</b>
<b>DRAINAGE FACILITIES ITEMS - SECTION 8</b>									
1.	18" RCP STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, TO INCLUDE BEDDING AND BACKFILL AND CEMENT STABILIZED SAND BACKFILL UNDER AND WITHIN 1' OF PAVING, COMPLETE IN PLACE	LF	224	\$81.00	\$18,144.00	\$78.00	\$17,472.00	\$135.00	\$30,240.00
2.	24" RCP STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, TO INCLUDE BEDDING AND BACKFILL AND CEMENT STABILIZED SAND BACKFILL UNDER AND WITHIN 1' OF PAVING, COMPLETE IN PLACE	LF	775	\$100.00	\$77,500.00	\$89.00	\$68,975.00	\$160.00	\$124,000.00
3.	30" RCP STORM SEWER, ASTM C-76, CLASS III, ALL CUTS, TO INCLUDE BEDDING AND BACKFILL AND CEMENT STABILIZED SAND BACKFILL UNDER AND WITHIN 1' OF PAVING, COMPLETE IN PLACE	LF	105	\$142.00	\$14,910.00	\$125.00	\$13,125.00	\$220.00	\$23,100.00
4.	TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE	LF	1104	\$1.00	\$1,104.00	\$0.12	\$132.48	\$0.01	\$11.04
5.	TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, INCLUDES FINAL GRADE ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	6	\$3,100.00	\$18,600.00	\$3,200.00	\$19,200.00	\$3,700.00	\$22,200.00

**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	5) R CONSTRUCTION CIVIL, LLC		6) BLAZEY CONSTRUCTION SERVICES LLC		7) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
6.	STAGE I – REINFORCED CONCRETE TYPE “C” INLET, 5’ OPENING, ALL DEPTHS, INCLUDES TEMPORARY INLET PROTECTION BARRIER FOR STAGE I INLETS, COMPLETE IN PLACE	EA	9	\$1,700.00	\$15,300.00	\$1,860.00	\$16,740.00	\$2,000.00	\$18,000.00
7.	STAGE II – REINFORCED CONCRETE TYPE “C” INLET, 5’ OPENING, COMPLETE IN PLACE	EA	9	\$2,800.00	\$25,200.00	\$2,400.00	\$21,600.00	\$2,200.00	\$19,800.00
8.	DEWATERING (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	500	\$21.00	\$10,500.00	\$20.00	\$10,000.00	\$20.00	\$10,000.00
9.	UTILITY SPOIL TO BE HAULED, SPREAD AND COMPACTED TO 95% STANDARD PROCTOR DENSITY (WITHIN 1 MILE OF ESCONDIDO OVERALL DEVELOPMENT LIMITS), COMPLETE IN PLACE	CY	920	\$6.00	\$5,520.00	\$6.00	\$5,520.00	\$1.00	\$920.00
10.	ADDITIONAL COST FOR STORM SEWER BEDDING AND BACKFILL FOR UNSATISFACTORY SOIL CONDITIONS, ALL SIZES & DEPTHS, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	300	\$15.00	\$4,500.00	\$15.00	\$4,500.00	\$15.00	\$4,500.00
11.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	100	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00
12.	REMOVE AND DISPOSE OF EXISTING 8” BRICK PLUG AND CONNECT PROPOSED STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$700.00	\$700.00	\$420.00	\$420.00	\$1,000.00	\$1,000.00
13.	DRAINAGE SWALE, “V” BOTTOM, INCLUDES EXCAVATION, HAULING AND GRADING, COMPLETE IN PLACE	LF	153	\$6.00	\$918.00	\$6.00	\$918.00	\$10.00	\$1,530.00
14.	RE-ESTABLISH DRAINAGE SWALE, “V” BOTTOM, INCLUDES EXCAVATION, HAULING AND GRADING, COMPLETE IN PLACE	LF	567	\$5.00	\$2,835.00	\$8.30	\$4,706.10	\$10.00	\$5,670.00
15.	REMOVE EXISTING REINFORCED CONCRETE TYPE “E” INLET TOP AND REPLACE WITH TYPE “C” STORM MH TOP, FOR 42” STORM SEWER AND SMALLER, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$2,400.00	\$2,400.00	\$540.00	\$540.00	\$3,500.00	\$3,500.00
16.	BREAK INTO EXISTING 10’ “TYPE C-1” INLET AND CONNECT PROPOSED STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$700.00	\$700.00	\$720.00	\$720.00	\$1,500.00	\$1,500.00
17.	4” CONCRETE LINED DRAINAGE SWALE WITH 2’ TOE WALLS ALL AROUND, “V” BOTTOM, INCLUDES EXCAVATION, HAULING AND GRADING, COMPLETE IN PLACE	SY	174	\$130.00	\$22,620.00	\$115.00	\$20,010.00	\$160.00	\$27,840.00
18.	4” REINFORCED CONCRETE SLOPE PAVEMENT WITH 2’ TOE WALLS ALL AROUND, COMPLETE IN PLACE	SY	51	\$145.00	\$7,395.00	\$114.00	\$5,814.00	\$160.00	\$8,160.00
19.	STAGE II-REINFORCED CONCRETE TYPE “C-1” INLET, 10’ OPENING, COMPLETE IN PLACE	EA	1	\$3,100.00	\$3,100.00	\$2,800.00	\$2,800.00	\$4,000.00	\$4,000.00
<b>SUBTOTAL DRAINAGE FACILITIES ITEMS - SECTION 8</b>					<b>\$236,946.00</b>		<b>\$218,192.58</b>		<b>\$310,971.04</b>
<b>MISCELLANEOUS ITEMS</b>									
1.	STANDARD DEDUCT FOR VARIANCE REQUESTS SUBMITTED BY THE ENGINEER ON BEHALF OF THE CONTRACTOR, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	0	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00	-\$1,000.00	\$0.00



**BID TABULATION FOR:**

**CONSTRUCTION OF THE WATER, SANITARY SEWER, AND DRAINAGE FACILITIES TO SERVE ESCONDIDO SECTION 8  
MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 174  
CITY OF MAGNOLIA E.T.J., MONTGOMERY COUNTY, TEXAS  
FEBRUARY 18, 2025  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
FEBRUARY 18, 2025  
2139-3108D (9.2)**

**BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	5) R CONSTRUCTION CIVIL, LLC		6) BLAZEY CONSTRUCTION SERVICES LLC		7) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
2.	STANDARD DEDUCT FOR STREET CLEANING (AS DIRECTED BY THE OWNER), COMPLETE IN PLACE	HR	0	-\$125.00	\$0.00	-\$125.00	\$0.00	-\$125.00	\$0.00
3.	FULL CONSTRUCTION STAKING FOR SECTION 8 WS&D ITEMS, COORDINATE WITH GBI PARTNERS, LLC., KYLE DUCKETT, 281.499.4539, COMPLETE IN PLACE	LS	1	\$18,010.00	\$18,010.00	\$18,010.00	\$18,010.00	\$18,010.00	\$18,010.00
4.	AS-BUILT SURVEY FOR ALL LOT CORNERS, BUILDING LINE, BACK OF PAD AND BACK OF LOT, INCLUDES A CERTIFIED EXHIBIT AND AN AUTOCAD FILE OF SURVEY, COORDINATE WITH GBI PARTNERS, LLC, KYLE DUCKETT, 281.499.4539, COMPLETE IN PLACE	LS	1	\$7,500.00	\$7,500.00	\$7,500.00	\$7,500.00	\$7,500.00	\$7,500.00
5.	ADDITIONAL DUCTILE IRON FITTINGS (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	TON	1	\$1,000.00	\$1,000.00	\$1,800.00	\$1,800.00	\$500.00	\$500.00
6.	EXTRA CEMENT STABILIZED SAND (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	CY	100	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$50.00	\$5,000.00
7.	CONCRETE TRUCK WASHOUT PIT, TO INCLUDE INSTALLATION, MAINTENANCE AND REMOVAL, COMPLETE IN PLACE	EA	1	\$500.00	\$500.00	\$1,250.00	\$1,250.00	\$500.00	\$500.00
8.	STORMWATER POLLUTION PREVENTION PLAN COMPLIANCE, INSPECTIONS, MAINTENANCE OF ENTRANCE AND FENCE, NOI, NOT, ALL ITEMS NOT SPECIFICALLY LISTED ABOVE, COMPLETE IN PLACE	LS	1	\$1,300.00	\$1,300.00	\$2,600.00	\$2,600.00	\$500.00	\$500.00
9.	STABILIZED CONSTRUCTION EXIT, INSTALLATION, MAINTENANCE AND REMOVAL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	EA	1	\$1,400.00	\$1,400.00	\$2,400.00	\$2,400.00	\$2,000.00	\$2,000.00
10.	REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), SWMHCA SPECIFICATION NO. 4311, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	4660	\$2.00	\$9,320.00	\$2.40	\$11,184.00	\$1.80	\$8,388.00
<b>SUBTOTAL MISCELLANEOUS ITEMS</b>					<b>\$44,030.00</b>		<b>\$49,744.00</b>		<b>\$42,398.00</b>
<b>BID SUMMARY</b>									
WATER ITEMS - SECTION 8					\$253,850.00		\$277,407.40		\$217,171.45
SANITARY SEWER SYSTEM ITEMS - SECTION 8					\$448,365.00		\$481,147.20		\$705,236.85
DRAINAGE FACILITIES ITEMS - SECTION 8					\$236,946.00		\$218,192.58		\$310,971.04
MISCELLANEOUS ITEMS					\$44,030.00		\$49,744.00		\$42,398.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$983,191.00</b>		<b>\$1,026,491.18</b>		<b>\$1,275,777.34</b>