
BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

BIDDER NAME	BASE BID
1) HAYDEN PAVING, INC.	$1,046,818.00
2) DURWOOD GREENE CONSTRUCTION CO.	$1,049,129.75
3) FORDE CONSTRUCTION COMPANY	$1,075,060.25

CALENDAR DAYS 150 / 180



11/11/26

I, CLAYTON WEISHUHN, P.E., hereby certify these bid tabulations to be true and correct.

LJA, INC.

FRN F-1386
LJA, Inc.
O:\LAND\2636\0160A\11102026_FM 529 Turn Lane, Traffic Signalization & Driveway_BT

BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

				1) HAYDEN PAVING, INC.		2) DURWOOD GREENE CONSTRUCTION CO.		3) FORDE CONSTRUCTION COMPANY	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
FM 529 PAVING ITEMS									
1.	3.5" D-GR HMA TY-D SAC-B PG 70-22, PAVING WITH 8" FLEXIBLE BASE, FL BS (CMP IN PLC) (TYA GR1-2) (FINAL POS), AND PRIME COAT (MC-30), COMPLETE IN PLACE	SY	2403	$92.00	$221,076.00	$95.00	$228,285.00	$61.00	$146,583.00
2.	6" LIME STABILIZED SUBGRADE MANIPULATION, COMPLETE IN PLACE	SY	2851	$15.00	$42,765.00	$7.50	$21,382.50	$14.00	$39,914.00
3.	LIME FOR 6" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT, AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	56	$400.00	$22,400.00	$380.00	$21,280.00	$375.00	$21,000.00
4.	1.5" HOT MIX ASPHALTIC CONCRETE PAVEMENT TRANSITION TO EXISTING PAVEMENT, RESTIPING, AND MILLING AS NECESSARY, ONLY AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	SY	677	$16.50	$11,170.50	$29.00	$19,633.00	$52.00	$35,204.00
5.	1.5" HOT MIX ASPHALTIC CONCRETE OVERLAY, D-GR HMA TY-D SAC-B PG 70-22, AND UNDERSEAL COURSE ON EXISTING AND PROPOSED PAVEMENT, AND RESTIPING AS NECESSARY, ONLY AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	SY	6979	$16.50	$115,153.50	$23.00	$160,517.00	$20.00	$139,580.00
6.	2' SAWCUT, REMOVE AND OFFSITE DISPOSAL OF EXISTING ASPHALT CONCRETE PAVEMENT, EXPOSE, CLEAN, AND TIE EXISTING REBAR INTO PROPOSED ASPHALT CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	2896	$6.00	$17,376.00	$8.00	$23,168.00	$4.00	$11,584.00
7.	EXTRA CEMENT STABILIZED SAND BACKFILL, BACKFILL (TY A) 2FT EDGE TAPER, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	212	$90.00	$19,080.00	$75.00	$15,900.00	$81.00	$17,172.00
8.	ADA RAMPS (TY 7), INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	4	$5,500.00	$22,000.00	$2,500.00	$10,000.00	$6,300.00	$25,200.00
9.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	$15,000.00	$15,000.00	$25,000.00	$25,000.00	$31,000.00	$31,000.00
10.	REMOVE EXISTING STRIPING, BUTTONS, AND SIGNAGE, COMPLETE IN PLACE	LS	1	$5,000.00	$5,000.00	$2,000.00	$2,000.00	$2,300.00	$2,300.00
11.	ROADWAY EXCAVATION, INCLUDES STRIPPING, STOCKPILING AND RE-APPLICATION OF STRIPPINGS TO APPLICABLE AREAS, COMPLETE IN PLACE	CY	622	$15.00	$9,330.00	$30.00	$18,660.00	$60.00	$37,320.00
12.	EMBANKMENT, INCLUDES DEMUCKING, REMOVING AND DISPOSING OF EXISTING UNSUITABLE MATERIAL BEFORE PLACING FILL, HAULING, STRIPPING, STOCKPILING STRIPPINGS, PROOFROLLING, RE-APPLICATION OF STRIPPINGS TO FILL AREA, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND FINAL GRADING, COMPLETE IN PLACE	CY	78	$30.00	$2,340.00	$11.00	$858.00	$78.00	$6,084.00
13.	REGRADE AND HYDROMULCH SEED EXISTING ROADSIDE DITCH, INCLUDES WATERING, COMPLETE IN PLACE	LF	2829	$18.00	$50,922.00	$8.00	$22,632.00	$9.00	$25,461.00
14.	EXCAVATED MATERIAL, INCLUDES HAULING EXCAVATED MATERIAL ONSITE, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, FINAL GRADING, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	544	$30.00	$16,320.00	$12.00	$6,528.00	$55.00	$29,920.00
15.	REMOVE AND RELOCAE EXISTING GRAVEL ROAD WITH STABILIZED SUBGRADE, (AS DIRECTED BY GEOTECHNICAL ENGINEER), INCLUDES GEOTEXTILE FABRIC, COMPLETE IN PLACE	SY	23	$100.00	$2,300.00	$60.00	$1,380.00	$155.00	$3,565.00
SUBTOTAL FM 529 PAVING ITEMS					**$572,233.00**		**$577,223.50**		**$571,887.00**

LJA, INC.

BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

				1) HAYDEN PAVING, INC.		2) DURWOOD GREENE CONSTRUCTION CO.		3) FORDE CONSTRUCTION COMPANY	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
KATY LAKES SECTION 6 PAVING ITEMS									
1.	3.5" D-GR HMA TY-D SAC-B PG 70-22, PAVING WITH 8" FLEXIBLE BASE, FL BS (CMP IN PLC) (TYA GR1-2) (FINAL POS), AND PRIME COAT (MC-30), COMPLETE IN PLACE	SY	996	$92.00	$91,632.00	$95.00	$94,620.00	$67.00	$66,732.00
2.	6" LIME STABILIZED SUBGRADE MANIPULATION, COMPLETE IN PLACE	SY	1062	$15.00	$15,930.00	$7.50	$7,965.00	$18.00	$19,116.00
3.	LIME FOR 6" STABILIZED SUBGRADE PREPARATION, 8% BY DRY WEIGHT, AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	21	$400.00	$8,400.00	$380.00	$7,980.00	$370.00	$7,770.00
4.	1.5" HOT MIX ASPHALTIC CONCRETE OVERLAY, D-GR HMA TY-D SAC-B PG 70-22, AND UNDERSEAL COURSE ON EXISTING AND PROPOSED PAVEMENT, AND RESTIPING AS NECESSARY, ONLY AS DIRECTED BY ENGINEER, COMPLETE IN PLACE	SY	996	$16.50	$16,434.00	$23.00	$22,908.00	$42.00	$41,832.00
5.	2' SAWCUT, REMOVE AND OFFSITE DISPOSAL OF EXISTING ASPHALT CONCRETE PAVEMENT, EXPOSE, CLEAN, AND TIE EXISTING REBAR INTO PROPOSED ASPHALT CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	150	$6.00	$900.00	$24.00	$3,600.00	$9.00	$1,350.00
6.	EXTRA CEMENT STABILIZED SAND BACKFILL, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	20	$90.00	$1,800.00	$75.00	$1,500.00	$65.00	$1,300.00
7.	ROADWAY EXCAVATION, INCLUDES STRIPPING, STOCKPILING AND RE-APPLICATION OF STRIPPINGS TO APPLICABLE AREAS, COMPLETE IN PLACE	CY	77	$15.00	$1,155.00	$15.00	$1,155.00	$79.00	$6,083.00
8.	EMBANKMENT, INCLUDES DEMUCKING, REMOVING AND DISPOSING OF EXISTING UNSUITABLE MATERIAL BEFORE PLACING FILL, HAULING, STRIPPING, STOCKPILING STRIPPINGS, PROOFROLLING, RE-APPLICATION OF STRIPPINGS TO FILL AREA, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND FINAL GRADING, COMPLETE IN PLACE	CY	775	$30.00	$23,250.00	$11.00	$8,525.00	$42.00	$32,550.00
9.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	$2,000.00	$2,000.00	$7,000.00	$7,000.00	$2,300.00	$2,300.00
10.	REMOVE EXISTING STRIPING, BUTTONS, AND SIGNAGE, COMPLETE IN PLACE	LS	1	$1,000.00	$1,000.00	$625.00	$625.00	$850.00	$850.00
11.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	$500.00	$1,000.00	$1.00	$2.00	$280.00	$560.00
SUBTOTAL KATY LAKES SECTION 6 PAVING ITEMS					**$163,501.00**		**$155,880.00**		**$180,443.00**
KATY LAKES SECTION 6 DRIVEWAY STORM SEWER ITEMS									
1.	30" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	252	$180.00	$45,360.00	$180.00	$45,360.00	$165.00	$41,580.00
2.	REINFORCED CONCRETE TYPE "AZ" INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	2	$6,500.00	$13,000.00	$6,000.00	$12,000.00	$8,600.00	$17,200.00
3.	6:1 SAFETY END TREATMENT FOR 30" STORM SEWER, INCLUDES PIPE RUNNERS AND SLOPE PAVING, COMPLETE IN PLACE	EA	4	$2,500.00	$10,000.00	$4,000.00	$16,000.00	$4,400.00	$17,600.00
4.	DEWATERING FOR STORM SEWER, (AS DIRECTED BY ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	252	$22.00	$5,544.00	$22.00	$5,544.00	$22.00	$5,544.00

LJA, INC.

FRN F-1386
LJA, Inc.
O:\LAND\2636\0160A\11102026_FM 529 Turn Lane, Traffic Signalization & Driveway_BT

BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

				1) HAYDEN PAVING, INC.		2) DURWOOD GREENE CONSTRUCTION CO.		3) FORDE CONSTRUCTION COMPANY	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
5.	VIDEO INSPECTION OF STORM SEWER, ALL SIZES, INCLUDES DIGITAL COPY, COMPLETE IN PLACE	LF	252	$1.00	$252.00	$1.00	$252.00	$8.00	$2,016.00
6.	TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	252	$1.00	$252.00	$5.00	$1,260.00	$1.00	$252.00
7.	ADDITIONAL COST FOR STORM SEWER BEDDING FOR UNSATISFACTORY SOIL CONDITIONS, (AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	252	$15.00	$3,780.00	$15.00	$3,780.00	$15.00	$3,780.00
8.	UTILITY SPOILS, INCLUDES HAULING EXCAVATED MATERIAL ONSITE, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, FINAL GRADING, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LS	1	$200.00	$200.00	$1,500.00	$1,500.00	$19,000.00	$19,000.00
SUBTOTAL KATY LAKES SECTION 6 DRIVEWAY STORM SEWER ITEMS					**$78,388.00**		**$85,696.00**		**$106,972.00**
FM 529 TRAFFIC SIGNALIZATION									
1.	CONDT PVC (SCHD 80) (2"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 618	LF	95	$19.00	$1,805.00	$20.00	$1,900.00	$14.00	$1,330.00
2.	CONDT PVC (SCHD 80) (3"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 618	LF	45	$27.00	$1,215.00	$28.00	$1,260.00	$16.50	$742.50
3.	CONDT PVC (SCHD 80) (3") (BORE), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 618	LF	200	$33.00	$6,600.00	$34.00	$6,800.00	$22.00	$4,400.00
4.	CONDT PVC (SCHD 80) (4"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 618	LF	25	$29.00	$725.00	$30.00	$750.00	$20.00	$500.00
5.	CONDT (RM) (3"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 618	LF	25	$105.00	$2,625.00	$110.00	$2,750.00	$44.00	$1,100.00
6.	ELEC CONDR (NO. 8) BARE, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 620	LF	405	$3.00	$1,215.00	$2.30	$931.50	$2.25	$911.25
7.	ELEC CONDR (NO. 4) INSULATED, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 620	LF	35	$4.00	$140.00	$4.50	$157.50	$4.25	$148.75
8.	TRAY CABLE (4 CONDR) (12 AWG), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 621	LF	865	$4.00	$3,460.00	$4.00	$3,460.00	$4.15	$3,589.75
9.	GROUND BOX TY D (162922) W/ APRON, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 624	EA	4	$1,600.00	$6,400.00	$1,400.00	$5,600.00	$1,320.00	$5,280.00
10.	ZINC-COAT STL WIRE STRAND (1/4"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 625	LF	590	$3.00	$1,770.00	$3.00	$1,770.00	$1.75	$1,032.50
11.	ZINC-COAT STL WIRE STRAND (5/16"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 625	LF	1340	$4.00	$5,360.00	$4.00	$5,360.00	$2.10	$2,814.00
12.	ZINC-COAT STL WIRE STRAND (3/8"), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 625	LF	310	$4.00	$1,240.00	$3.50	$1,085.00	$2.40	$744.00
13.	TIMBER POLE (CL 2) 50 FT, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 627	EA	4	$4,000.00	$16,000.00	$4,000.00	$16,000.00	$3,740.00	$14,960.00
14.	ELC SRV TY D 120/240 060 (NS) SS (E) SP (O), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 628	EA	1	$7,500.00	$7,500.00	$7,700.00	$7,700.00	$8,670.00	$8,670.00

LJA, INC.

BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

				1) HAYDEN PAVING, INC.		2) DURWOOD GREENE CONSTRUCTION CO.		3) FORDE CONSTRUCTION COMPANY	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
15.	INSTALL HWY TRF SIG (ISOLATED), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$3,000.00	$3,000.00	$3,200.00	$3,200.00	$2,165.00	$2,165.00
16.	CNT FULL ACTUATED SOLID STATE W/ NEMA CAB, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$25,000.00	$25,000.00	$25,000.00	$25,000.00	$30,000.00	$30,000.00
17.	CNT CAB FOUNDATION, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$2,000.00	$2,000.00	$2,100.00	$2,100.00	$3,450.00	$3,450.00
18.	ROD 5/8" X 10' COPPER-CLAD GROUND (CNT ONLY), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$100.00	$100.00	$100.00	$100.00	$66.00	$66.00
19.	18-INCH CABINET BASE EXTENSION, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$1,501.00	$1,501.00	$1,400.00	$1,400.00	$1,600.00	$1,600.00
20.	OVERHEAD SIGN, FM 529 (48" X 18") 6 SF, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$1,100.00	$1,100.00	$1,100.00	$1,100.00	$830.00	$830.00
21.	OVERHEAD SIGN, MINERAL POND RD (96" X 18") 12 SF, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	2	$1,100.00	$2,200.00	$1,100.00	$2,200.00	$830.00	$1,660.00
22.	CELLULAR MODEM, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	1	$1,000.00	$1,000.00	$850.00	$850.00	$450.00	$450.00
23.	LED RDWY LUMINAIRE (.25 KW EQ), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 680	EA	4	$500.00	$2,000.00	$500.00	$2,000.00	$1,850.00	$7,400.00
24.	VEH SIG SEC (12IN) LED (GRN), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	6	$400.00	$2,400.00	$370.00	$2,220.00	$293.00	$1,758.00
25.	VEH SIG SEC (12IN) LED (GRN ARW), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	1	$400.00	$400.00	$370.00	$370.00	$293.00	$293.00
26.	VEH SIG SEC (12IN) LED (YEL), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	6	$400.00	$2,400.00	$370.00	$2,220.00	$293.00	$1,758.00
27.	VEH SIG SEC (12IN) LED (YEL ARW), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	1	$400.00	$400.00	$370.00	$370.00	$293.00	$293.00
28.	VEH SIG SEC (12IN) LED (RED), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	6	$400.00	$2,400.00	$370.00	$2,220.00	$293.00	$1,758.00
29.	VEH SIG SEC (12IN) LED (RED ARW), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	2	$400.00	$800.00	$370.00	$740.00	$293.00	$586.00
30.	PED SIG SEC (LED) (COUNTDOWN), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	4	$700.00	$2,800.00	$750.00	$3,000.00	$696.00	$2,784.00
31.	BACK PLATE W/ REF BRDR (4 SEC), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	1	$300.00	$300.00	$300.00	$300.00	$282.00	$282.00
32.	BACK PLATE W/ REF BRDR (3 SEC), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 682	EA	6	$250.00	$1,500.00	$230.00	$1,380.00	$228.00	$1,368.00
33.	TRF SIG CBL (TY A) (12 AWG) (2 CONDR), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 684	LF	630	$3.00	$1,890.00	$2.50	$1,575.00	$1.75	$1,102.50

LJA, INC.

BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

				1) HAYDEN PAVING, INC.		2) DURWOOD GREENE CONSTRUCTION CO.		3) FORDE CONSTRUCTION COMPANY	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
34.	TRF SIG CBL (TY A) (12 AWG) (4 CONDR), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 684	LF	650	$4.00	$2,600.00	$3.75	$2,437.50	$2.60	$1,690.00
35.	TRF SIG CBL (TY A) (12 AWG) (7 CONDR), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 684	LF	620	$5.00	$3,100.00	$5.25	$3,255.00	$4.00	$2,480.00
36.	PED POLE ASSEMBLY, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 687	EA	3	$1,200.00	$3,600.00	$1,200.00	$3,600.00	$1,350.00	$4,050.00
37.	SCREW-IN ANCHOR FND, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 687	EA	3	$2,000.00	$6,000.00	$2,100.00	$6,300.00	$1,800.00	$5,400.00
38.	PED DETECT PUSH BUTTON (APS), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 688	EA	4	$1,000.00	$4,000.00	$800.00	$3,200.00	$1,000.00	$4,000.00
39.	PED DETECTOR CONTROLLER UNIT, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 688	EA	1	$5,000.00	$5,000.00	$4,400.00	$4,400.00	$4,450.00	$4,450.00
40.	BBU SYSTEM (EXTERNAL BATT CAB), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 6007	EA	1	$8,500.00	$8,500.00	$9,000.00	$9,000.00	$9,500.00	$9,500.00
41.	RVDS (PRESENCE DETECTION ONLY), IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 6008	EA	3	$8,000.00	$24,000.00	$8,700.00	$26,100.00	$11,000.00	$33,000.00
42.	RFDS PRESENCE CABLE, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 6008	LF	580	$3.00	$1,740.00	$2.75	$1,595.00	$4.10	$2,378.00
43.	PRES. RADAR #18/2C & #22/4C, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 6292	LF	590	$3.00	$1,770.00	$2.75	$1,622.50	$3.20	$1,888.00
44.	ADV. RADAR #18/2 & #22/4C, IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS, COMPLETE IN PLACE, TXDOT SPEC. NO. 6292	LF	255	$3.00	$765.00	$2.75	$701.25	$3.20	$816.00
SUBTOTAL FM 529 TRAFFIC SIGNALIZATION					**$170,321.00**		**$170,080.25**		**$175,478.25**
MISCELLANEOUS ITEMS									
1.	BROADCAST SEEDING, INCLUDES FERTILIZING AND WATERING, TO ACHIEVE 90% HOMOGENEOUS GRASS COVERAGE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	1	$4,500.00	$4,500.00	$650.00	$650.00	$2,250.00	$2,250.00
2.	TEMPORARY TRAFFIC CONTROL DEVICES AS NEEDED FOR THE DURATION OF THE PROJECT, (FLAGGERS, CONES, TMA, ETC.), PER TMUTCD, AND AS SHOWN ON PLANS, INCLUDES INSTALLATION, MAINTENANCE, AND REMOVAL, COMPLETE IN PLACE	LS	1	$15,000.00	$15,000.00	$25,000.00	$25,000.00	$11,600.00	$11,600.00
3.	INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT, AND REGRADE AREA TO MATCH FINISHED GRADE, COMPLETE IN PLACE	EA	2	$1,500.00	$3,000.00	$500.00	$1,000.00	$1,400.00	$2,800.00
4.	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	1	$500.00	$500.00	$1,500.00	$1,500.00	$330.00	$330.00
5.	STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS AND ALL ITEMS NOT SPECIFICALLY LISTED IN THE BID PROPOSAL, COMPLETE IN PLACE	LS	1	$7,500.00	$7,500.00	$1,500.00	$1,500.00	$2,900.00	$2,900.00
6.	CLEARING AND GRUBBING OF TREE LINE ALONG FM 529, INCLUDES ROOT RAKING AND BACK DRAGGING, AND OFFSITE DISPOSAL OF CLEARED AND GRUBBED MATERIAL AND EXISTING BARB WIRE FENCE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LF	1275	$25.00	$31,875.00	$24.00	$30,600.00	$16.00	$20,400.00
SUBTOTAL MISCELLANEOUS ITEMS					**$62,375.00**		**$60,250.00**		**$40,280.00**

LJA, INC.

BID TABULATION FOR: CONSTRUCTION OF THE FM 529 TURN LANE, TRAFFIC SIGNALIZATION, AND DRIVEWAY
HARRIS COUNTY MUNICIPAL UTILITY DISTRICT NO. 538
CITY OF HOUSTON, HARRIS COUNTY, TEXAS

BID OPENING DATE: NOVEMBER 10, 2026
BID OPENING LOCATION: LJA, INC.
TABULATION BY: S. YOUNG
TABULATION DATE: NOVEMBER 10, 2026
LJA JOB NO. 2636-0160A (9.2)

				1) HAYDEN PAVING, INC.		2) DURWOOD GREENE CONSTRUCTION CO.		3) FORDE CONSTRUCTION COMPANY	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BID SUMMARY									
	FM 529 PAVING ITEMS				$572,233.00		$577,223.50		$571,887.00
	KATY LAKES SECTION 6 PAVING ITEMS				$163,501.00		$155,880.00		$180,443.00
	KATY LAKES SECTION 6 DRIVEWAY STORM SEWER ITEMS				$78,388.00		$85,696.00		$106,972.00
	FM 529 TRAFFIC SIGNALIZATION				$170,321.00		$170,080.25		$175,478.25
	MISCELLANEOUS ITEMS				$62,375.00		$60,250.00		$40,280.00
TOTAL AMOUNT BASE BID					**$1,046,818.00**		**$1,049,129.75**		**$1,075,060.25**

LJA, INC.