

BID TABULATION FOR:

CONSTRUCTION OF THE ABERMORE LANE FENCE IMPROVEMENTS TO SERVE ALIANA COMMUNITY  
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134B  
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS  
OCTOBER 17, 2024  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
OCTOBER 17, 2024  
2883-2401 (9.2)

BID OPENING DATE:  
BID OPENING LOCATION:  
TABULATION BY:  
TABULATION DATE:  
LJA JOB NO.

BIDDER'S NAME	TOTAL AMOUNT BID
1) AMERICAN WALL SYSTEMS, L.P.	\$646,251.50

CALENDAR DAYS 110/125



10/18/2024

I, Cole Caraway, PE, hereby certify these bid tabulations to be true and correct.

LJA Engineering, Inc.

**BID TABULATION FOR:**

CONSTRUCTION OF THE ABERMORE LANE FENCE IMPROVEMENTS TO SERVE ALIANA COMMUNITY  
FORT BEND COUNTY MUNICIPAL UTILITY DISTRICT NO. 134B  
CITY OF HOUSTON E.T.J., FORT BEND COUNTY, TEXAS  
OCTOBER 17, 2024  
LJA ENGINEERING, INC.  
AVIGAIL AMIGLEO  
OCTOBER 17, 2024  
2883-2401 (9.2)

**BID OPENING DATE:**  
**BID OPENING LOCATION:**  
**TABULATION BY:**  
**TABULATION DATE:**  
**LJA JOB NO.**

ITEM	DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL COST
<b>GENERAL SITE AND DEMOLITION ITEMS</b>					
1	GENERAL CONDITIONS, INCLUDES BONDING AND RESIDENT NOTIFICATION AND COORDINATION PRIOR TO COMMENCEMENT OF CONSTRUCTION, COMPLETE IN PLACE	LS	1	\$11,900.00	\$11,900.00
2	MOBILIZATION COMPLETE IN PLACE	LS	1	\$0.00	\$0.00
3	INSTALLATION, MAINTENANCE AND REMOVAL OF TREE PROTECTION FENCING, COMPLETE IN PLACE	LS	1	\$750.00	\$750.00
4	REMOVE AND DISPOSE OF EXISTING 6-FOOT CEDAR WOOD FENCE, INCLUDES REMOVAL OF 4-INCH X 4-INCH TREATED PINE POST AND 4-FOOT-DEEP CONCRETE FOOTING, HAULING OF MATERIAL OFF-SITE OF DISPOSED MATERIAL AND DISPOSAL FEES, COMPLETE IN PLACE	LF	3451	\$8.00	\$27,608.00
5	INSTALLATION, MAINTENANCE AND REMOVAL OF TEMPORARY 6-FOT CHAIN LINK FENCE WITH WINDSCREEN FOR THE DURATION OF FENCE DEMOLITION AND REPLACEMENT ACROSS ALL LOTS, COMPLETE IN PLACE	LF	3451	\$4.00	\$13,804.00
<b>GENERAL SITE AND DEMOLITION ITEMS SUBTOTAL:</b>					<b>\$54,062.00</b>
<b>FENCING ITEMS</b>					
1	BRICK FENCE PER MATERIAL SCHEDULE, INCLUDES PRODUCT INFORMATION FOR APPROVAL BY OWNER, SINGLE WYTHE COLUMNS WITH MORTAR BED CROWNED TOP, COMPLETE IN PLACE	LF	3451	\$164.50	\$567,689.50
2	FOOTING DESIGN PREPARED BY A TEXAS LICENSED ENGINEER, SIGN AND SEALED SHOW DRAWINGS, COMPLETE IN PLACE	LS	1	\$1,500.00	\$1,500.00
<b>FENCING ITEMS SUBTOTAL:</b>					<b>\$569,189.50</b>
<b>SUPPLEMENTAL ITEMS</b>					
1	LANDSCAPE AND IRRIGATION ALLOWANCE FOR REPAIRS, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LS	1	\$20,000.00	\$20,000.00
2	WOOD FENCING TIE BACKS AND REPAIRS AS NEEDED, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	50	\$60.00	\$3,000.00
<b>SUPPLEMENTAL ITEMS SUBTOTAL:</b>					<b>\$23,000.00</b>
<b>BIDDING SUMMARY</b>					
SUBTOTAL GENERAL SITE AND DEMOLITION ITEMS					\$54,062.00
SUBTOTAL FENCING ITEMS					\$569,189.50
SUBTOTAL SUPPLEMENTAL ITEMS					\$23,000.00
<b>TOTAL AMOUNT BASE BID</b>					<b>\$646,251.50</b>