BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6 CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS NOVEMBER 13, 2025 LJA ENGINEERING, INC. AVIGAIL AMIGLEO NOVEMBER 13, 2025 2959-1402 (9.2)

BIDDER NAME	BASE BID
1) S & J EXCAVATION LLC	\$1,418,114.46
2) HARRIS CONSTRUCTION COMPANY, LLC	\$1,439,733.35
3) CE BARKER LTD.	\$1,774,481.00
4) DC CONTRACTING SERVICES, LLC	\$1,790,442.00
5) AR TURNKEE	\$3,178,975.25
90/100 CALENDAR DAYS OF THE O	

90/100 CALENDAR DAYS



I, Nicholas Hollek, P.E., hereby certify these bid tabulations to be true and correct.

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LIA JOB NO. CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS

FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6 CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025 LJA ENGINEERING, INC.

AVIGAIL AMIGLEO NOVEMBER 13, 2025

2959-1402 (9.2)

				1) S & J EX	CAVATION LLC	2) HARRIS CONSTRU	JCTION COMPANY, LLC	3) CE BAF	RKER LTD.	4) DC CONTRACTIN	IG SERVICES, LLC
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
1.	ON POND ITEMS EXCAVATION FOR DETENTION POND, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE	СУ	86194	\$3.88	\$334,432.72	\$2.75	\$237,033.50	\$5.00	\$430,970.00	\$4.80	\$413,731.20
	EXCAVATION AND GRADING OF DRAINAGE SWALE, 3:1 MINIMUM SIDE SLOPE - V-BOTTOM, (ALL DEPTHS), INCLUDES STRIPPING, STOCKPILING AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	3651	\$2.50	\$9,127.50	\$3.00	\$10,953.00	\$3.00	\$10,953.00	\$2.00	\$7,302.00
	EXCAVATION AND GRADING OF EXTREME EVENT OVERFLOW SWALE, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, SEE PLANS FOR CROSS SECTION, COMPLETE IN PLACE	LF	194	\$8.00	\$1,552.00	\$12.50	\$2,425,00	\$10.00	\$1,940.00	\$11.00	\$2,134.00
	BACKSLOPE INTERCEPTOR STRUCTURE FOR DETENTION POND, INCLUDES #4 REBAR, CONCRETE SLOPE PAVING AND SLOPE PROTECTION, INCLUDES 24" CGMP PIPE, COMPLETE IN PLACE	EA	3	\$16,800.00	\$50,400.00	\$11,595.00	\$34,785.00	\$10,000.00	\$30,000.00	\$17,000.00	\$51,000.00
	BACKSLOPE INTERCEPTOR SWALE FOR DETETNTION POND, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	EA	1822	\$2.58	\$4,700.76	\$3.00	\$5,466.00	\$3.00	\$5,466.00	\$2.00	\$3,644.00
	DEMUCK, SCARIFY, AND FILL, EXISTING PONDED AREAS, COMPLETE IN PLACE	AC	1	\$5,000.00	\$5,000.00	\$2,500.00	\$2,500.00	\$5,000.00	\$5,000.00	\$3,549.90	\$3,549.90
	REMOVE AND OFFSITE DISPOSAL OF EXISTING BACKSLOPE INTERCEPTOR STRUCTURES IN DETERTION POND, INCLUDES REMOVAL OF PIPES, BACKSLOPE INTERCEPTOR AND SLOPE PAVING, COMPLETE IN PLACE	EA	3	\$800.00	\$2,400.00	\$1,200.00	\$3,600.00	\$2,000.00	\$6,000.00	\$1,750.00	\$5,250.00
	AL DETENTION POND ITEMS				\$407,612.98		\$296,762.50	-	\$490,329.00		\$486,611.10
1.	AYOU NORTH ITEMS EXCAVATION FOR RABBS BAYOU EXPANSION, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE	СҮ	26414	\$3.28	\$86,637.92	\$4.25	\$112,259.50	\$5.00	\$132,070.00	\$6.00	\$158,484.00
	EXCAVATION AND GRADING OF DITCHES FOR FARM LAND DRAINAGE, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	90	\$8.00	\$720.00	\$7.35	\$661.50	\$10.00	\$900.00	\$8.00	\$720.00
	BACKSLOPE INTERCEPTOR STRUCTURE FOR RABBS BAYOU EXPANSION, INCLUDES #4 REBAR, CONCRETE SLOPE PAVING AND SLOPE PROTECTION, INCLUDES 24" CGMP PIPE, COMPLETE IN PLACE	EA	3	\$16,800.00	\$50,400.00	\$11,595.00	\$34,785.00	\$10,000.00	\$30,000.00	\$17,000.00	\$51,000.00 FRN F-1386

LJA Engineering, Inc.

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LIA JOB NO. CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS

FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6 CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025

LJA ENGINEERING, INC. AVIGAIL AMIGLEO

NOVEMBER 13, 2025 2959-1402 (9.2)

			1) S & J EXC	AVATION LLC	2) HARRIS CONSTRU	CTION COMPANY, LLC	3) CE BAR	KER LTD.	4) DC CONTRACTIN	IG SERVICES, LLC
										4
NO. ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
4. BACKSLOPE INTERCEPTOR SWALE FOR RABBS BAYOU, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM I LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF B"	1298	\$2.58	\$3,348.84	\$3.00	\$3,894.00	\$3.00	\$3,894.00	\$2.00	\$2,596.00
5. 12" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	193	\$128.00	\$24,704.00	\$86.50	\$16,694.50	\$80.00	\$15,440.00	\$106.00	\$20,458.00
6. REINFORCED CONCRETE TYPE "C" MANHOLE FOR 42" STORM SEWER ANI SMALLER, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	O EA	2	\$5,888.00	\$11,776.00	\$3,825.00	\$7,650.00	\$4,500.00	\$9,000.00	\$7,486.00	\$14,972.00
 REMOVE AND OFFSITE DISPOSAL OF EXISTING 24" PIPES, INCLUDES ADJUSTMENTS TO MATCH PROPOSED SIDESLOPE AND SLOPE PAVING, A DEPTHS, COMPLETE IN PLACE 	EA LL	2	\$2,800.00	\$5,600.00	\$875.00	\$1,750.00	\$6,000.00	\$12,000.00	\$4,000.00	\$8,000.00
8. 4" REINFORCED CONCRETE SLOPE PAVEMENT WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY N	53	\$108.00	\$5,724.00	\$124.00	\$6,572.00	\$150.00	\$7,950.00	\$143.00	\$7,579.00
9. REMOVE AND OFFSITE DISPOSAL OF EXISTING 12" RCP, SLOPE PAVING STORM SEWER MANHOLE, ALL DEPTHS, COMPLETE IN PLACE.	EA	2	\$1,088.00	\$2,176.00	\$5,000.00	\$10,000.00	\$3,000.00	\$6,000.00	\$2,900.00	\$5,800.00
10. TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	193	\$1.00	\$193.00	\$3.95	\$762.35	\$1.00	\$193.00	\$1.00	\$193.00
SUBTOTAL RABBS BAYOU NORTH ITEMS				\$191,279.76	-	\$195,028.85		\$217,447.00	_	\$269,802.00
RABBS BAYOU SOUTH & EAST DITCH ITEMS 1. EXCAVATION FOR EAST DITCH, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE	СУ	7421	\$3.80	\$28,199.80	\$4.35	\$32,281.35	\$5.00	\$37,105.00	\$3.95	\$29,312.95
2. EXCAVATION FOR RABBS BAYOU EXPANSION, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE F & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENS AS INDICATED ON PLANS, COMPLETE IN PLACE		29141	\$3.18	\$92,668.38	\$4.35	\$126,763.35	\$5.00	\$145,705.00	\$3.95	\$115,106.95
3. BACKSLOPE INTERCEPTOR STRUCTURE FOR RABBS BAYOU EXPANSION, INCLUDES #4 REBAR, CONCRETE SLOPE PAVING AND SLOPE PROTECTION INCLUDES 24" CGMP PIPE, COMPLETE IN PLACE	EA ,	3	\$16,800.00	\$50,400.00	\$11,595.00	\$34,785.00	\$10,000.00	\$30,000.00	\$17,000.00	\$51,000.00
4. BACKSLOPE INTERCEPTOR SWALE FOR RABBS BAYOU, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF 8"	1488	\$2.58	\$3,839.04	\$3.00	\$4,464.00	\$3.00	\$4,464.00	\$2.00	\$2,976.00
5. 24" RCP STORM SEWER, ASTM C-76, CLASS III, ALL DEPTHS, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	63	\$118.00	\$7,434.00	\$124.00	\$7,812.00	\$110.00	\$6,930.00	\$130.00	\$8,190.00 FRN F-1386

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS

FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6

CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS **NOVEMBER 13, 2025**

LJA ENGINEERING, INC. AVIGAIL AMIGLEO

NOVEMBER 13, 2025 2959-1402 (9.2)

				1) S & J EXC	AVATION LLC	2) HARRIS CONSTRU	OCTION COMPANY, LLC	3) CE BAR	KER LTD.	4) DC CONTRACTIN	NG SERVICES, LLC
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
6	. 24" HDPE STORM SEWER, ASTM F-2306, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	142	\$98.00	\$13,916.00	\$90.45	\$12,843.90	\$100.00	\$14,200.00	\$130.00	\$18,460.00
7	. 7'XS' RCP STORM SEWER, ASTM C-76, CLASS III, ALL DEPTHS, TO INCLUDE BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	405	\$692.38	\$280,413.90	\$778.15	\$315,150.75	\$800.00	\$324,000.00	\$790.00	\$319,950.00
8	. 4" REINFORCED CONCRETE SLOPE PAVEMENT WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	381	\$108.00	\$41,148.00	\$124.00	\$47,244.00	\$150.00	\$57,150.00	\$127.00	\$48,387.00
9	. JUNCTION BOX WITH TYPE "C" MANHOLE TOP, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$25,800.00	\$51,600.00	\$21,550.00	\$43,100.00	\$30,000.00	\$60,000.00	\$24,133.00	\$48,266.00
10	. REINFORCED CONCRETE TYPE "E" INLET, ALL SIDES OPEN, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$6,000.00	\$6,000.00	\$3,995.00	\$3,995.00	\$5,000.00	\$5,000.00	\$5,473.00	\$5,473.00
11	. REMOVE AND OFFSITE DISPOSAL OF EXISTING 10' X 10' REINFORCED CONCRETE BOX CULVERT, ALL DEPTHS, INCLUDES SLOPE PAVING, COMPLETE IN PLACE	LS	1	\$5,000.00	\$5,000.00	\$17,995.00	\$17,995.00	\$3,000.00	\$3,000.00	\$7,000.00	\$7,000.00
12	. REMOVE AND OFFSITE DISPOSAL OF EXISTING 24" PIPE AND MANHOLES, INCLUDES SLOPE PAVING, ALL DEPTHS, COMPLETE IN PLACE	LF	100	\$18.00	\$1,800.00	\$85.00	\$8,500.00	\$60.00	\$6,000.00	\$26.00	\$2,600.00
13	. REMOVE AND OFFSITE DISPOSAL OF EXISTING 42" PIPE AND MANHOLES, INCLUDES SLOPE PAVING, ALL DEPTHS, COMPLETE IN PLACE	LF	146	\$38.00	\$5,548.00	\$98.00	\$14,308.00	\$90.00	\$13,140.00	\$41.00	\$5,986.00
14	. 4" REINFORCED CONCRETE SLOPE PAVEMENT FOR STORM PIPE AT KELSEY SEYBOLD WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	280	\$108.00	\$30,240.00	\$124.00	\$34,720.00	\$150.00	\$42,000.00	\$127.00	\$35,560.00
15	. 4" REINFORCED CONCRETE SLOPE PAVEMENT FOR 10' X 10' WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	390	\$108.00	\$42,120.00	\$124.00	\$48,360.00	\$150.00	\$58,500.00	\$148.00	\$57,720.00
16	. RELOCATE EXISTING LOW WATER CROSSING AND ADD 286 SY OF NEW ACCESS ROAD, INCLUDES EXCAVATION, COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$15,495.00	\$15,495.00	\$17,500.00	\$17,500.00	\$12,500.00	\$12,500.00
17	. TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	547	\$1.00	\$547.00	\$3.95	\$2,160.65	\$1.00	\$547.00	\$1.00	\$547.00
	TAL RABBS BAYOU SOUTH & EAST DITCH ITEMS			_	\$668,874.12	-	\$769,978.00	_	\$825,241.00	_	\$769,034.90
	INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	16364	\$1.00	\$16,364.00	\$1.00	\$16,364.00	\$1.00	\$16,364.00	\$1.00	\$16,364.00
2	. STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00	\$2,100.00	\$2,100.00	\$2,500.00	\$2,500.00	\$9,700.00	\$9,700.00
3	. INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	4	\$800.00	\$3,200.00	\$2,500.00	\$10,000.00	\$3,000.00	\$12,000.00	\$3,350.00	\$13,400.00 FRN F-138

LJA Engineering, Inc.

O:\LAND\2959\1402\111325_Circle Oak Ph 2 Detention, Drainage & Mitigation

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LIA JOB NO. CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS

FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6 CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025 LJA ENGINEERING, INC.

AVIGAIL AMIGLEO NOVEMBER 13, 2025 2959-1402 (9.2)

			1) S & J EXC	AVATION LLC	2) HARRIS CONSTRU	JCTION COMPANY, LLC	3) CE BA	RKER LTD.	4) DC CONTRACTI	NG SERVICES, LLC
NO. ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
 INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE 	EA	2	\$1,200.00	\$2,400.00	\$1,000.00	\$2,000.00	\$750.00	\$1,500.00	\$450.00	\$900.00
BEDDING AND BACKFILL FOR STORM SEWER WET SAND CONSTRUCTION AND UNSATISFACTORY SOIL CONDITIONS (PER DETAIL), TO BE USED ONLY AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	100	\$30.00	\$3,000.00	\$60.00	\$6,000.00	\$30.00	\$3,000.00	\$25.00	\$2,500.00
6. CEMENT STABILIZED SAND BACKFILL, (1.1 SACKS PER TON), (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	СУ	10	\$15.00	\$150.00	\$15.00	\$150.00	\$15.00	\$150.00	\$15.00	\$150.00
7. HYDROMULCH SEEDING FOR PROPOSED SIDE SLOPE, COMPLETE IN PLACE	AC	4	\$1,800.00	\$7,200.00	\$3,450.00	\$13,800.00	\$1,650.00	\$6,600.00	\$2,150.00	\$8,600.00
 BROADCAST SEEDING, INCLUDES FERTILIZING AND WATERING, TO ACHIEV 90% HOMOGENEOUS GRASS COVERAGE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE 	E AC	13.5	\$500.00	\$6,750.00	\$500.00	\$6,750.00	\$500.00	\$6,750.00	\$500.00	\$6,750.00
 PUMP DOWN {WITH 4-INCH PUMP STANDING WATER, AS NECESSARY TO CREATE A DRY WORKING ENVIRONMENT FOR THE INSTALLATION OF PROPOSED DRAINAGE IMPROVEMENTS, COMPLETE IN PLACE 	HR	100	\$25.00	\$2,500.00	\$25.00	\$2,500.00	\$25.00	\$2,500.00	\$25.00	\$2,500.00
10. AS BUILT SURVEY OF ALL DETENTION, RABBS BAYOU, CHANNEL, AND FILL AREAS, INCLUDES HIGH POINTS, LOW POINTS, GRADE BREAKS, AND ANY ADDITIONAL POINTS CALLED OUT IN THE PLANS. INCLUDES AN EXHIBIT CERTIFIED BY A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATI OF TEXAS, AS WELL AS AN AUTOCAD FILE OF SURVEY, COMPLETE IN PLACE		1	\$18,000.00	\$18,000.00	\$8,525.00	\$8,525.00	\$20,000.00	\$20,000.00	\$17,500.00	\$17,500.00
11. CLEARING AND GRUBBING, INCLUDES OFFSITE DISPOSAL OF CLEARED AND GRUBBED MATERIAL, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	3.6	\$1.00	\$3.60	\$7,425.00	\$26,730.00	\$9,500.00	\$34,200.00	\$9,250.00	\$33,300.00
12. REMOVE EXISTING BRIDGE, INCLUDES OFFSITE DISPOSAL, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LS	1	\$8,000.00	\$8,000.00	\$10,000.00	\$10,000.00	\$25,000.00	\$25,000.00	\$4,050.00	\$4,050.00
13. 24" RCP STORM SEWER FOR SOUTH LOW WATER CROSSING, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE		160	\$98.00	\$15,680.00	\$121.50	\$19,440.00	\$140.00	\$22,400.00	\$163.00	\$26,080.00
14. 36" RCP STORM SEWER FOR NORTH LOW WATER CROSSING, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE		200	\$130.00	\$26,000.00	\$160.40	\$32,080.00	\$180.00	\$36,000.00	\$238.00	\$47,600.00
15. CRUSHED CONCRETE FOR NORTH LOW WATER CROSSING OVER OUTFALL, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE	SY	1800	\$19.00	\$34,200.00	\$10.25	\$18,450.00	\$25.00	\$45,000.00	\$36.00	\$64,800.00
16. CRUSHED CONCRETE FOR SOUTH LOW WATER CROSSING OVER OUTFALL, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE	SY	300	\$19.00	\$5,700.00	\$10.25	\$3,075.00	\$25.00	\$7,500.00	\$36.00	\$10,800.00
SUBTOTAL MISCELLANEOUS ITEMS			-	\$150,347.60		\$177,964.00	-	\$241,464.00	_	\$264,994,00 _{F-1386}

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LIA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6
CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS
NOVEMBER 13, 2025
LIA ENGINEERING, INC.
AVIGAIL AMIGLEO

			1) S & J E)	CAVATION LLC	2) HARRIS CONSTR	UCTION COMPANY, LLC	3) CE B/	ARKER LTD.	4) DC CONTRACTIF	IG SERVICES, LLC
NO. ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BID SUMMARY										
DETENTION POND ITEMS				\$407,612.98		\$296,762.50		\$490,329.00		\$486,611.10
RABBS BAYOU NORTH ITEMS				\$191,279.76		\$195,028.85		\$217,447.00		\$269,802.00
RABBS BAYOU SOUTH & EAST DITCH ITEMS				\$668,874.12		\$769,978.00		\$825,241.00		\$769,034.90
MISCELLANEOUS ITEMS				\$150,347.60		\$177,964.00		\$241,464.00		\$264,994.00
TOTAL AMOUNT BASE BID				\$1,418,114.46		\$1,439,733.35		\$1,774,481.00		\$1,790,442.00

NOVEMBER 13, 2025

2959-1402 (9.2)

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: **TABULATION DATE:** LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS

FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6 CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025

LJA ENGINEERING, INC. AVIGAIL AMIGLEO **NOVEMBER 13, 2025**

LIA JOB NO.			959-1402 (9.2)		
			5) AR T	URNKEE	
NO. ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	
DETENTION POND ITEMS 1. EXCAVATION FOR DETENTION POND, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE	СҮ	86194	\$12.00	\$1,034,328.00	
2. EXCAVATION AND GRADING OF DRAINAGE SWALE, 3:1 MINIMUM SIDE SLOPE - V-BOTTOM, (ALL DEPTHS), INCLUDES STRIPPING, STOCKPILING AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	3651	\$7.75	\$28,295.25	4.001
3. EXCAVATION AND GRADING OF EXTREME EVENT OVERFLOW SWALE, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, SEE PLANS FOR CROSS SECTION, COMPLETE IN PLACE	LF	194	\$10.00	\$1,940.00	
BACKSLOPE INTERCEPTOR STRUCTURE FOR DETENTION POND, INCLUDES #4 REBAR, CONCRETE SLOPE PAVING AND SLOPE PROTECTION, INCLUDES 24" CGMP PIPE, COMPLETE IN PLACE	EA	3	\$7,700.00	\$23,100.00	
5. BACKSLOPE INTERCEPTOR SWALE FOR DETETNTION POND, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	EA	1822	\$5.00	\$9,110.00	
6. DEMUCK, SCARIFY, AND FILL, EXISTING PONDED AREAS, COMPLETE IN PLACE	AC	1	\$21,000.00	\$21,000.00	
7. REMOVE AND OFFSITE DISPOSAL OF EXISTING BACKSLOPE INTERCEPTOR STRUCTURES IN DETENTION POND, INCLUDES REMOVAL OF PIPES, BACKSLOPE INTERCEPTOR AND SLOPE PAVING, COMPLETE IN PLACE	EA	3	\$1,030.00	\$3,090.00	
SUBTOTAL DETENTION POND ITEMS			_	\$1,120,863.25	
RABBS BAYOU NORTH ITEMS 1. EXCAVATION FOR RABBS BAYOU EXPANSION, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE	СУ	26414	\$13.00	\$343,382.00	
2. EXCAVATION AND GRADING OF DITCHES FOR FARM LAND DRAINAGE, INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	90	\$10.00	\$900.00	
3. BACKSLOPE INTERCEPTOR STRUCTURE FOR RABBS BAYOU EXPANSION, INCLUDES #4 REBAR, CONCRETE SLOPE PAVING AND SLOPE PROTECTION, INCLUDES 24" CGMP PIPE, COMPLETE IN PLACE	EA	3	\$7,700.00	\$23,100.00	ı

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: **TABULATION DATE:** LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS

FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6 CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025

LJA ENGINEERING, INC. AVIGAIL AMIGLEO

NOVEMBER 13, 2025 2959-1402 (9.2)

5)	AR TURNKEE	
----	------------	--

LJA JOB	ATION DATE: B NO.			NOVEMBER 13, 2025 1959-1402 (9.2)	
				5) AR TU	JRNKEE
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
4	I. BACKSLOPE INTERCEPTOR SWALE FOR RABBS BAYOU, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	1298	\$5.50	\$7,139.00
5	5. 12" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	193	\$137.00	\$26,441.00
6	5. REINFORCED CONCRETE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$5,000.00	\$10,000.00
7	7. REMOVE AND OFFSITE DISPOSAL OF EXISTING 24" PIPES, INCLUDES ADJUSTMENTS TO MATCH PROPOSED SIDESLOPE AND SLOPE PAVING , ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$1,700.00	\$3,400.00
8	B. 4" REINFORCED CONCRETE SLOPE PAVEMENT WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	53	\$207.00	\$10,971.00
9	9. REMOVE AND OFFSITE DISPOSAL OF EXISTING 12" RCP, SLOPE PAVING STORM SEWER MANHOLE, ALL DEPTHS, COMPLETE IN PLACE.	EA	2	\$1,050.00	\$2,100.00
10). TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	193	\$10.00	\$1,930.00
SUBTO	TAL RABBS BAYOU NORTH ITEMS				\$429,363.00
1	BAYOU SOUTH & EAST DITCH ITEMS 1. EXCAVATION FOR EAST DITCH, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE	СУ	7421	\$13.00	\$96,473.00
2	2. EXCAVATION FOR RABBS BAYOU EXPANSION, INCLUDES SITE PREP, EXCAVATION, HAULING DIRT TO FILL AREAS LOCATED ON SITE PER THE FILL & GRADING PLAN, PLACEMENT IN MAXIMUM 8-INCH LIFTS, MANIPULATION, AND COMPACTION TO 95% STANDARD PROCTOR DENSITY AS INDICATED ON PLANS, COMPLETE IN PLACE		29141	\$17.00	\$495,397.00
3	B. BACKSLOPE INTERCEPTOR STRUCTURE FOR RABBS BAYOU EXPANSION, INCLUDES #4 REBAR, CONCRETE SLOPE PAVING AND SLOPE PROTECTION, INCLUDES 24" CGMP PIPE, COMPLETE IN PLACE	EA	3	\$7,700.00	\$23,100.00
4	I. BACKSLOPE INTERCEPTOR SWALE FOR RABBS BAYOU, INCLUDES EXCAVATION, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	1488	\$5.00	\$7,440.00
5	5. 24" RCP STORM SEWER, ASTM C-76, CLASS III, ALL DEPTHS, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	63	\$173.00	\$10,899.00

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: **TABULATION DATE:** LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6

CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS **NOVEMBER 13, 2025** LJA ENGINEERING, INC. AVIGAIL AMIGLEO

NOVEMBER 13, 2025 2959-1402 (9.2)

5)	AR	TUR	NKEE
----	----	-----	------

TABULA	NO.			OVEMBER 13, 2025 959-1402 (9.2)		
				5) AR T	URNKEE	
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	
6	. 24" HDPE STORM SEWER, ASTM F-2306, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	142	\$107.00	\$15,194.00	100
7	. 7'X5' RCP STORM SEWER, ASTM C-76, CLASS III, ALL DEPTHS, TO INCLUDE BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	405	\$1,177.00	\$476,685.00	
8	. 4" REINFORCED CONCRETE SLOPE PAVEMENT WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	381	\$137.00	\$52,197.00	
9	. JUNCTION BOX WITH TYPE "C" MANHOLE TOP, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$33,300.00	\$66,600.00	erin9,
10	. REINFORCED CONCRETE TYPE "E" INLET, ALL SIDES OPEN, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$5,000.00	\$5,000.00	
11	. REMOVE AND OFFSITE DISPOSAL OF EXISTING 10' X 10' REINFORCED CONCRETE BOX CULVERT, ALL DEPTHS, INCLUDES SLOPE PAVING, COMPLETE IN PLACE	LS	1	\$11,300.00	\$11,300.00	8,
12	. REMOVE AND OFFSITE DISPOSAL OF EXISTING 24" PIPE AND MANHOLES, INCLUDES SLOPE PAVING, ALL DEPTHS, COMPLETE IN PLACE	LF	100	\$20.00	\$2,000.00	
13	. REMOVE AND OFFSITE DISPOSAL OF EXISTING 42" PIPE AND MANHOLES, INCLUDES SLOPE PAVING, ALL DEPTHS, COMPLETE IN PLACE	LF	146	\$40.00	\$5,840.00	
14	. 4" REINFORCED CONCRETE SLOPE PAVEMENT FOR STORM PIPE AT KELSEY SEYBOLD WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	280	\$133.00	\$37,240.00	
15	. 4" REINFORCED CONCRETE SLOPE PAVEMENT FOR 10' X 10' WITH TOE WALLS ALL AROUND, INCLUDES WEEP HOLES AND EXPANSION JOINTS, COMPLETE IN PLACE	SY	390	\$133.00	\$51,870.00	
16	RELOCATE EXISTING LOW WATER CROSSING AND ADD 286 SY OF NEW ACCESS ROAD, INCLUDES EXCAVATION, COMPLETE IN PLACE	LS	1	\$23,500.00	\$23,500.00	
17	. TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	547	\$10.00	\$5,470.00	
SUBTO	TAL RABBS BAYOU SOUTH & EAST DITCH ITEMS			=	\$1,386,205.00	
	LANEOUS ITEMS INSTALL, MAINTAIN, AND REMOVE REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	16364	\$1.00	\$16,364.00	
2	. STORM WATER POLLUTION PREVENTION PLAN COMPLIANCE, INCLUDES GENERAL SOURCE CONTROLS, COMPLETE IN PLACE	LS	1	\$1,200.00	\$1,200.00	
3	. INSTALL, MAINTAIN, AND REMOVE STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	4	\$500.00	\$2,000.00	FRN F-1386

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: **TABULATION DATE:** LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6

CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025 LJA ENGINEERING, INC.

AVIGAIL AMIGLEO **NOVEMBER 13, 2025**

LJA JOI	B NO.		2	2959-1402 (9.2)	
				5) AR T	URNKEE
NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL
-	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	2	\$300.00	\$600.00
!	5. BEDDING AND BACKFILL FOR STORM SEWER WET SAND CONSTRUCTION AND UNSATISFACTORY SOIL CONDITIONS (PER DETAIL), TO BE USED ONLY AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	100	\$15.00	\$1,500.00
(5. CEMENT STABILIZED SAND BACKFILL, (1.1 SACKS PER TON), (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	CY	10	\$15.00	\$150.00
	7. HYDROMULCH SEEDING FOR PROPOSED SIDE SLOPE, COMPLETE IN PLACE	AC	4	\$3,000.00	\$12,000.00
;	B. BROADCAST SEEDING, INCLUDES FERTILIZING AND WATERING, TO ACHIEVE 90% HOMOGENEOUS GRASS COVERAGE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	13.5	\$500.00	\$6,750.00
9	9. PUMP DOWN (WITH 4-INCH PUMP STANDING WATER, AS NECESSARY TO CREATE A DRY WORKING ENVIRONMENT FOR THE INSTALLATION OF PROPOSED DRAINAGE IMPROVEMENTS, COMPLETE IN PLACE	HR	100	\$25.00	\$2,500.00
10	D. AS BUILT SURVEY OF ALL DETENTION, RABBS BAYOU, CHANNEL, AND FILL AREAS, INCLUDES HIGH POINTS, LOW POINTS, GRADE BREAKS, AND ANY ADDITIONAL POINTS CALLED OUT IN THE PLANS. INCLUDES AN EXHIBIT CERTIFIED BY A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF TEXAS, AS WELL AS AN AUTOCAD FILE OF SURVEY, COMPLETE IN PLACE	LS	1	\$11,000.00	\$11,000.00
1:	CLEARING AND GRUBBING, INCLUDES OFFSITE DISPOSAL OF CLEARED AND GRUBBED MATERIAL, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	3.6	\$10,000.00	\$36,000.00
1	2. REMOVE EXISTING BRIDGE, INCLUDES OFFSITE DISPOSAL, TO BE USED AT THE DIRECTION OF THE ENGINEER, COMPLETE IN PLACE	LS	1	\$7,000.00	\$7,000.00
1:	3. 24" RCP STORM SEWER FOR SOUTH LOW WATER CROSSING, ASTM C 76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE	LF	160	\$133.00	\$21,280.00
14	4. 36" RCP STORM SEWER FOR NORTH LOW WATER CROSSING, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE	LF	200	\$201.00	\$40,200.00
1!	5. CRUSHED CONCRETE FOR NORTH LOW WATER CROSSING OVER OUTFALL, TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF CONSTRUCTION, COMPLETE IN PLACE	SY	1800	\$40.00	\$72,000.00

\$242,544.00 SUBTOTAL MISCELLANEOUS ITEMS

300

\$40.00

16. CRUSHED CONCRETE FOR SOUTH LOW WATER CROSSING OVER OUTFALL,

TO BE REMOVED AND DISPOSED OF OFFSITE AT THE END OF

CONSTRUCTION, COMPLETE IN PLACE

\$12,000.00

BID OPENING DATE: BID OPENING LOCATION: TABULATION BY: TABULATION DATE: LJA JOB NO.

CONSTRUCTION OF THE CIRCLE OAK PHASE 2 DETENTION, DRAINAGE, & MITIGATION IMPROVEMENTS FORT BEND COUNTY LEVEE IMPROVEMENT DISTRICT NO. 6

CITY OF RICHMOND E.T.J., FORT BEND COUNTY, TEXAS

NOVEMBER 13, 2025 LJA ENGINEERING, INC.

AVIGAIL AMIGLEO

NOVEMBER 13, 2025

2959-1402 (9.2)

			5) AR TURNKEE		
	1				

NO.	ITEM DESCRIPTION	UNIT	QTY	UNIT COST	TOTAL	
BID SUMMARY						
DETENTION POND ITEMS					\$1,120,863.25	
RABBS BAYOU NORTH ITEMS					\$429,363.00	
RABBS BAYOU SOUTH & EAST DITCH ITEMS					\$1,386,205.00	
MISCELL	ANEOUS ITEMS				\$242,544.00	
TOTAL A	MOUNT BASE BID				\$3,178,975.25	

O:\LAND\2959\1402\111325_Circle Oak Ph 2 Detention, Drainage & Mitigation