

BID TABULATION FOR:

CONSTRUCTION OF THE ROADWAY CONSTRUCTION
TO SERVE SIENNA VILLAGE OF DESTREHAN SECTION 2 - SIENNA PARKWAY (REBID)
SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.


JULY 30, 2024
LJA ENGINEERING, INC.
C CORTEZ
JULY 31, 2024
1415-0200 (9.2)

TOTAL AMOUNT BID

BIDDER'S NAME

1) DVL ENTERPRISES LLC	\$709,000.00
2) HARRIS CONSTRUCTION COMPANY, LLC	\$994,901.80

CALENDAR DAYS 50/60



Richard Stanfield Jr
8/1/2024

Richard Stanfield Jr

I, RICHARD STANFIELD, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE ROADWAY CONSTRUCTION
 TO SERVE SIENNA VILLAGE OF DESTREHAN SECTION 2 - SIENNA PARKWAY (REBID)
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JULY 30, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JULY 31, 2024
 1415-0200 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DVL ENTERPRISES LLC		2) HARRIS CONSTRUCTION COMPANY, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
SIENNA VILLAGE OF DESTREHAN SECTION 2-SIENNA PARKWAY (SMUD 5)							
1	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY SOUTHBOUND STATION 36+00, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
2	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 36+00, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
3	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY SOUTHBOUND STATION 36+42, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
4	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY SOUTHBOUND STATION 38+50, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
5	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 38+50, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
6	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 39+40, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
7	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 40+14, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
8	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY SOUTHBOUND STATION 42+90, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
9	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 44+76, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
10	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY SOUTHBOUND STATION 46+77, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
11	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 46+77, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
12	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 49+09, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	40	\$60.00	\$2,400.00	\$101.50	\$4,060.00
13	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY SOUTHBOUND STATION 49+87, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	20	\$75.00	\$1,500.00	\$101.50	\$2,030.00
14	REPAIR EXISTING BIRDBATH AT SIENNA PARKWAY NORTHBOUND STATION 51+89, BY GRINDING, OR BY ANY OTHER MEANS NECESSARY (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	40	\$60.00	\$2,400.00	\$101.50	\$4,060.00
15	REMOVE AND REPLACE WHEELCHAIR RAMPS AS PER COMC DETAIL, INCLUDING TRUNCATED DOME PAVER AS NOTED IN THE CONSTRUCTION PLAN SET, COMPLETE IN PLACE	EA	2	\$6,000.00	\$12,000.00	\$6,675.00	\$13,350.00
16	6" OR 4" X 18" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	320	\$10.00	\$3,200.00	\$21.75	\$6,960.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE ROADWAY CONSTRUCTION
 TO SERVE SIENNA VILLAGE OF DESTREHAN SECTION 2 - SIENNA PARKWAY (REBID)
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JULY 30, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JULY 31, 2024
 1415-0200 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DVL ENTERPRISES LLC		2) HARRIS CONSTRUCTION COMPANY, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
17	REPAIR INLET TOP, COMPLETE IN PLACE	EA	7	\$1,500.00	\$10,500.00	\$3,625.00	\$25,375.00
18	INSTALL RAISED PAVEMENT MARKINGS (THROUGHOUT ROADWAY), AS PER APPROVED TRAFFIC CONTROL PLAN	LS	1	\$2,000.00	\$2,000.00	\$14,500.00	\$14,500.00
19	RE-STRIPE ALL PAVEMENT (THROUGHOUT ROADWAY) WITH APPROVED CITY OF MISSOURI CITY THERMAL PAINT, AS PER APPROVED TRAFFIC CONTROL PLAN	LS	1	\$15,000.00	\$15,000.00	\$14,500.00	\$14,500.00
20	CLEAN AND SEAL EXPANSION JOINTS (THROUGHOUT ROADWAY) WITH MASTIC, OR APPROVED EQUAL, COMPLETE IN PLACE.	LS	1	\$5,000.00	\$5,000.00	\$14,875.00	\$14,875.00
21	SEAL SURFACE CRACKS THROUGHOUT ROADWAY, BY INJECTABLE METHOD, PRODUCT TO BE TXDOT APPROVED SEALANT, CONTRACTOR TO SUBMIT PRODUCT FOR ENGINEER APPROVAL, (TO BE COMPLETED AT THE DIRECTION OF THE ENGINEER)	LF	1000	\$35.00	\$35,000.00	\$43.50	\$43,500.00
22	FORT BEND COUNTY INSPECTION AND ACCEPTANCE FEE, COMPLETE IN PLACE	EA	1	\$5,000.00	\$5,000.00	\$1,500.00	\$1,500.00
23	FORT BEND COUNTY RIGHT OF WAY PERMIT, COMPLETE IN PLACE	EA	1	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00
24	TEMPORARY TRAFFIC CONTROL FOR CONSTRUCTION ALONG SIENNA PARKWAY, AS PER ATTACHED LAYOUT, INCLUDES ELECTRONIC SIGNAGE DURING CONSTRUCTION AND INCLUDING 2 WEEKS PRIOR TO CONSTRUCTION, SIGNAGE, BARRELS, FLAGMEN, STEEL PLATES, ETC. AND ALL OTHER APPURTENANCES NECESSARY TO COMPLETE PHASE I REPAIR WORK, COMPLETE IN PLACE	LS	1	\$10,000.00	\$10,000.00	\$20,000.00	\$20,000.00
25	REPAIR AND RESTORE ALL LANDSCAPE AND IRRIGATION AFFECTED BY CONSTRUCTION AND OR SITE MODIFICATIONS, CONTRACTOR SHALL USE GREENYARD INC., (CONTACT: AMY HOYT; 979.398.2696) TO PERFORM ALL DUTIES RELATED TO THIS TASK AND THE MINIMUM UNIT PRICE PROVIDED ON THE BID FORM. LANDSCAPE AND IRRIGATION WORK INCLUDES (A) CUT AND CAP ALL IRRIGATION LINES AND REMOVAL OF TREES, SHRUBS AND GROUND COVER WITHIN L.O.C. PRIOR TO CONSTRUCTION, (B) INSTALLATION OF NEW SHRUBS/GROUND COVERS AND (C) INSTALLATION OF IRRIGATION NEEDED TO PROVIDE COMPLETE COVERAGE. NOTE: CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL CONSTRUCTION DEBRIS AND INITIAL GRADING NECESSARY TO BRING AFFECTED AREAS WITHIN 1" OF FINAL GRADE BEFORE TURNING OVER SITE TO LANDSCAPE CONTRACTOR, COMPLETE IN PLACE	LS	1	\$30,000.00	\$30,000.00	\$150,000.00	\$150,000.00
SIENNA VILLAGE OF DESTREHAN SECTION 2-SIENNA PARKWAY (SMUD 5) SUBTOTAL:					\$160,500.00		\$339,540.00
ALTERNATE BID NO. 1 - SIENNA VILLAGE OF DESTREHAN SECTION 2-SIENNA PARKWAY							
1	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY SOUTHBOUND STATION 36+00, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE. (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE ROADWAY CONSTRUCTION
 TO SERVE SIENNA VILLAGE OF DESTREHAN SECTION 2 - SIENNA PARKWAY (REBID)
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JULY 30, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JULY 31, 2024
 1415-0200 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DVL ENTERPRISES LLC		2) HARRIS CONSTRUCTION COMPANY, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
2	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 36+00, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	105	\$250.00	\$26,250.00	\$292.45	\$30,707.25
3	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY SOUTHBOUND STATION 36+42, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00
4	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY SOUTHBOUND STATION 38+50, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00
5	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 38+50, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	91	\$250.00	\$22,750.00	\$292.45	\$26,612.95
6	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 39+40, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00
7	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 40+14, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	296	\$250.00	\$74,000.00	\$292.45	\$86,565.20

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE ROADWAY CONSTRUCTION
 TO SERVE SIENNA VILLAGE OF DESTREHAN SECTION 2 - SIENNA PARKWAY (REBID)
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JULY 30, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JULY 31, 2024
 1415-0200 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DVL ENTERPRISES LLC		2) HARRIS CONSTRUCTION COMPANY, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
8	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY SOUTHBOUND STATION 42+90, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00
9	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 44+76, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	245	\$250.00	\$61,250.00	\$292.45	\$71,650.25
10	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY SOUTHBOUND STATION 46+77, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00
11	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 46+77, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00
12	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 49+09, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	142	\$250.00	\$35,500.00	\$292.45	\$41,527.90
13	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY SOUTHBOUND STATION 49+87, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	80	\$250.00	\$20,000.00	\$292.45	\$23,396.00

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE ROADWAY CONSTRUCTION
 TO SERVE SIENNA VILLAGE OF DESTREHAN SECTION 2 - SIENNA PARKWAY (REBID)
 SIENNA MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF MISSOURI CITY, FORT BEND COUNTY, TEXAS
 JULY 30, 2024
 LJA ENGINEERING, INC.
 C CORTEZ
 JULY 31, 2024
 1415-0200 (9.2)

ITEM	DESCRIPTION	UNIT	QTY	1) DVL ENTERPRISES LLC		2) HARRIS CONSTRUCTION COMPANY, LLC	
				UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
14	REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NORTHBOUND STATION 51+89. INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE. INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	145	\$250.00	\$36,250.00	\$292.45	\$42,405.25
15	ADDITIONAL REMOVE AND DISPOSE OF CONCRETE PAVEMENT AT SIENNA PARKWAY NECESSARY IN ORDER TO REMOVE THE BIRD BATH AND MAKE PAVEMENT TO GRADE, INCLUDES FULL DEPTH SAWCUT, CURB, AND PROPER DISPOSAL OF ALL MATERIAL OFFSITE, INCLUDES OVER EXCAVATION OF UNSUITABLE MATERIAL (AS DIRECTED BY THE GEOTECHNICAL ENGINEER)AND OFFSITE DISPOSAL, PLACEMENT AND COMPACTION OF CEMENT STABILIZED SAND FOR SUBGRADE, (MINIMUM 2 SACKS PER CY MIX), AND PLACEMENT OF 8" CONCRETE PAVEMENT, 7-SACK, HIGH EARLY, INCLUDING ALL NECESSARY DOWELS, COMPLETE IN PLACE.	SY	500	\$250.00	\$125,000.00	\$292.45	\$146,225.00
16	CORING OF PAVEMENT IN AREAS WHERE APPROVED FORT BEND COUNTY SEALING METHODS WERE USED BY THE CONTRACTOR, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	EA	15	\$500.00	\$7,500.00	\$1,500.00	\$22,500.00
ALTERNATE BID NO. 1 - SIENNA VILLAGE OF DESTREHAN SECTION 2-SIENNA PARKWAY					\$548,500.00		\$655,361.80
BIDDING SUMMARY							
SUBTOTAL SIENNA VILLAGE OF DESTREHAN SECTION 2-SIENNA PARKWAY (SMUD 5)					\$160,500.00		\$339,540.00
SUBTOTAL ALTERNATE BID NO. 1 - SIENNA VILLAGE OF DESTREHAN SECTION 2-SIENNA					\$548,500.00		\$655,361.80
TOTAL AMOUNT BASE BID					\$709,000.00		\$994,901.80

