

BID TABULATION FOR:

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILDTREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)

BID OPENING DATE:

BID OPENING LOCATION:

TABULATION BY:

TABULATION DATE:

LJA JOB NO.

BIDDER NAME	BASE BID	ALTERNATE BID FOR PAVING PLUS BASE BID	PROPOSED DURATION	PROPOSED DURATION
			(DAYS) BASE BID	(DAYS) BASE BID PLUS ALTERNATE BID
1) LEXTON CONSTRUCTION, LLC	\$1,826,046.30	\$2,719,596.15	45 \ 55	90 \ 100
2) TEXASITE, LLC	\$1,910,236.00	\$2,825,296.15	50 \ 60	100 \ 110
3) R CONSTRUCTION CIVIL, LLC	\$1,998,720.30	\$2,882,814.90	90 \ 90	120 \ 120
4) CE BARKER LTD.	\$2,139,133.00	\$3,306,073.00	90 \ 120	150 \ 180

Kenya Franco

I, Kenya Franco, PE, hereby certify these bid tabulations to be true and correct.



BID TABULATION FOR:

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILDTREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) LEXTON CONSTRUCTION, LLC		2) TEXASITE, LLC		3) R CONSTRUCTION CIVIL, LLC		4) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID WATER ITEMS											
1.	4" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	346	\$25.30	\$8,753.80	\$26.00	\$8,996.00	\$25.00	\$8,650.00	\$30.00	\$10,380.00
2.	6" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	226	\$26.90	\$6,079.40	\$28.00	\$6,328.00	\$30.00	\$6,780.00	\$35.00	\$7,910.00
3.	8" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	2307	\$36.50	\$84,205.50	\$38.00	\$87,666.00	\$40.00	\$92,280.00	\$40.00	\$92,280.00
4.	8" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	16	\$98.30	\$1,572.80	\$89.00	\$1,424.00	\$100.00	\$1,600.00	\$135.00	\$2,160.00
5.	8" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	38	\$42.60	\$1,618.80	\$45.00	\$1,710.00	\$55.00	\$2,090.00	\$95.00	\$3,610.00
6.	10" PVC WATER LINE, C-900, DR 18, CLASS 235, INCLUDES FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	607	\$49.60	\$30,107.20	\$51.00	\$30,957.00	\$55.00	\$33,385.00	\$55.00	\$33,385.00
7.	10" PVC RESTRAINED JOINT WATER LINE, C-900, DR 14, CLASS 305, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	78	\$119.50	\$9,321.00	\$67.00	\$5,226.00	\$145.00	\$11,310.00	\$200.00	\$15,600.00
8.	10" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	381	\$66.90	\$25,488.90	\$67.00	\$25,527.00	\$80.00	\$30,480.00	\$115.00	\$43,815.00
9.	12" PVC RESTRAINED JOINT WATER LINE, C-900, DR 18, CLASS 235, INCLUDES RESTRAINED JOINT FITTINGS, BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	405	\$87.70	\$35,518.50	\$95.00	\$38,475.00	\$110.00	\$44,550.00	\$150.00	\$60,750.00
10.	4" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	1	\$1,317.00	\$1,317.00	\$1,139.00	\$1,139.00	\$1,400.00	\$1,400.00	\$1,100.00	\$1,100.00
11.	8" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	4	\$2,158.00	\$8,632.00	\$2,075.00	\$8,300.00	\$2,300.00	\$9,200.00	\$1,900.00	\$7,600.00
12.	10" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	3	\$3,140.50	\$9,421.50	\$3,162.00	\$9,486.00	\$3,400.00	\$10,200.00	\$2,900.00	\$8,700.00
13.	12" AWWA GATE VALVE & BOX, COMPLETE IN PLACE	EA	1	\$3,783.50	\$3,783.50	\$3,875.00	\$3,875.00	\$4,000.00	\$4,000.00	\$3,600.00	\$3,600.00
14.	12" AWWA GATE VALVE & BOX WITH RESTRAINED JOINTS, COMPLETE IN PLACE	EA	2	\$3,783.50	\$7,567.00	\$4,234.00	\$8,468.00	\$4,100.00	\$8,200.00	\$4,100.00	\$8,200.00
15.	FLUSHING VALVE UNIT, INCLUDES APPROPRIATE TEE, FITTINGS, 6" GATE VALVE & BOX, AND LEAD PIPE, ALL DEPTHS, COMPLETE IN PLACE	EA	8	\$5,962.00	\$47,696.00	\$6,182.00	\$49,456.00	\$6,700.00	\$53,600.00	\$5,100.00	\$40,800.00
16.	LONG SIDE DOUBLE OR SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9) WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	33	\$1,788.00	\$59,004.00	\$1,898.00	\$62,634.00	\$1,950.00	\$64,350.00	\$1,450.00	\$47,850.00
17.	SHORT SIDE DOUBLE OR SINGLE SERVICE, 1" (CTS POLYETHYLENE, SDR-9), WATER SERVICE INCLUDES METER BOX, CURB STOP, ALL NECESSARY CONNECTORS AND TAPS, COMPLETE IN PLACE	EA	25	\$1,063.50	\$26,587.50	\$996.00	\$24,900.00	\$1,000.00	\$25,000.00	\$1,000.00	\$25,000.00
18.	PLUG & CLAMP WITH 2" BLOW-OFF VALVE & BOX ASSEMBLY, ALL SIZES, COMPLETE IN PLACE	EA	2	\$1,150.00	\$2,300.00	\$1,554.00	\$3,108.00	\$1,400.00	\$2,800.00	\$1,500.00	\$3,000.00
19.	WET CONNECTION OF PROPOSED 8" WATER LINE TO EXISTING WATER LINE, INCLUDES FITTINGS, ALL ADAPTERS AND CONNECTORS NECESSARY, AND REMOVAL OF EXISTING PLUG & CLAMP AND 2" BLOW-OFF VALVE & BOX, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$607.80	\$607.80	\$1,542.00	\$1,542.00	\$500.00	\$500.00	\$1,500.00	\$1,500.00
20.	WET CONNECTION OF PROPOSED 10" WATER LINE TO EXISTING WATER LINE, INCLUDES FITTINGS, ALL ADAPTERS AND CONNECTORS NECESSARY, AND REMOVAL OF EXISTING PLUG & CLAMP AND 2" BLOW-OFF VALVE & BOX, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$810.40	\$810.40	\$1,902.00	\$1,902.00	\$600.00	\$600.00	\$1,700.00	\$1,700.00

BID TABULATION FOR:

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILDTREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LIA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) LEXTON CONSTRUCTION, LLC		2) TEXASITE, LLC		3) R CONSTRUCTION CIVIL, LLC		4) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
21.	WET CONNECTION OF PROPOSED 12" WATER LINE TO EXISTING WATER LINE, INCLUDES FITTINGS, ALL ADAPTERS AND CONNECTORS NECESSARY, AND REMOVAL OF EXISTING PLUG & CLAMP AND 2" BLOW-OFF VALVE & BOX, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$911.70	\$911.70	\$2,262.00	\$2,262.00	\$700.00	\$700.00	\$1,800.00	\$1,800.00
22.	TRENCH SAFETY SYSTEM FOR WATER LINE, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	6084	\$0.10	\$608.40	\$1.00	\$6,084.00	\$0.10	\$608.40	\$1.00	\$6,084.00
SUBTOTAL BASE BID WATER ITEMS					\$371,912.70		\$389,465.00		\$412,283.40		\$426,824.00
BASE BID SANITARY SEWER ITEMS											
1.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 0' - 8' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	751	\$42.60	\$31,992.60	\$45.00	\$33,795.00	\$46.00	\$34,546.00	\$60.00	\$45,060.00
2.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 8' - 12' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	1284	\$43.60	\$55,982.40	\$50.00	\$64,200.00	\$47.00	\$60,348.00	\$65.00	\$83,460.00
3.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 12' - 16' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	1006	\$46.10	\$46,376.60	\$55.00	\$55,330.00	\$48.00	\$48,288.00	\$70.00	\$70,420.00
4.	8" PVC SEWER PIPE, ASTM D-3034, SDR 26, 16' - 20' CUT, INCLUDES BEDDING AND BACKFILL, COMPLETE IN PLACE	LF	272	\$50.70	\$13,790.40	\$60.00	\$16,320.00	\$50.00	\$13,600.00	\$115.00	\$31,280.00
5.	STANDARD 4' DIAMETER PRECAST SANITARY SEWER MANHOLE, (0' - 8' DEPTH), INCLUDES ADJUSTMENTS, COMPLETE IN PLACE	EA	19	\$3,930.50	\$74,679.50	\$3,060.00	\$58,140.00	\$2,700.00	\$51,300.00	\$3,300.00	\$62,700.00
6.	EXTRA VERTICAL DEPTH FOR 4' DIAMETER SANITARY SEWER MANHOLE (OVER 8' DEPTH), COMPLETE IN PLACE	VF	49	\$238.10	\$11,666.90	\$198.00	\$9,702.00	\$200.00	\$9,800.00	\$330.00	\$16,170.00
7.	SHORT SIDE SINGLE 6" PVC PIPE SERVICE LEAD, ASTM D-2241, SDR 26, INCLUDES PIPE, CEMENT STABILIZED SAND BACKFILL, DROP STRUCTURE, STACK, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ALL DEPTHS, COMPLETE IN PLACE	EA	27	\$1,555.00	\$41,985.00	\$1,600.00	\$43,200.00	\$1,800.00	\$48,600.00	\$2,200.00	\$59,400.00
8.	LONG SIDE DOUBLE OR SINGLE 6" PVC PIPE SERVICE LEAD, ASTM D-2241, SDR 26, INCLUDES PIPE, CEMENT STABILIZED SAND BACKFILL, DROP STRUCTURE, STACK, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ALL DEPTHS, COMPLETE IN PLACE	EA	18	\$3,039.00	\$54,702.00	\$3,500.00	\$63,000.00	\$3,200.00	\$57,600.00	\$4,800.00	\$86,400.00
9.	LONG SIDE DOUBLE OR SINGLE 8" PVC PIPE SERVICE LEAD, ASTM D-2241, SDR 26, INCLUDES PIPE, CEMENT STABILIZED SAND BACKFILL, DROP STRUCTURE, STACK, RISER, WYE, PLUG, MARKER, AND ANY NECESSARY FITTINGS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$5,951.50	\$5,951.50	\$3,678.00	\$3,678.00	\$3,800.00	\$3,800.00	\$6,000.00	\$6,000.00
10.	STANDARD SANITARY SEWER DROP STRUCTURE, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	EA	4	\$805.40	\$3,221.60	\$745.00	\$2,980.00	\$550.00	\$2,200.00	\$1,100.00	\$4,400.00
11.	STANDARD DROP STRUCTURE ON EXISTING SANITARY SEWER MANHOLE FOR ALL PIPE SIZES, INCLUDES CORE INTO MANHOLE, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$805.40	\$1,610.80	\$1,026.00	\$2,052.00	\$1,900.00	\$3,800.00	\$2,300.00	\$4,600.00
12.	CORE INTO EXISTING SANITARY SEWER MANHOLE AND CONNECT PROPOSED 8" SANITARY SEWER LINE, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$1,570.00	\$3,140.00	\$2,262.00	\$4,524.00	\$1,800.00	\$3,600.00	\$2,800.00	\$5,600.00
13.	ADDITIONAL COST FOR WATER AND SANITARY SEWER CROSSINGS, ALL DEPTHS, INCLUDES UPGRADE TO 18" SECTION FOR RESTRAINED JOINT AWWA C900 DR 18 PIPE FOR BOTH WATER AND SANITARY SEWER LINES WHERE APPLICABLE AND RESTRAINED JOINT FITTINGS, INCLUDES CEMENT STABILIZED SAND BACKFILL, COMPLETE IN PLACE	EA	6	\$217.80	\$1,306.80	\$100.00	\$600.00	\$1,500.00	\$9,000.00	\$1,550.00	\$9,300.00
14.	TRENCH SAFETY SYSTEM FOR SANITARY SEWER, INCLUDES ALL LATERAL LEADS, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	4641	\$1.00	\$4,641.00	\$1.00	\$4,641.00	\$0.10	\$464.10	\$1.00	\$4,641.00
SUBTOTAL BASE BID SANITARY SEWER ITEMS					\$351,047.10		\$362,162.00		\$346,946.10		\$489,431.00

BID TABULATION FOR:

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILD TREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) LEXTON CONSTRUCTION, LLC		2) TEXASITE, LLC		3) R CONSTRUCTION CIVIL, LLC		4) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
BASE BID DRAINAGE ITEMS											
1.	18" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	18	\$76.00	\$1,368.00	\$73.00	\$1,314.00	\$83.00	\$1,494.00	\$100.00	\$1,800.00
2.	24" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	1609	\$92.20	\$148,349.80	\$94.00	\$151,246.00	\$105.00	\$168,945.00	\$110.00	\$176,990.00
3.	30" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	356	\$113.50	\$40,406.00	\$116.00	\$41,296.00	\$128.00	\$45,568.00	\$135.00	\$48,060.00
4.	36" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	448	\$155.00	\$69,440.00	\$160.00	\$71,680.00	\$175.00	\$78,400.00	\$180.00	\$80,640.00
5.	48" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	499	\$238.10	\$118,811.90	\$250.00	\$124,750.00	\$260.00	\$129,740.00	\$280.00	\$139,720.00
6.	54" RCP STORM SEWER, ASTM C-76, CLASS III, INCLUDES BEDDING AND BACKFILL, ALL DEPTHS, COMPLETE IN PLACE	LF	708	\$338.40	\$239,587.20	\$370.00	\$261,960.00	\$370.00	\$261,960.00	\$385.00	\$272,580.00
7.	REINFORCED CONCRETE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	24	\$2,938.00	\$70,512.00	\$3,720.00	\$89,280.00	\$3,500.00	\$84,000.00	\$3,400.00	\$81,600.00
8.	REINFORCED CONCRETE TYPE "C" MANHOLE FOR 48" STORM SEWER AND LARGER, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	7	\$3,637.00	\$25,459.00	\$5,280.00	\$36,960.00	\$6,900.00	\$48,300.00	\$8,700.00	\$60,900.00
9.	REINFORCED CONCRETE TYPE "C" MANHOLE FOR 48" STORM SEWER AND LARGER WITH REINFORCED CONCRETE TYPE "E" INLET TOP, ALL SIDES OPEN, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	3	\$4,153.50	\$12,460.50	\$5,760.00	\$17,280.00	\$7,500.00	\$22,500.00	\$9,600.00	\$28,800.00
10.	REINFORCED CONCRETE TYPE "C" MANHOLE FOR 42" STORM SEWER AND SMALLER WITH REINFORCED CONCRETE TYPE "E" INLET TOP, ALL SIDES OPEN, INCLUDES ADJUSTMENTS, ALL DEPTHS, COMPLETE IN PLACE	EA	2	\$3,986.50	\$7,973.00	\$4,200.00	\$8,400.00	\$5,000.00	\$10,000.00	\$4,800.00	\$9,600.00
11.	STAGE I - REINFORCED CONCRETE TYPE "C" INLET, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	14	\$1,464.00	\$20,496.00	\$1,920.00	\$26,880.00	\$1,300.00	\$18,200.00	\$1,650.00	\$23,100.00
12.	STAGE II - REINFORCED CONCRETE TYPE "C" INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	14	\$1,975.50	\$27,657.00	\$1,920.00	\$26,880.00	\$2,900.00	\$40,600.00	\$2,100.00	\$29,400.00
13.	STAGE I - REINFORCED CONCRETE TYPE "C-1" INLET FOR STORM SEWERS 48" AND LARGER, INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	4	\$2,021.00	\$8,084.00	\$3,360.00	\$13,440.00	\$4,500.00	\$18,000.00	\$1,800.00	\$7,200.00
14.	STAGE I - MODIFIED TYPE REINFORCED CONCRETE "C-1" INLET, (10' MINIMUM INSIDE OPENING), INCLUDES INLET PROTECTION BARRIER FOR STAGE I INLET, ALL DEPTHS, COMPLETE IN PLACE	EA	3	\$1,464.00	\$4,392.00	\$1,920.00	\$5,760.00	\$1,700.00	\$5,100.00	\$2,200.00	\$6,600.00
15.	STAGE II - MODIFIED REINFORCED CONCRETE TYPE "C-1" INLET, (10' MINIMUM INSIDE OPENING), ALL DEPTHS, COMPLETE IN PLACE	EA	7	\$2,760.50	\$19,323.50	\$3,000.00	\$21,000.00	\$2,900.00	\$20,300.00	\$2,500.00	\$17,500.00
16.	8" BRICK PLUG FOR 18" RCP STORM SEWER, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$506.50	\$506.50	\$702.00	\$702.00	\$600.00	\$600.00	\$1,000.00	\$1,000.00
17.	WING WALLS FOR 30" RCP STORM SEWER PER TXDOT DETAILS, INCLUDES HEADWALL AND APRON, COMPLETE IN PLACE	EA	1	\$2,532.50	\$2,532.50	\$5,400.00	\$5,400.00	\$7,800.00	\$7,800.00	\$20,000.00	\$20,000.00
18.	CONNECT PROPOSED 54" STORM SEWER TO EXISTING 54" STORM SEWER, INCLUDES ALL NECESSARY CONNECTIONS, ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$217.80	\$217.80	\$1,062.00	\$1,062.00	\$750.00	\$750.00	\$1,200.00	\$1,200.00
19.	18" THICK CONCRETE RIP RAP, INCLUDES GEOTEXTILE FABRIC, COMPLETE IN PLACE	SY	35	\$146.90	\$5,141.50	\$132.00	\$4,620.00	\$160.00	\$5,600.00	\$230.00	\$8,050.00
20.	REGRADE AND RE-ESTABLISH CREEK BANK, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	LS	1	\$253.30	\$253.30	\$100.00	\$100.00	\$2,500.00	\$2,500.00	\$10,000.00	\$10,000.00

BID TABULATION FOR:

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILD TREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) LEXTON CONSTRUCTION, LLC		2) TEXASITE, LLC		3) R CONSTRUCTION CIVIL, LLC		4) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
21.	TRENCH SAFETY SYSTEM FOR STORM SEWER, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE	LF	3638	\$1.00	\$3,638.00	\$1.00	\$3,638.00	\$0.10	\$363.80	\$1.00	\$3,638.00
SUBTOTAL BASE BID DRAINAGE ITEMS					\$826,609.50		\$913,648.00		\$970,720.80		\$1,028,378.00
BASE BID MISCELLANEOUS WS&D ITEMS											
1.	HAUL UTILITY SPOILS TO DESIGNATED DISPOSAL SITE, USING OFF ROAD TRUCKS, (0.5 - 1 MILE), INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	CY	5100	\$7.40	\$37,740.00	\$3.60	\$18,360.00	\$5.20	\$26,520.00	\$0.50	\$2,550.00
2.	HAUL UTILITY SPOILS TO DESIGNATED DISPOSAL SITE, USING ON ROAD TRUCKS, (0.5 - 1 MILE), INCLUDES STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LS	1	\$37,715.50	\$37,715.50	\$61,200.00	\$61,200.00	\$28,000.00	\$28,000.00	\$5,000.00	\$5,000.00
3.	DUST CONTROL, INCLUDES PROCUREMENT OF WATER, (AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LS	1	\$5,571.50	\$5,571.50	\$1,200.00	\$1,200.00	\$20,000.00	\$20,000.00	\$6,000.00	\$6,000.00
4.	CLEARING AND GRUBBING, INCLUDES ROOT RAKING AND BACK DRAGGING, AND OFFSITE DISPOSAL OF CLEARED AND GRUBBED MATERIAL, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	2	\$15,100.00	\$30,200.00	\$500.00	\$1,000.00	\$10,000.00	\$20,000.00	\$8,000.00	\$16,000.00
5.	EXTRA CEMENT STABILIZED SAND BACKFILL, (2 SACKS PER CY), (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	CY	15	\$30.00	\$450.00	\$30.00	\$450.00	\$30.00	\$450.00	\$30.00	\$450.00
6.	ADJUST EXISTING MANHOLE RIM, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	1	\$250.00	\$250.00	\$1.00	\$1.00	\$500.00	\$500.00	\$750.00	\$750.00
7.	DEWATERING FOR UTILITY LINES, ALL LINE SIZES, DEPTH 0'-16' (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	272	\$20.00	\$5,440.00	\$20.00	\$5,440.00	\$20.00	\$5,440.00	\$20.00	\$5,440.00
8.	DEWATERING FOR UTILITY LINES, ALL LINE SIZES, DEPTH 16' AND GREATER (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE	LF	3041	\$50.00	\$152,050.00	\$50.00	\$152,050.00	\$50.00	\$152,050.00	\$50.00	\$152,050.00
9.	ADDITIONAL DUCTILE IRON FITTINGS, ALL DEPTHS, COMPLETE IN PLACE	TON	0.01	\$10,000.00	\$100.00	\$10,000.00	\$100.00	\$10,000.00	\$100.00	\$10,000.00	\$100.00
10.	EXTRA COST OF WET SAND CONSTRUCTION UNDER MANHOLE, (AS DIRECTED BY ENGINEER), ALL DEPTHS, COMPLETE IN PLACE	EA	1	\$50.00	\$50.00	\$50.00	\$50.00	\$500.00	\$500.00	\$50.00	\$50.00
11.	EXTRA COST OF STORM SEWER WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	100	\$5.00	\$500.00	\$5.00	\$500.00	\$5.00	\$500.00	\$5.00	\$500.00
12.	EXTRA COST OF SANITARY SEWER WET SAND CONSTRUCTION, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	LF	50	\$5.00	\$250.00	\$5.00	\$250.00	\$5.00	\$250.00	\$5.00	\$250.00
13.	MAINTAIN EXISTING STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	1	\$2,125.00	\$2,125.00	\$200.00	\$200.00	\$1,500.00	\$1,500.00	\$3,000.00	\$3,000.00
14.	INSTALL FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	100	\$1.00	\$100.00	\$1.00	\$100.00	\$2.50	\$250.00	\$1.00	\$100.00
15.	EXTRA INLET PROTECTION BARRIER ON EXISTING INLET, COMPLETE IN PLACE	EA	1	\$10.00	\$10.00	\$10.00	\$10.00	\$60.00	\$60.00	\$10.00	\$10.00
16.	INSTALL, MAINTAIN, AND REMOVE CONCRETE TRUCK WASHOUT AREA, COMPLETE IN PLACE	EA	1	\$375.00	\$375.00	\$50.00	\$50.00	\$600.00	\$600.00	\$750.00	\$750.00
17.	INSTALL REINFORCED FILTER FABRIC FENCE (SILT BARRIER FENCING), COMPLETE IN PLACE	LF	100	\$1.00	\$100.00	\$1.00	\$100.00	\$60.00	\$6,000.00	\$1.00	\$100.00

BID TABULATION FOR:

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILDTREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) LEXTON CONSTRUCTION, LLC		2) TEXASITE, LLC		3) R CONSTRUCTION CIVIL, LLC		4) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
18.	BROADCAST SEEDING, INCLUDES FERTILIZING AND WATERING, TO ACHIEVE 90% HOMOGENEOUS GRASS COVERAGE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	1	\$450.00	\$450.00	\$450.00	\$450.00	\$750.00	\$750.00	\$450.00	\$450.00
19.	HYDROMULCH SEEDING AND FINE GRADING, INCLUDES WATERING, TO ACHIEVE 90% HOMOGENEOUS GRASS COVERAGE, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	AC	1	\$450.00	\$450.00	\$450.00	\$450.00	\$1,800.00	\$1,800.00	\$450.00	\$450.00
20.	STORMWATER POLLUTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE	LS	1	\$2,550.00	\$2,550.00	\$3,000.00	\$3,000.00	\$3,500.00	\$3,500.00	\$500.00	\$500.00
SUBTOTAL BASE BID MISCELLANEOUS WS&D ITEMS					\$276,477.00		\$244,961.00		\$268,770.00		\$194,500.00
ALTERNATE BID FOR PAVING PAVING ITEMS											
1.	ROADWAY AND LOT EXCAVATION, INCLUDES STRIPPING, STOCKPILING AND RE-APPLICATION OF STRIPPINGS TO APPLICABLE AREAS, COMPLETE IN PLACE	CY	4200	\$2.00	\$8,400.00	\$3.57	\$14,994.00	\$2.00	\$8,400.00	\$2.50	\$10,500.00
2.	EMBANKMENT, INCLUDES DEMUCKING, REMOVING AND DISPOSING OF EXISTING UNSUITABLE MATERIAL BEFORE PLACING FILL, HAULING, STRIPPING, STOCKPILING STRIPPINGS, PROOFROLLING, RE-APPLICATION OF STRIPPINGS TO FILL AREA, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND FINAL GRADING, COMPLETE IN PLACE	CY	4200	\$5.25	\$22,050.00	\$3.57	\$14,994.00	\$4.00	\$16,800.00	\$2.50	\$10,500.00
3.	FINAL LOT AND RESERVE GRADING, COMPLETE IN PLACE	LS	1	\$30,000.00	\$30,000.00	\$23,257.50	\$23,257.50	\$31,000.00	\$31,000.00	\$20,000.00	\$20,000.00
4.	DEMUCK AND FILL EXISTING DRAINAGE SWALE, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, COMPLETE IN PLACE	LF	515	\$44.00	\$22,660.00	\$29.14	\$15,007.10	\$3.00	\$1,545.00	\$9.00	\$4,635.00
5.	EXCAVATION AND GRADING OF DRAINAGE SWALE, 4:1 MINIMUM SIDE SLOPE - 2' BOTTOM, (0'-2' DEPTHS), INCLUDES HAULING OF SPOIL MATERIAL, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	105	\$7.15	\$750.75	\$11.92	\$1,251.60	\$10.00	\$1,050.00	\$12.00	\$1,260.00
6.	EXCAVATION AND GRADING OF DRAINAGE SWALE, 4:1 MINIMUM SIDE SLOPE - V-BOTTOM, (0'-2' DEPTHS), INCLUDES HAULING OF SPOIL MATERIAL, STRIPPING, STOCKPILING STRIPPINGS, PLACEMENT AND COMPACTION TO 95% STANDARD PROCTOR DENSITY, WITH MAXIMUM 8" LIFTS, AND RE-APPLICATION OF STRIPPINGS, COMPLETE IN PLACE	LF	105	\$7.15	\$750.75	\$11.92	\$1,251.60	\$10.00	\$1,050.00	\$12.00	\$1,260.00
7.	6" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	SY	11465	\$53.25	\$610,511.25	\$54.60	\$625,989.00	\$53.50	\$613,377.50	\$69.00	\$791,085.00
8.	6" LIME/FLY ASH STABILIZED SUBGRADE MANIPULATION, COMPLETE IN PLACE	SY	13010	\$3.85	\$50,088.50	\$4.20	\$54,642.00	\$3.95	\$51,389.50	\$8.00	\$104,080.00
9.	LIME FOR 6" STABILIZED SUBGRADE PREPARATION, 23 LBS/SY, AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	150	\$395.00	\$59,250.00	\$383.25	\$57,487.50	\$340.00	\$51,000.00	\$395.00	\$59,250.00
10.	FLY ASH FOR 6" STABILIZED SUBGRADE PREPARATION, 33 LBS/SY, AS REQUIRED BY SOIL CONDITIONS AND APPROVED BY GEOTECHNICAL ENGINEER, COMPLETE IN PLACE	TON	215	\$141.00	\$30,315.00	\$141.75	\$30,476.25	\$165.00	\$35,475.00	\$250.00	\$53,750.00
11.	CONNECT PROPOSED 6" REINFORCED CONCRETE PAVEMENT TO EXISTING REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	LF	56	\$19.00	\$1,064.00	\$26.25	\$1,470.00	\$45.00	\$2,520.00	\$60.00	\$3,360.00
12.	4" X 12" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	4867	\$3.70	\$18,007.90	\$3.94	\$19,175.98	\$3.95	\$19,224.65	\$5.00	\$24,335.00
13.	6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	LF	2021	\$3.70	\$7,477.70	\$3.94	\$7,962.74	\$3.95	\$7,982.95	\$5.00	\$10,105.00
14.	EA - ADA COMPLIANT TYPE 7 CONCRETE CURB RAMP, INCLUDES TRUNCATED DOME PAVERS WITH CONTRASTING COLOR PER DETAIL, COMPLETE IN PLACE	EA	10	\$1,600.00	\$16,000.00	\$1,680.00	\$16,800.00	\$2,200.00	\$22,000.00	\$1,900.00	\$19,000.00

BID TABULATION FOR:

**CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES & PAVING AND APPURTENANCES TO SERVE WILD TREE SECTION 4
MONTGOMERY-GRIMES COUNTIES MUNICIPAL UTILITY DISTRICT NO. 146B
CITY OF MONTGOMERY, MONTGOMERY COUNTY, TEXAS
JANUARY 07, 2025
LJA ENGINEERING, INC.
A. GUIJOSA
JANUARY 07, 2025
3141-3007 & 3141-3008 (9.2)**

**BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.**

NO.	ITEM DESCRIPTION	UNIT	QTY	1) LEXTON CONSTRUCTION, LLC		2) TEXASITE, LLC		3) R CONSTRUCTION CIVIL, LLC		4) CE BARKER LTD.	
				UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL	UNIT COST	TOTAL
15.	PERMANENT TRAFFIC CONTROL DEVICES, INCLUDES ALL TRAFFIC BUTTONS, PAVEMENT STRIPING, MARKERS, REFLECTIVE PAINT ON MEDIAN NOSES, STREET SIGNS, TRAFFIC SIGNS, ETC., COMPLETE IN PLACE	LS	1	\$6,500.00	\$6,500.00	\$12,600.00	\$12,600.00	\$10,000.00	\$10,000.00	\$20,000.00	\$20,000.00
16.	4" SQUARE DOUBLE REFLECTORIZED BLUE TRAFFIC BUTTONS FOR FLUSHING VALVE LOCATION, COMPLETE IN PLACE	EA	8	\$19.00	\$152.00	\$18.11	\$144.88	\$15.00	\$120.00	\$30.00	\$240.00
17.	EXTRA TRAFFIC CONTROL SIGNS, (AS DIRECTED BY ENGINEER), COMPLETE IN PLACE	EA	1	\$1,000.00	\$1,000.00	\$1,102.50	\$1,102.50	\$950.00	\$950.00	\$1,000.00	\$1,000.00
18.	METAL BEAM GUARD FENCE, INCLUDES DOWNSTREAM ANCHOR TERMINAL GF-31 (22), COMPLETE IN PLACE	LF	50	\$153.80	\$7,690.00	\$304.50	\$15,225.00	\$165.00	\$8,250.00	\$600.00	\$30,000.00
19.	6" PVC IRRIGATION SLEEVE, SCHEDULE 40, INCLUDES RISERS, PVC END CAPS, CEMENT STABILIZED SAND BACKFILL AND MARKERS, COMPLETE IN PLACE	LF	32	\$26.00	\$832.00	\$36.75	\$1,176.00	\$55.00	\$1,760.00	\$40.00	\$1,280.00
20.	REMOVE AND OFFSITE DISPOSAL OF EXISTING TYPE III BARRICADE, COMPLETE IN PLACE	EA	2	\$25.00	\$50.00	\$26.25	\$52.50	\$100.00	\$200.00	\$650.00	\$1,300.00
SUBTOTAL ALTERNATE BID FOR PAVING PAVING ITEMS					\$893,549.85		\$915,060.15		\$884,094.60		\$1,166,940.00

BID SUMMARY

BASE BID WATER ITEMS	\$371,912.70	\$389,465.00	\$412,283.40	\$426,824.00
BASE BID SANITARY SEWER ITEMS	\$351,047.10	\$362,162.00	\$346,946.10	\$489,431.00
BASE BID DRAINAGE ITEMS	\$826,609.50	\$913,648.00	\$970,720.80	\$1,028,378.00
BASE BID MISCELLANEOUS WS&D ITEMS	\$276,477.00	\$244,961.00	\$268,770.00	\$194,500.00
TOTAL AMOUNT BASE BID	\$1,826,046.30	\$1,910,236.00	\$1,998,720.30	\$2,139,133.00

ALTERNATE BID FOR PAVING

TOTAL AMOUNT BASE BID	\$1,826,046.30	\$1,910,236.00	\$1,998,720.30	\$2,139,133.00
PAVING ITEMS	\$893,549.85	\$915,060.15	\$884,094.60	\$1,166,940.00
TOTAL ALTERNATE BID FOR PAVING PLUS BASE BID	\$2,719,596.15	\$2,825,296.15	\$2,882,814.90	\$3,306,073.00