

BID TABULATION FOR:

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
& PAVING AND APPURTENANCES TO SERVE VIA PRINCIPALE PARKWAY
EAST MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 5
CITY OF HOUSTON, E.T.J., MONTGOMERY COUNTY, TEXAS
MARCH 19, 2021
LJA ENGINEERING, INC.
A.CAROTHERS
MARCH 19, 2021
6969-1018A & 6967-1018A (9.2)

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

BIDDER'S NAME


- 1) C.E. BARKER, LTD.
- 2) TRIPLE B SERVICES, LLP

**TOTAL BID
AMOUNT**

\$1,195,248.65
\$1,369,932.89

CALENDAR DAYS - 65/75

LJA Engineering, Inc.



3/22/2021

I, Justin Graham, PE., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 & PAVING AND APPURTENANCES TO SERVE VIA PRINCIPALE PARKWAY
 EAST MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF HOUSTON, E.T.J., MONTGOMERY COUNTY, TEXAS
 MARCH 19, 2021
 LJA ENGINEERING, INC.
 A.CAROTHERS
 MARCH 19, 2021
 6969-1018A & 6967-1018A (9.2)

| ITEM | DESCRIPTION | UNIT | QTY | 1) C.E. BARKER, LTD. | | 2) TRIPLE B SERVICES, LLP | |
|-----------------------------|---|------|-------|----------------------|---------------------|---------------------------|---------------------|
| | | | | UNIT COST | TOTAL COST | UNIT COST | TOTAL COST |
| WATER ITEMS | | | | | | | |
| 1. | 12" P.V.C. WATER PIPE, C-900, DR 18, CL 235, ALL DEPTHS, COMPLETE IN PLACE | LF | 1,751 | \$34.89 | \$61,092.39 | \$46.00 | \$80,546.00 |
| 2. | 12" P.V.C. WATER PIPE, C-900, DR-14, CLASS 305, RESTRAINED JOINT, ALL DEPTHS, COMPLETE IN PLACE | LF | 669 | \$67.91 | \$45,431.79 | \$65.00 | \$43,485.00 |
| 3. | 8" P.V.C. WATER PIPE, C-900, DR 18, CL 235, RESTRAINED JOINT, ALL DEPTHS, COMPLETE IN PLACE | LF | 334 | \$28.97 | \$9,675.98 | \$28.00 | \$9,352.00 |
| 4. | FIRE HYDRANT UNIT, ALL DEPTHS, INCLUDES APPROPRIATE TEE, 6" GATE VALVE & BOX, 6" LEAD AND FIRE HYDRANT AND TRENCH SAFETY, COMPLETE IN PLACE | EA | 10 | \$3,856.69 | \$38,566.90 | \$4,950.00 | \$49,500.00 |
| 5. | 12" AWWA GATE VALVE AND BOX, COMPLETE IN PLACE | EA | 4 | \$2,286.51 | \$9,146.04 | \$2,875.00 | \$11,500.00 |
| 6. | 8" AWWA GATE VALVE AND BOX, COMPLETE IN PLACE | EA | 1 | \$1,337.36 | \$1,337.36 | \$1,650.00 | \$1,650.00 |
| 7. | CAST IRON FITTINGS, COMPLETE IN PLACE | TON | 0.76 | \$3,109.59 | \$2,363.29 | \$2,650.00 | \$2,014.00 |
| 8. | REMOVE PLUG & CLAMP AND BLOW-OFF VALVE AND CONNECT PROPOSED WATER, ALL SIZES (WET CONNECT), COMPLETE IN PLACE | EA | 3 | \$873.13 | \$2,619.39 | \$1,030.00 | \$3,090.00 |
| 9. | 12" PLUG AND CLAMP, WITH 2" BLOW-OFF VALVE AND BOX, COMPLETE IN PLACE | EA | 2 | \$601.45 | \$1,202.90 | \$1,720.00 | \$3,440.00 |
| 10. | 8" PLUG AND CLAMP, WITH 2" BLOW-OFF VALVE AND BOX, COMPLETE IN PLACE | EA | 1 | \$497.19 | \$497.19 | \$1,600.00 | \$1,600.00 |
| 11. | TRENCH SAFETY SYSTEM, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE | LF | 3,456 | \$0.14 | \$483.84 | \$0.01 | \$34.56 |
| 12. | AUGER SECTION FOR 12" WATER LINE, (DOES NOT INCLUDE CARRIER PVC PIPE), COMPLETE IN PLACE | LF | 77 | \$67.86 | \$5,225.22 | \$69.50 | \$5,351.50 |
| 13. | 6" P.V.C. N.P.W. (PURPLE PIPE), C-900, DR 18, CLASS 235, ALL DEPTHS, COMPLETE IN PLACE | LF | 722 | \$14.01 | \$10,115.22 | \$27.00 | \$19,494.00 |
| 14. | 6" P.V.C. N.P.W. (PURPLE PIPE), C-900, DR 18, CLASS 235, RESTRAINED JOINT, ALL DEPTHS, COMPLETE IN PLACE | LF | 57 | \$20.70 | \$1,179.90 | \$28.00 | \$1,596.00 |
| SUBTOTAL WATER ITEMS | | | | | \$188,937.41 | | \$232,653.06 |
| SANITARY SEWER ITEMS | | | | | | | |
| 1. | 8" P.V.C. GREEN SEWER PIPE, ASTM D-2241, SDR 26, 8'-12' DEPTH, COMPLETE IN PLACE | LF | 28 | \$31.65 | \$886.20 | \$46.00 | \$1,288.00 |
| 2. | 8" P.V.C. GREEN SEWER PIPE, ASTM D-2241, SDR 26, 12'-16' DEPTH, COMPLETE IN PLACE | LF | 829 | \$35.83 | \$29,703.07 | \$50.55 | \$41,905.95 |
| 3. | STANDARD SANITARY SEWER MANHOLE FOR 6"-24" SANITARY SEWER PIPES, (8' DEPTH), INCLUDES INFLOW PREVENTER, COMPLETE IN PLACE | EA | 4 | \$1,854.08 | \$7,416.32 | \$4,385.00 | \$17,540.00 |
| 4. | EXTRA DEPTH OF SANITARY MANHOLE, (OVER 8' DEPTH), COMPLETE IN PLACE | VF | 19.2 | \$148.41 | \$2,849.47 | \$163.00 | \$3,129.60 |
| 5. | T.V. INSPECTION OF SANITARY SEWER LINES, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | LF | 710 | \$0.01 | \$7.10 | \$2.00 | \$1,420.00 |
| 6. | TRENCH SAFETY SYSTEM, ALL DEPTHS, COMPLETE IN PLACE | LF | 857 | \$0.14 | \$119.98 | \$0.01 | \$8.57 |
| 7. | DEWATERING FOR SANITARY SEWER, ALL SIZES, ALL DEPTHS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE | LF | 710 | \$20.00 | \$14,200.00 | \$20.00 | \$14,200.00 |
| 8. | ADDITIONAL COST FOR MODIFIED "A-A" BEDDING FOR WET SAND CONSTRUCTION, ALL DEPTHS, ALL SIZES, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE | LF | 710 | \$12.00 | \$8,520.00 | \$12.00 | \$8,520.00 |
| 9. | CORE INTO EXISTING SANITARY MANHOLE INCLUDES ALL NECESSARY CONNECTORS, ADAPTERS, FITTINGS, COMPLETE IN PLACE | EA | 1 | \$1,134.44 | \$1,134.44 | \$3,430.00 | \$3,430.00 |
| 10. | STANDARD SANITARY SEWER DROP AT MANHOLE, (2.0' DEPTH), COMPLETE IN PLACE | EA | 1 | \$1,178.85 | \$1,178.85 | \$1,000.00 | \$1,000.00 |

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 & PAVING AND APPURTENANCES TO SERVE VIA PRINCIPALE PARKWAY
 EAST MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF HOUSTON, E.T.J., MONTGOMERY COUNTY, TEXAS
 MARCH 19, 2021
 LJA ENGINEERING, INC.
 A.CAROTHERS
 MARCH 19, 2021
 6969-1018A & 6967-1018A (9.2)

| ITEM | DESCRIPTION | UNIT | QTY | 1) C.E. BARKER, LTD. | | 2) TRIPLE B SERVICES, LLP | |
|--------------------------------------|---|------|-------|----------------------|--------------------|---------------------------|--------------------|
| | | | | UNIT COST | TOTAL COST | UNIT COST | TOTAL COST |
| 11. | EXTRA DEPTH ON SANITARY SEWER DROP, (OVER 2' DEPTH), COMPLETE IN PLACE | VF | 5.93 | \$49.50 | \$293.54 | \$9.00 | \$53.37 |
| 12. | AUGER SECTION FOR 8" SANITARY SEWER, COMPLETE IN PLACE | LF | 77 | \$91.81 | \$7,069.37 | \$68.00 | \$5,236.00 |
| SUBTOTAL SANITARY SEWER ITEMS | | | | | \$73,378.34 | | \$97,731.49 |
| DRAINAGE FACILITIES ITEMS | | | | | | | |
| 1. | 24" R.C.P. STORM SEWER, ASTM C-76, CLASS III, ALL DEPTHS, COMPLETE IN PLACE | LF | 1,513 | \$65.98 | \$99,827.74 | \$85.00 | \$128,605.00 |
| 2. | 30" R.C.P. STORM, SEWER, ASTM C-76, CLASS III, ALL DEPTHS, COMPLETE IN PLACE | LF | 302 | \$81.40 | \$24,582.80 | \$115.00 | \$34,730.00 |
| 3. | 36" CORRUGATED GALVANIZED METAL PIPE (FULLY ASPHALT COATED 2 - 2/3" X 1/2" CORRUGATION, 12 GAGE OR HDPE EQUIVALENT), ALL DEPTHS, COMPLETE IN PLACE | LF | 69 | \$113.58 | \$7,837.02 | \$120.00 | \$8,280.00 |
| 4. | TYPE "C" MANHOLE FOR 42" STORM SEWERS AND SMALLER WITH TYPE "E" INLET ON TOP, ALL DEPTHS, COMPLETE IN PLACE | EA | 12 | \$3,020.63 | \$36,247.56 | \$3,375.00 | \$40,500.00 |
| 5. | DEWATERING, ALL SIZES, ALL DEPTHS, (THIS IS AN ESTIMATED QUANTITY TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | LF | 1,884 | \$20.00 | \$37,680.00 | \$20.00 | \$37,680.00 |
| 6. | ADDITIONAL COST FOR MODIFIED "A-A" BEDDING, (TO BE USED ONLY AT THE WRITTEN DIRECTION OF THE ENGINEER), ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE | LF | 1,884 | \$12.00 | \$22,608.00 | \$12.00 | \$22,608.00 |
| 7. | WATER, SANITARY SEWER, AND STORM SEWER UTILITY SPOIL TO BE HAULED UTILIZING OFF-ROAD TRUCKS TO A DESIGNATED STOCKPILE LOCATION WITHIN (0.5 MILE) OF THE PROJECT, PLACED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY, INCLUDES SITE PREP, ANY TEMPORARY TRAFFIC CONTROL, FLAGMEN, ETC., REQUIRED TO CROSS OR TRAVERSE EXISTING ROADWAYS, COMPLETE IN PLACE | CY | 3,075 | \$3.53 | \$10,854.75 | \$7.40 | \$22,755.00 |
| 8. | TRENCH SAFETY SYSTEM, ALL SIZES, ALL DEPTHS, COMPLETE IN PLACE | LF | 1,884 | \$0.14 | \$263.76 | \$0.01 | \$18.84 |
| 9. | OUTFALL STRUCTURE 4 INCLUDES 4" THICK REINFORCED CONCRETE SLOPE PAVING AND CRUSHED CONCRETE OR STONE RIP RAP, AND REDRESSING SIDE SLOPES, COMPLETE IN PLACE | EA | 1 | \$4,459.94 | \$4,459.94 | \$3,575.00 | \$3,575.00 |
| 10. | INSTALLATION MAINTENANCE AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, INCLUDES INSTALLATION AND REMOVAL, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE | EA | 1 | \$1,500.00 | \$1,500.00 | \$1,500.00 | \$1,500.00 |
| 11. | STORM WATER POLLUTION PREVENTION PLAN, INCLUDES CONTRACTOR'S BOOKLET NOI & NOT, COMPLETE IN PLACE | LS | 1 | \$732.62 | \$732.62 | \$1,100.00 | \$1,100.00 |
| 12. | REINFORCED FILTER FABRIC FENCE, SWMHCA SPECIFICATION NO. 4311, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | LF | 5,920 | \$1.55 | \$9,176.00 | \$1.60 | \$9,472.00 |
| 13. | METHOD "A" FULL CONSTRUCTION STAKING (BY GBI SURVEYING COORDINATE WITH JON BORDOVSKY: 281.499.4539), OWNER ONLY PROVIDES LIMITED CONTROL STAKING, COMPLETE IN PLACE | LS | 1 | \$6,903.00 | \$6,903.00 | \$6,903.00 | \$6,903.00 |
| 14. | TEMPORARY V - SHAPED DRAINAGE SWALE, COMPLETE IN PLACE | LF | 462 | \$7.93 | \$3,663.66 | \$11.00 | \$5,082.00 |
| 15. | BREAK INTO EXIST MANHOLE #D-20 AND CONNECT PROPOSED STORM SEWER, COMPLETE IN PLACE | EA | 1 | \$1,662.48 | \$1,662.48 | \$1,450.00 | \$1,450.00 |
| 16. | COFFER DAM WITH BY-PASS PUMPING FOR CONSTRUCTION OF OUTFALL STRUCTURE 4, COMPLETE IN PLACE | LS | 1 | \$7,326.15 | \$7,326.15 | \$21,000.00 | \$21,000.00 |
| 17. | RESHAPE HIGH BANK AND TOE FOR DRAINAGE CHANNEL TO ENSURE PROPER DRAINAGE, COMPLETE IN PLACE | LS | 1 | \$10,200.26 | \$10,200.26 | \$5,200.00 | \$5,200.00 |

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 & PAVING AND APPURTENANCES TO SERVE VIA PRINCIPALE PARKWAY
 EAST MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF HOUSTON, E.T.J., MONTGOMERY COUNTY, TEXAS
 MARCH 19, 2021
 LJA ENGINEERING, INC.
 A.CAROTHERS
 MARCH 19, 2021
 6969-1018A & 6967-1018A (9.2)

| ITEM | DESCRIPTION | UNIT | QTY | 1) C.E. BARKER, LTD. | | 2) TRIPLE B SERVICES, LLP | |
|---|---|------|-------|----------------------|---------------------|---------------------------|--------------|
| | | | | UNIT COST | TOTAL COST | UNIT COST | TOTAL COST |
| 18. | STAGE I – 10' PRECAST CURB INLET, ALL DEPTHS, (INCLUDES TEMPORARY SILT BARRIER FENCE FOR STAGE I INLET), COMPLETE IN PLACE | EA | 10 | \$1,414.52 | \$14,145.20 | \$2,235.00 | \$22,350.00 |
| 19. | STAGE II – 10' PRECAST CURB INLET, ALL DEPTHS, (INCLUDES TEMPORARY SAND FILLED BURLAP BAGS FOR EROSION AND SEDIMENT CONTROL), COMPLETE IN PLACE | EA | 10 | \$1,527.23 | \$15,272.30 | \$2,420.00 | \$24,200.00 |
| SUBTOTAL DRAINAGE FACILITIES ITEMS | | | | | \$314,943.24 | \$397,008.84 | |
| MISCELLANEOUS ITEMS | | | | | | | |
| 1. | EXTRA CEMENT STABILIZED SAND BACKFILL (2 SACKS PER TON), (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | CY | 1 | \$15.00 | \$15.00 | \$15.00 | \$15.00 |
| 2. | EXTRA COST OF SANITARY SEWER WET SAND CONSTRUCTION AS PER CITY OF HOUSTON DRAWING NO. 02317-01 OR 02317-02, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | LF | 1 | \$5.00 | \$5.00 | \$5.00 | \$5.00 |
| 3. | EXTRA COST OF STORM SEWER WET SAND CONSTRUCTION AS PER CITY OF HOUSTON DRAWING NO. 02317-02, ALL LINE SIZES AND DEPTHS, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | LF | 1 | \$5.00 | \$5.00 | \$5.00 | \$5.00 |
| 4. | EXTRA COST OF WET SAND CONSTRUCTION UNDER MANHOLE AS PER CITY OF HOUSTON DRAWING NO. 02082-05 (EFFECTIVE DATE ON OCTOBER 1, 2002 OR LATEST DETAIL), ALL DEPTHS, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | EA | 1 | \$50.00 | \$50.00 | \$50.00 | \$50.00 |
| 5. | ADJUST EXISTING MANHOLE RIM ELEVATION AS REQUIRED, (TO BE USED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE | EA | 1 | \$563.55 | \$563.55 | \$860.00 | \$860.00 |
| 6. | STORMWATER POLLUTION INSPECTION REPORTS CONDUCTED ON A WEEKLY BASIS ACCORDING TO TCEQ PERMIT, COMPLETE IN PLACE | LS | 1 | \$732.62 | \$732.62 | \$1,560.00 | \$1,560.00 |
| 7. | DEDUCT FOR DAMAGE TO TREES OUTSIDE CLEARING LIMITS OR MARKED FOR PRESERVATION, COMPLETE IN PLACE | EA | 0 | (\$1,000.00) | \$0.00 | \$1,000.00 | \$0.00 |
| SUBTOTAL MISCELLANEOUS ITEMS | | | | | \$1,371.17 | \$2,495.00 | |
| VIA PRINCIPALE PARKWAY PHASE II PAVING ITEMS | | | | | | | |
| 1. | 7" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE | SY | 8,580 | \$49.17 | \$421,878.60 | \$50.60 | \$434,148.00 |
| 2. | 6" REINFORCED CONCRETE CURB, COMPLETE IN PLACE | LF | 4,819 | \$3.80 | \$18,312.20 | \$4.50 | \$21,685.50 |
| 3. | 6" LIME/FLY-ASH STABILIZED SUBGRADE, COMPLETE IN PLACE | SY | 9,650 | \$2.97 | \$28,660.50 | \$3.60 | \$34,740.00 |
| 4. | TRU BLN LIME/FLY ASH MIXTURE FOR SUBGRADE PREPARATION (2% LIME BY WEIGHT, 10LB/SY AND 8% FLY ASH BY WEIGHT, 40LB/SY), QUANTITY TO BE PAID ONLY FOR FIELD LAB RECOMMENDED QUANTITY, COMPLETE IN PLACE | TON | 241.3 | \$203.02 | \$48,988.73 | \$240.00 | \$57,912.00 |
| 5. | COMMON ROADWAY EXCAVATION TO BE HAULED UTILIZING OFF-ROAD TRUCKS TO BE DESIGNATES STOCKPILE LOCATION WITH IN (0.5 MILE) OF THE PROJECT PLACED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY, INCCLUDES SITE PREP, ANY TEMPORARY TRAFFIC CONTROL, FLAGMEN, ETC., REQUIRED TO CROSS OR TRAVERSE EXISTING ROADWAYS COMPLETE IN PLACE | CY | 6,420 | \$8.60 | \$55,212.00 | \$7.00 | \$44,940.00 |
| 6. | WHEELCHAIR RAMPS AS PER DETAIL, INCLUDING TRUNCATED DOME PAVERS OR GROOVED DETECTIBLE AREA AS NOTED IN CONSTRUCTION PLAN SET, COMPLETE IN PLACE | EA | 2 | \$2,028.92 | \$4,057.84 | \$2,170.00 | \$4,340.00 |
| 7. | PERMANENT TRAFFIC CONTROL DEVICES, INCLUDING TRAFFIC BUTTONS, STREET SIGNS, STOP SIGNS, PAVEMENT STRIPPING, MARKERS, ETC., COMPLETE IN PLACE | LS | 1 | \$3,944.99 | \$3,944.99 | \$2,840.00 | \$2,840.00 |
| 8. | TYPE III BARRICADES, COMPLETE IN PLACE | EA | 2 | \$1,014.53 | \$2,029.06 | \$1,100.00 | \$2,200.00 |
| 9. | PAVING HEADER, COMPLETE IN PLACE | LF | 56 | \$22.68 | \$1,270.08 | \$16.50 | \$924.00 |

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CONSTRUCTION OF THE WATER, SANITARY SEWER AND DRAINAGE FACILITIES
 & PAVING AND APPURTENANCES TO SERVE VIA PRINCIPALE PARKWAY
 EAST MONTGOMERY COUNTY MUNICIPAL UTILITY DISTRICT NO. 5
 CITY OF HOUSTON, E.T.J., MONTGOMERY COUNTY, TEXAS
 MARCH 19, 2021
 LJA ENGINEERING, INC.
 A.CAROTHERS
 MARCH 19, 2021
 6969-1018A & 6967-1018A (9.2)

| ITEM | DESCRIPTION | UNIT | QTY | 1) C.E. BARKER, LTD. | | 2) TRIPLE B SERVICES, LLP | |
|--|---|------|-------|----------------------|-----------------------|---------------------------|-------------|
| | | | | UNIT COST | TOTAL COST | UNIT COST | TOTAL COST |
| 10. | INSTALLATION, MAINTENANCE AND REMOVAL OF STABILIZED CONSTRUCTION EXIT, SWMHCA SPECIFICATION NO. 4711, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE | EA | 1 | \$2,028.92 | \$2,028.92 | \$1,500.00 | \$1,500.00 |
| 11. | SELECT CLEARING AND GRUBBING, INCLUDES REMOVING ALL STUMPS AND ROOTS, EXCAVATION OF BURN PITS, BURNING OR CHIPPING OF CLEARING DEBRIS, HAULING OF ASHES OUTSIDE THE BOUNDARY OF THE DEVELOPMENT, CLEAN-OUT OF BURN PITS, AND BACKFILL OF BURN PITS TO 95% STANDARD PROCTOR DENSITY IN MAXIMUM 8" LIFTS, (ONLY AREAS AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE | AC | 1 | \$9,580.49 | \$9,580.49 | \$10,800.00 | \$10,800.00 |
| 12. | ADDITIONAL 6" LIME/FLY - ASH STABILIZED SUBGRADE TO BE USED FOR UNSTABLE SOIL CONDITIONS AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE | SY | 1,000 | \$2.68 | \$2,680.00 | \$6.25 | \$6,250.00 |
| 13. | ADDITIONAL TRU BLN LIME/FLY ASH MIXTURE FOR SUBGRADE PREPARATION (2% LIME BY WEIGHT, 10 LB/SY AND 8% FLY ASH BY WEIGHT, 40 LB/SY), TO BE USED FOR UNSTABLE SOIL CONDITIONS, (TO BE USED ONLY AS DIRECTED BY THE ENGINEER), COMPLETE IN PLACE | TON | 50 | \$197.39 | \$9,869.50 | \$240.00 | \$12,000.00 |
| 14. | TEMPORARY TRAFFIC CONTROL AS REQUIRED FOR CONSTRUCTION, INCLUDES BUTTONS, SIGNS, STRIPING, MARKERS, BARRELS, FLAGMEN AND ANY OTHER TRAFFIC CONTROL MEASURES REQUIRED, COMPLETE IN PLACE | LS | 1 | \$5,184.80 | \$5,184.80 | \$3,250.00 | \$3,250.00 |
| 15. | FULL CONSTRUCTION STAKING FOR PAVING CONSTRUCTION, COORDINATE WITH GBI SURVEY, JON BORDOVSKY, 281.499.4539, COMPLETE IN PLACE | LS | 1 | \$2,817.89 | \$2,817.89 | \$2,410.00 | \$2,410.00 |
| 16. | 4" SQUARE DOUBLE REFLECTORIZED TRAFFIC BUTTONS FOR FIRE HYDRANT LOCATION, COMPLETE IN PLACE | EA | 10 | \$10.29 | \$102.90 | \$10.50 | \$105.00 |
| SUBTOTAL VIA PRINCIPALE PARKWAY PHASE II PAVING ITEMS | | | | | \$616,618.50 | \$640,044.50 | |
| BID SUMMARY | | | | | | | |
| SUBTOTAL WATER ITEMS | | | | | \$188,937.41 | \$232,653.06 | |
| SUBTOTAL SANITARY SEWER ITEMS | | | | | \$73,378.34 | \$97,731.49 | |
| SUBTOTAL DRAINAGE FACILITIES ITEMS | | | | | \$314,943.24 | \$397,008.84 | |
| SUBTOTAL MISCELLANEOUS ITEMS | | | | | \$1,371.17 | \$2,495.00 | |
| SUBTOTAL VIA PRINCIPALE PARKWAY PHASE II PAVING ITEMS | | | | | \$616,618.50 | \$640,044.50 | |
| TOTAL AMOUNT BID | | | | | \$1,195,248.65 | \$1,369,932.89 | |